

Safe roads, reliable journeys, informed travellers

The Delivery Hub health, safety and environment Raising the bar 16 Working at height

Version I - September 2013

Contents

Objective State of the Control of th	I
Background	_
linimum requirement	_
Considerations	
egislation/guidance	_
Collective protection	_
Appendix 1: Example - motorway verge works edge protection / delineation matrix	_
Appendix 2: BB3MM – M6 S/B departure from perry bar work unit	_
Appendix 3: Sample harness permit	_ -

Objective

To help reduce the number of work at height related injury accidents by detailing minimum standards and promoting good practice for operations where work at height is unavoidable.

Background

Falls continue to be the biggest cause of fatal injury in Britain's workplaces, 51per cent of worker deaths in construction in 2011/12 resulting from a fall from height. On top of this, over 2,200 major injuries such as broken bones or fractured skulls are reported to Health and Safety Executive each year by the construction industry, the most common cause of major injuries are falls.

Minimum requirements

The work at height regulations requires the employer to carry out a risk assessment for all work at height and put in place arrangements for:

- eliminating or minimising risks from working at height
- safe systems of work for organising and performing work at height
- safe systems for selecting suitable work equipment to perform work at height
- safe systems for protecting people from the consequences of work at height

All work at height is considered a high risk activity. From the design stage through the construction process and into the maintenance phase of a project work at height must be eliminated where ever possible either through design, sequencing or other methods. A risk assessment and overall strategy for prevention of injury needs to be produced and reviewed at each phase of the project. Examples of this for work on motorway verges can be found in appendix one and two of this document. The following hierarchy of control should be adopted:

- avoid the risk by not working at height
- prevent falls by means of work equipment or other measures where work at height cannot be avoided
- minimise the distance and consequences of a fall should one
- occur by the use of work equipment or other measures
- give **collective measures** preference over personal protective measures.

Considerations

Examples of avoidance of working at height

The use of long-handled tools or other equipment can sometimes be used to safely carry out a task from ground level, eg a long handled brush or roller for painting and water-fed poles with brushes for window cleaning. Think about whether it is possible to design out the need to work at height, eg could new or replacement services, such as pipes or cables, be put at ground level?



Pre-slinging and bulk/pallet delivering of loads for mechanical handling off delivery vehicles will help prevent the requirement of access to the back of delivery vehicles

Prefabrication/assembly of structures at low level and the installation of systems such as gantry cable routes etc. prior to final installation at high level.

Minimise working at height on structures

http://assets.highways.gov.uk/specialist-information/major-projects-knowledge-sharing-a46/L16 rev 1 - No bridge work at height - Richard Jones.pdf

Emergency arrangements

Due to the very nature of work at height emergency arrangements are particularly important, links to several examples are given to help project teams determine the best approach for their own set of circumstances.

Escape from scaffold structures:

http://partoneclaims.highways.dft.gov.uk/minisite/ssrtoolkit/HS%20Toolkit/ Escape%20access%20within%20scaffold%20structures.pdf

Role call and evacuation routes:

The use of roll call/tally boards is particularly important where multiple access points or complex areas where in the event of an emergency numbers of persons missing or trapped may be vital to emergency services.

The posting of evacuation routes and accombly points can also prove vital in emergency situations.







Working adjacent to overhead power lines

Health and Safety Executive guidance on work near overhead power lines

www.hse.gov.uk/construction/safetytopics/overhead.htm

Exclusion zones

The creation of exclusion zones around and below the working areas

- Limitations due to inclement weather
- Medical limitations health assessments (for safety critical workers?)
- Highways Agency raising the bar standard B12 occupational health

http://www.highways.gov.uk/our-road-network/safety/major-projects-delivery-hubhealth-safety-action-group/

Legislation/guidance

Management of health and safety at work regulations 1999

Work at height regulations 2005 (amended) (WAHR)

INDG401: The Work at height regulations 2005 (as amended) a brief guide

INDG367: Inspecting fall arrest equipment made from webbing or rope (leaflet)

HSG150: Health and safety in construction (Health and Safety Executive books)

HSG33: Health and safety in roof work (Health and Safety Executive books)

CIS58: The selection and management of mobile elevating work platforms

Construction safety manual (CIP)

GE700 Construction site safety, section D 01-06 (CITB)

IPAF website: www.ipaf.org/en/

Highways Agency raising the bar standard occupational health B12

Health and Safety Executive guidance on use of ladders:

www.hse.gov.uk/falls/ladders.htm

Health and Safety Executive guidance work at height access equipment information toolkit: http://www.hse.gov.uk/falls/wait/index.htm

Collective protection

Edge protection warning systems

Minimum requirements

Guardrails, toe boards and similar barriers are provided wherever someone could suffer personal injury as a result of a fall.

The guardrails provided are:

- strong and rigid enough to resist any loads likely to be placed on them
- securely fixed to a structure capable of supporting them include:

a main guardrail at least 950mm high for temporary structures and 1m for permanent structures

a toe board of at least 150mm high

additional intermediate guardrails positioned so that the unprotected gaps do not exceed 470mm

Barriers other than guardrails may be used provided that they offer an equivalent standard of protection.



Desirable

Early installation of edge protection

http://partoneclaims.highways.dft.gov.uk/minisite/ssrtoolkit/HS%20Toolkit/

Fixed Scaffold

Minimum requirements

- Scaffolds are to be designed, erected, altered and dismantled only by CISRS trained scaffolders with competence specific to the scaffold type and to the required level. A competent person shall also supervise the work
- Provision of suitable access to install, maintain and dismantle scaffolds must be considered at the design stage and form part of the scaffolding process.
- Scaffolders to work to NASC latest guidance SG4:10.
- Scaffolders always adopt fall prevention measures during erection and dismantling; this normally means wearing a safety harness
- System scaffolds are installed in accordance with manufacturers' instructions.

 The instruction manual is made available on site
- Scaffolds are based on a firm, level foundation that is capable of supporting the weight of the scaffold and any imposed loads
- The scaffold is adequately braced and tied into a permanent structure or otherwise stabilised. If a tie is removed to allow work to proceed, an equivalent tie is provided nearby to maintain stability.
- Where scaffolds need to take heavy loads or are to be sheeted, this is brought to the attention of the provider; a special design may be required
- Platforms are fully boarded and wide enough for the work and for access, with boards that are properly supported and not overhanging excessively. (The recommended overhang for a 38mm thick board is 50mm minimum and 150mm maximum)
- Tower staircase providing access to all working platforms unless restricted by space available.

- All openings are fitted with gates
- Checks are made before use, after substantial alteration and where adversely affected by the weather
- Scaffolds to be tagged/labelled with person responsible for erection, latest inspection dates and design loadingsInspections are determined by risk assessment, but should be at least weekly and records available on site









Desirable

Anti slip tread on steps

http://partoneclaims.highways.dft.gov.uk/minisite/ssrtoolkit/HS%20Toolkit/Anti%20 Slip%20Tread.pdf

Netting

Minimum requirements

Safety nets are usefully employed to reduce potential falls and to minimise their effects. They offer collective, passive safety as they protect everyone working within their boundary without requiring those workers to act to be protected. All safety nets must meet the specific requirements and testing methods given in BS EN 1263-1.

All safety nets must be fitted in accordance with manufacturer's instructions and the safety requirements for positioning in accordance with BS EN 1263-2.

Safety nets overlaid with a fine mesh debris cover can also protect those who have to work or pass below. An enhanced inspection and maintenance regime must be put in place if debris netting is utilised with any safety net. This must include measures to stop works if the build up of debris may injure a faller or damage the safety netting/supports.

Adequate clearance must be allowed below the net to allow it to function properly.

Ladders are not recommended for erection of netting.



Desirable

A fully designed netting system with the following:

- inspection and maintenance regime
- emergency rescue plan and a
- program of emergency drills.

Planning%20early%20installation%20of%20edge%20protection%20at%20 permanent%20works.pdf

Air mats

Air mats are an alternative to netting where but should only be used where falls of less than 2 metres are possible. This type of protection should not be used as a first choice as alternative methods which prevent falls should be utilised first.

If air mats are utilised the must be installed as per manufacturer's instructions and checked for compliance to ensure they will provide the protection specified.

Consideration should be given prior to use of the risk of a falling person striking objects during a potential fall such as intermediate walls or adjacent objects/structures.





Mobile elevated work platforms MEWPS

Minimum requirements

MEWPS are classified as lifting equipment and as such are covered by the lifting operations and lift equipment regulations 1998 (LOLER) regulation 8 requires lifts to be properly planned by a competent person.

For the purposes of this standard a competent person with regard to lifting is the

holder of a CPCS (blue) competent person card endorsed with category A62. Appointed persons-lifting operations or similar.

Hazards/considerations that must be taken into account during planning operations for MEWPs are given in but not limited to the listed below:

- Alternative means of undertaking the work by safer method
- Work to be undertaken from the platform
- Overturning
- Falls of persons or materials
- Collision
- Height to be reached
- Route to work site including travelling in a raised position
- Entrapment of operator or basket against structures
- Ground conditions uneven/soft ground conditions, excavations or subsurface chambers such as manhole/duct runs etc.
- Temporary structures/covers
- Segregation from passing traffic
- Protrusion of MEWP into live road or other transport route
- Weather conditions High winds- wind speed limitations etc.
- Overhead lines
- Power cables
- Use of and position of outriggers

- Emergency/rescue procedure
- Supervision of the works

The risk of falling from a MEWP is from sudden movements caused by an impact, ground movement, failure of a stability critical part, or overreaching. The wearing of appropriate fall protection equipment can provide protection against the residual risk of falling, or being thrown out of the carrier. Guidance on appropriate Fall Protection in Mobile Elevating Work Platforms can be found at http://www.hse.gov.uk/pubns/misc614.pdf and www.ipaf.org/fileadmin/user_upload/documents/en/H10812.pdf

MEWPs have a thorough examination and inspection by a competent person at least once every 6 months. They are also inspected and maintained in accordance with Manufacturers instructions.

All MEWPS used on projects covered by this standard must meet the requirements of BS EN 280 standard (mobile elevating work platforms) BS8460 Safe use of MEWPS Code of practice must also be used to assist in the selection, hiring, positioning maintenance and thorough examination of MEWPS. The code of practice should also be used for guidance on the safe use of MEWPS selection/training of operators and other personnel.

The safe working load must be clearly marked at the base of the machine and on the working platform. The load specified must not be exceeded. Care needs to be taken to reduce the build up of debris on the platform, and any materials being lowered into the platform area.

Telescopic and articulating machines are normally designed to carry operators and tools only, while scissor lifts may have the capability to carry some materials. Manufacturer's instructions must be followed.

All MEWP controls must be suitably shrouded or fitted with a cut off devise to prevent inadvertent operation of the control panel.

All operators of MEWPS must be trained and competent; recognised training accepted is CPCS and IPAF PAL + it is important that the correct category of training for operator is matched to the equipment to be used. Checks on the

category/training for each type of MEWP can be found at http://www.citb.co.uk/cards-testing/construction-plant-competence-scheme-cpcs/cpcs-downloads/ and http://www.citb.co.uk/cards-testing/construction-plant-competence-scheme-cpcs/cpcs-downloads/ and www.ipaf.org/en/training/pal-card/

Before using a MEWP the operator and another responsible person on site (who is not working on the platform) must know how to use the emergency controls.

Persons should not leave the working platform whilst in an elevated position, nor should materials be transferred, unless the risk assessment has addressed this requirement and the full control measures are in place.

Lone working is prohibited.

The minimum requirements of Highways Agency raising the bar standard B1.08 plant and equipment-MEWPS must also be adhered with http://www.highways.gov.uk/our-road-network/safety/major-projects-delivery-hub-health-safety-action-group/

Desirable

Best practice guidance for MEWPs 'is available via this link to the IPAF website: www.ipaf.org/en/ also within documents noted in the reference section of this guidance.

Managers and supervisors responsible for MEWP operations are to have awareness training covering the management of MEWPS or similar eg IPAF managers for MEWPS

Best practice guidance for MEWPS Avoiding trapping/crushing injuries www.ipaf.org/en/publications/avoiding-trappingcrushing-injuries/

The use of "IPAF Trained" helmet stickers for all scissor lift and articulated boom operators.

These are issued to all IPAF certified operators with use of MEWPs prohibited if not displayed by the user.

Mobile access towers

Minimum requirements

When a scaffold tower is to be used:

- It is erected, altered and dismantled only by PASMA trained personnel, or CISRS trained scaffolders with type specific training.
- Mobile access towers must be inspected by a competent person.
 - after assembly in any position;
 - after any event liable to have affected its stability; and
 - at intervals not exceeding seven days.
 - towers to be tagged/labelled with the name of the person
 - responsible for erection, latest inspection dates
 - register of inspections held on site.

New inspection reports are not required every time a mobile access tower is moved to a new location on the same site. However, if guard rails or other components have to be removed to enable the tower to be moved past an obstruction, then a preuse check should be undertaken by a trained and competent person.

- The manufacturer's instructions for erection, use and dismantling are followed. An instruction manual is made available on site if the scaffold has been hired, the hirer ought to provide this information
- The tower is kept vertical with the legs resting properly on firm, level ground
- Wheels and outriggers are locked in position; base plates provide greater stability if the tower doesn't have to be moved
- A safe means is provided to get to and from the platform, for example internal ladders. www.hse.gov.uk/pubns/cis10.pdf

- Proper edge protection (guardrails and toe boards) is provided
- The tower is tied rigidly to the structure it is serving, or other additional support is provided if:
 - the tower is sheeted
 - it is likely to be exposed to strong winds
 - it is used for water jetting or grit blasting
 - heavy materials are lifted up the outside or
 - the tower base is too small to ensure stability for the height of the platform

When moving the tower:

- check for power lines or overhead obstructions
- check that there are no holes or dips in the ground
- ensure that people or materials do not remain on the platform.

Ladders and steps

Minimum requirements

The use of ladders, whether to perform work at height or as a means of access or egress, is subject to risk assessment. The assessment is appropriate to the risks involved, but even for simple tasks, doing a risk assessment ensure that the risks are recorded. The assessment covers such factors as the height to be negotiated, the site conditions, the duration and extent of the work and the frequency of access. However, when considering the use of ladders it is important to remember that:

- Ladders are used as a place of work only when other, potentially safer, means such as tower scaffolds are not reasonably practicable
- Ladders are used for access only when provision of a staircase is not reasonably practicable
- A register to be held of all podium/steps/ladders detailing unique identification numbers, type, date and result of inspection along with date of next routine inspection.

In practice, ladders are used as a workplace only for short-term work under the following conditions:

- The work only requires one hand to be used.
- The work can be reached without stretching
- The ladder can be fixed to prevent slipping
- A good handhold is available

Whatever the use, the ladder needs to be strong enough for the job and in good condition ie the stiles not damaged, buckled or warped, no rungs are cracked or missing and any safety feet are not missing. In use:

- The ladder is set at an angle to minimise the risk of slipping outwards ie one out for every four up
- The top of the ladder rests against a solid surface.
- Both feet are on a firm footing and cannot slip
- The ladder is fixed at the top or footed at the base
- The ladder extends at least one metre above any landing place unless some other adequate handhold is available
- Suitable landings are provided where ladders are used in a run measuring a vertical distance of nine metres or more

Desirable

- Permit to use steps/ladder issued following completion of specific task based risk assessment
- All podium/steps/ladders that are available for use to be tagged/labelled with unique Identification numbers, date of last and next inspection and the name of person who completed the last inspection

• The use of podiums steps to be encouraged over the use of just ladders





• The use of fall arrest systems with ladders http://partoneclaims.highways.dft.gov. uk/minisite/ssrtoolkit/HS%20Toolkit/Fall%20arrest%20for%20ladders.pdf

Lifting operations – man riding

Minimum requirements

Operations that involve the lifting of persons will usually be undertaken by work equipment specifically designed for that purpose eg passenger hoists or MEWPs.

Man riding on cranes is permitted only for work when another safe means of access cannot be provided and is limited to work of short duration as far as possible.

The use of excavators for man riding is prohibited.

Man riding is classed as a complex lifting operation. It therefore requires a lift plan approved by the appointed person lifting (APL.)

Any crane used for man riding must be adequate and suitable for the task. In addition:

- is subject to 6 monthly thorough examination
- any free-fall capability must be locked-out a hydraulic crane is preferable
- is equipped with appropriate devices such as 'deadman' controls, safety hook on block, hoisting limiter, lowering limiter, rated capacity indicator and rated capacity limiter
- hoist rope at least 8mm diameter
- the SWL at the required radius is at least twice the weight of the carrier plus its contents
- work stops if wind speed exceeds 7m/s (approx. 15.6mph)
- no lifts may be made with any other hoist line on the crane during man riding operations
- the crane may not travel

The use of forklift trucks or telescopic handlers for man riding duties is only ever considered in exceptional circumstances. A failsafe method of communication must be put in place and fully understood by the machine operator and those within the basket.

Carriers used for man riding are subject to specific requirements. These include:

- a notice attached to the carrier stating 'man riding duties only'
- a notice stating the SWL and maximum number of passengers
- secure attachment to the crane by means of a shackle or latched hook

- daily recorded inspection by a competent person
- anti-spin arrangements such as the use of multiple-fall ropes or swivel hook block and the use of tail ropes where appropriate
- doors or gates that open inwards fitted with a safety catch to prevent inadvertent opening
- edge protection sufficiently strong to prevent people or equipment falling through
- provision for safety harnesses to be used and anchored

Man riding is appropriate mainly as a means of access. Where work has to be done from the man rider, then safety harnesses are worn except for work over water, where lifejackets are worn, not harnesses.

The safe system of work for man riding must include arrangements for rescue in the event of a failure.

Delivery vehicles

Minimum requirements


The main aim of all tasks associated with work at height whilst loading and unloading delivery vehicles should be reviewed to see if they can be fully or partially completed at ground level.

The use of loading/sheeting bays or loading docks either permanent or temporary structures must be the first considered for all deliveries, the use of tail lift vehicles (with edge/side protection) should also be considered.

Where personnel are required to access open sided vehicles where there is the potential of a fall from height edge protection should be considered as the first level of control to prevent falls from height.

Where access is required to a delivery vehicle and there is the potential for a fall from height the following are minimum requirements:

Provision of safe access and egress, either by fixed ladder or purpose designed hand/foot holds.









Examples of ladder access flat bed vehicles

http://partoneclaims.highways.dft.gov.uk/minisite/ssrtoolkit/HS%20Toolkit/Ladder%20access%20to%20flat%20bed%20lorries.pdf

Protection to prevent a fall

The uses of proprietary systems are preferable where permanent or semi permanent loading docks cannot be utilised.

http://partoneclaims.highways.dft.gov.uk/minisite/ssrtoolkit/HS%20Toolkit/Edge%20 protection%20system%20for%20flat%20bed%20lorries.pdf

Example of side rails installed on vehicles



Where the risk of a fall cannot be eliminated, use work equipment to minimise the distance of a fall

Desirable

- All loads to be designed to be removable from vehicles without the need to work at height. eg palletised loads, pre-slung loads etc.
- All aggregate/surfacing delivery vehicles fitted with automatic sheeting and automatic tailgates
- Construction plant hire-association best practice guide work at height whilst loading/unloading transport CPA 0902 www.cpa.uk.net/p/Safety-Leaflets/

Individual protection

Harnesses

Minimum requirements

In some circumstances it is not reasonably practicable to provide physical measures to prevent a person falling. In such cases, a full body harness, suitably anchored and incorporating some form of energy absorber may be the only precaution available. This at least ensures that if a fall occurs, it is safely arrested.

The safe performance of a safety harness depends completely on a suitable anchorage being provided. The adequacy of the anchorage point, including the ability of the supporting structure to carry the loads, is verified by calculation or by testing.

Anchorages are installed as high as possible, preferably above the user and never below foot level. Retractable type fall arrestors are anchored at chest height or above.


Adequate clearance is required in order for a fall arrest system to function. When establishing fall arrest systems consideration must also be given to possible pendulum effect on the system users particularly when energy absorber/arrester devices are utilised.

Training in the use of safety harnesses should align with BS8454 Code of practice for the delivery of training and education for work at height and rescue and as a minimum include the following:

- Introduction to working at height and the need for fall protection equipment (PFPE).
- Height safety legislation, standards and guidelines.
- Principles of personal fall protection systems for travel restraint, work positioning and fall arrest.
- Pre-use inspection procedures.
- Equipment connection and adjustment.
- Practical application, problem solving and use of workplace PFPE.
- An appreciation of emergency actions, rescue incl. suspension trauma.

Desirable

Control of harness usage, none regular harness users to be issued with a harness permit (see appendix 3)



Visual examples of varying topographical conditions



Generally flat



Slope no steeper than 1:2 with no hazards or obstructions



Slope no steeper than 1:2 with hazards or obstructions

Visual examples of varying topographical conditions



Slope no steeper than 1:2 with hazards or obstructions



Slopes steeper than 1:2



Shear/vertical drop eg wing wall / helical pile platform

Types of protection



Edge delineation system (eg cones and rope)



Free standing fence system (eg pedestrian guardrail)



Fixed edge protection system (eg scaffold tube and fitting / ultraguard

	TARCET	No. Sheet No. of 1 2	Risk Asses This Risk Assessment should be accompanied by a Point of Work Assessment specific location and completed on the day/shift by the person leading the	relating to the
Part 1 – Risk Assessm			Part 4 – Additional Safety Information Details of related safety information; i.e. further documents required for the activity. All Risk Assessments must be written	Likelihood of incident or injury
Title Working at he Assessed by Rob Nybo Approved	Ody Contract B	B3MM Phase 3 lotorway N/B & S/B	This assessment outlines the areas of risk (risk zones) for works on a gradient slope or in proximity to a gradient slope, within the longitudinal working area of Birmingham Box Phase 3	tajor R R A G G Innor R A G G G
Part 2 – Review History Date established Review 1 (Date) Review 2 (Date)	updated document must be communic	mum, be reviewed annually. Once reviewed the ated to all those who use it. Once a document has noe it was originally created) it must be rewritten. Signature	Temporary works edge protection must be installed by competent people using fall restraint systems. Anchored to either safety barrier, fence posts, steel or concrete structures. Note that Zone 3 (below) extends into the verge by 500mm Contact the IMS Team for further guid	- Re-assess rol Measures ivity
Part 3 – Hazards & Ris. What might go wrong? (Hazard)	ks Outcome or consequence (Risk)	Who could be affected? Select all relevant options. Specify "other" in the Additional Safety Information box. Rating Matrix.	Proprior. How we will stop this activity from going wrong	This is how safe we have made it! Residual Risk. This Risk Rating is determined using the Risk Rating
ZONE 4 Flat area, between Slope and Boundary Fence	Not working at height	X X X X X X X X X X X X X X X X X X X	No edge protection necessary as not categorised as work at height. If any works are carried out within this location a task specific risk assessment will be carried out.	Matrix. Note and the second of the second o
ZONE 3 Slopes no steeper than 1:2 No hazards or obstructions	Not working at height	X X X X X X X X X X Water Amber Ambe	The most common type of gradient within motorway networks is approximately 1:2. Any work within this type of gradient will be covered by a separate risk assessment, factoring inclement weather conditions.	X Amber Green
ZONE 3 Slopes no steeper than 1:2 with hazards & obstructions	Obstruction could be a tree Hazard could be a river.	X X X X X X X X X X X X X X X X X X X	Hazards & Obstructions will need to be protected by edge protection systems, installed by authorised competent people to a temporary works approved drawing, the system will undergo a weekly check by temporary works approved checkers.	X Amber X
ZONE 3 Slopes steeper than 1:2	Working at height & falling objects	X X X X X X X X X X X X X X X X X X X	Protected by edge protection systems, installed by authorised competent people to a temporary works approved drawing, the system will undergo a weekly check by temporary works approved checkers.	Red Amber Green
ZONE 3 Sheer drop, wing wall, helical platform	Working at height & falling objects	X X X X X X X X X X X X X X X X X X X	Frotected by edge protection systems, installed by authorised competent people to a temporary works approved drawing, the system will undergo a weekly check by temporary works approved checkers Note: Helical pile platform may be protected by handrail secured to fence posts	X Amber

© Carillion 2008 carillionplc.com

	TARGET	KAH Shee	et No. of	Risk Assessment — (continuation of the Continuation of the Continu	On sheet) nt relating to the the work activity
Part 3 – Hazards & Ris What might go wrong? (Hazard)	sks (continued) Outcome or consequence (Risk)	Who could be affected? Select all relevant options. Specify "other" in the Additional Safety Information box.	To what extent? Select only one option. This Risk Rating is determined using the Risk Rating Matrix.	How we will stop this activity from going wrong (Control Measures) Control measures should always seek to eliminate the hazards that are described.	This is how safe we have made it! Residual Risk. This Risk Rating is determined using the Risk Rating
ZONE 2 Verge Area	Potentially working at height subject to actual task and proximity to slope edge	X X X X X X X (Specify)	X Red Amber CGreen	Hazards & Obstructions will need to be protected by edge protection systems, installed by authorised competent people to a temporary works approved drawing, the system will undergo a weekly check by temporary works approved checkers. Subject to task, delineation may be acceptable.	Matrix.
ZONE 1 Hard shoulder	Not working at height	X X X X X X X X Specify)	X Red Green	No edge protection necessary as not categorised as work at height. If any works are carried out within this location a task specific risk assessment will be carried out.	Red Amber X
		Employeex Public Client Other (Specify)	Red Amber Green). 	Red Amber Green
		Employee Public Client Other (Specify)	Red Amber Green		Red Amber Green
		Employee Public Client Other (Specify)	Red Amber Green		Red Amber Green
		Employee Public Client Other (Specify)	Red Amber Green		Red Amber Green
		Employee Public Client Client (Specify)	Red Amber Green	2.	Red Amber Green
		Employee Public Client Client (Specify)	Green 13		Red Amber Green
© Carillion 2008 carillionplc.cc	om			Carillion Risk Asset	ssment Document – Version 1.0

			ARGET	Ref. No	AH		Shee 1	t No.	2			Risk Assess This Risk Assessment should be accompanied by a Point of Work Assessment r specific location and completed on the day/shift by the person leading the	elatii	ng to	the
Part 1 – Risk									_			rt 4 – Additional Safety Information ils of related safety information; i.e. further documents required for the activity. All Risk Assessments must be written		ikelihoo ident or	
		orway inclin	es no ste					truct	ions			is document details the controls which must be in	nevitable	Probable	Remote
Assessed by	Rob Nybo	dy	Contract	BB3I	MM P	hase	3				•	ace for working on inclines no steeper than 1.2 with structions on slopes such as trees & header walls		R	A G
Approved b			Site	Moto	rway	N/B	& S/	В				Irvey needs to be carried out in advance identifying		A	G G
Part 2 – Revi		All Risk Assessmupdated document been reviewed tw	nt must be comr	municated to	all those	who use	it. Once	a docum	ent has		all	Obstructions. Control measures are to be. 2 Lo Once a final Risk Rating has been established the rules set out below must be applied.	ow R	A	3 G
established	16/07/13	Reviewer	()-		Signati		,					Red Do not proceed – R	Re-asse	ss	
Review 1 (Date)												A Amber Review the Control G Green Proceed with activi		ires	
Review 2 (Date)												Contact the IMS Team for further guidar			
What might go w (Hazard) Installation of delineation of protection sys	wrong? of or edge	Outcome or con (Risk) Falling object people from	ts and	affe Sele Spec	ct all relevant of the street	ant optio		Select This R determ	only one isk Ratin, inned usir Matrix.	optior g is	n. Risk	How we will stop this activity from going wrong (Control Measures) Control measures should always seek to eliminate the hazards that are		re ma Risk. Th is dete he Risk	de it! nis Risk ermined
Ducting, Cha and Cabinet Construction		Falling object people from		Employee	Public	Client	Other	Red	Amber	Green] 2	2. No working unless fixed edge protection system has been installed and checked isolating the obstruction.	Red	Amber	Green
the Verge				X			X		X	L	ٍل				X
Works on bat (e.g. steps / drains)		Falling object people from		Employee	Public	Client	Other Operator	Red	Amber	Green	_ `	No working unless fixed edge protection system has been installed and checked isolating the obstruction.	Red	Amber	Green
urairis)				X			Х	Х	L	L	╛				X
Environments Screen Post Installation		Falling object people from		Employee	Public	Client	Other Operator	Red	Amber	Green	4	No working unless fixed edge protection system has been installed and checked isolating the obstruction.	Red	Amber	Green
				X			Х	Х	L	L	┚				X
Formwork (B Narrow Vergo Shutter – (ins	je 📗	Falling object people from		Employee	Public	Client	Other (Specify)	Red	Amber	Green	5	No working unless fixed edge protection system has been installed and checked isolating the obstruction.	Red	Amber	Green
remove	stall /			X			Х	X		L	J				X

	TARGET	ef. No.	Sheet 2			Risk Assessment – (continuation This Risk Assessment should be accompanied by a Point of Work Assessment	on s	she	et)
	ARO	WAH				specific location and completed on the day/shift by the person leading the	he wo	rk act	tivity
Part 3 – Hazards & Risi What might go wrong? (Hazard)	ks (continued) Outcome or consequence (Risk)	Who could be affected? Select all relevant opt Specify "other" in the Safety Information box	Additional	To what external Select only one op This Risk Rating is determined using the Rating Matrix.	otion.	How we will stop this activity from going wrong (Control Measures) Control measures should always seek to eliminate the hazards that are described.	we ha	is hove ave ma al Risk. T ing is det g the Risl	ade it! This Risk termined isk Rating
Formwork (Back of Narrow Verge Shutter – (install / remove)	Falling objects and people from height.	Employee Client	X Other (Specify)	X Red	Green	No working unless fixed edge protection system has been installed and checked isolating the obstruction.	Red	Amber	Matrix.
Hand works - Resoiling / finishing works	Falling objects and people from height.	X Employee	X Specify)	X Red	Green	No working unless fixed edge protection system has been installed and checked isolating the obstruction	Red	Amber	X
Environmental Screen Panel Installation	Falling objects and people from height	X Employeex	X Other (Specify)	X Red	Green	No working unless fixed edge protection system has been installed and checked isolating the obstruction.	Red	Amber	Z Green
Cable Installation Works (Works within verge accessed from (hard shoulder	Falling objects and people from height	Employee X	X (Specify)	X Red	Green	Edge delineation of pegs & orange rope to demarcate edge of slope.	Red	Amber	X
		Employee Public Client	Other (Specify)	Red Amber	10 Green		Red	Amber	Green
		Employee Public Clent	Other (Specify)	Red	Green 11		Red	Amber	Green
		Employee Public Client	Other (Specify)	Red Amber	Oreen 2	2.	Red	Amber	Green
		Employee Public Cilent	Other (Specify)	Red Amber	13 Ueeu		Red	Amber	Green
© Carillion 2008 carillion ptc.com						Carillion Risk Asses	sment Po	cument –	Version 1

© Carillion 2008

carillionplc.com

Appendix 1: Example - motorway verge works edge protection / delineation matrix

	TARGET	MAH Sheet I	No. of	Risk Assess This Risk Assessment should be accompanied by a Point of Work Assessment r specific location and completed on the day/shift by the person leading the	relatin	g to the
Part 1 – Risk Assessm				Part 4 – Additional Safety Information Details of related safety information; i.e. further documents required for the activity. Risk Rating Matrix		kelihood of dent or injury
Title Working on M	otorway inclines stee	per than 1.2		This document explains the controls for working on gradients atomory than 1.2	nevitable	robable ossible
Assessed by Rob Nybo	ody Contract	BB3MM Phase 3		Fixed edge protection system will be installed by be determined using the matrix set out on the right.	ior R	R A G
Approved b	Site	Motorway N/B & S/B		competent people defined by foremen with skill knowledge & experience to carry out such tasks Fixed odgs protection system is classed as temporary.	us R	A G G
Part 2 – Review Histor	All Risk Assessments must, as a m updated document must be commu	nimum, be reviewed annually. Once revi		works, drawing will be produced and checks carried Once a final Risk Rating has been established the rules set out	ow R	A G G
Date 16/07/13 established	been reviewed twice (or three years Reviewer	since it was originally created) it must b Signature	e rewritten.	out by people named on the temporary works check register.	?e-asses	
Review 1 (Date)				Edge Delineation will consist of Inserted pegs with	l Measure	
Review 2 (Date)				Contact the IMS Team for further guidan		
Part 3 – Hazards & Ris What might go wrong? (Hazard)	ks Outcome or consequence (Risk)	affected? Select all relevant options. T Specify "other" in the Additional	Fo what extenselect only one opt This Risk Rating is letermined using the Rating Matrix.	tion. How we will stop this activity from going wrong Re (Control Measures) Control measures should always seek to eliminate the hazards that are	/e have esidual Ri Rating is	how safe e made it! isk. This Risk s determined e Risk Rating
Installation of delineation or edge protection system	Falling objects and people from height.	Employee M	X Amber	Individuals installing fixed edge protection system using an harness & lanyard (inertia reel) fixed to safety fencing, fencing posts, concrete or steel structures. Ensure fall arrest system is checked daily prior to using and report any defects if applicable. Exclusion zones implemented	Red	Matrix. Output Both B
Ducting, Chambers and Cabinet Construction within	Falling objects and people from height.	Employee Client Client Coperator	Red Amber	Edge delineation of pegs & orange rope to demarcate edge of slope.	Red	Amber Green
the Verge Works on batters	Falling objects and			3. Individuals installing fixed adaptive stips quatern using an horness 0		
(e.g. steps / ducts /	people from height.	Employ Public Client Other	Red	Individuals installing fixed edge protection system using an harness & lanyard (inertia reel) fixed to safety fencing, fencing posts, concrete or	Red	Amber
drains)		X	X	steel structures. Ensure fall arrest system is checked daily prior to using and report any defects if applicable. Exclusion zones implemented		X
Environmental Screen Post Installation	Falling objects and people from height.	Employee Public Clent Other		Individuals installing fixed edge protection system using an harness & lanyard (inertia reel) fixed to safety fencing, fencing posts, concrete or steel structures. Ensure fall arrest system is checked daily prior to using	Red	Amber
		X	х	and report any defects if applicable. Exclusion zones implemented		Х
Formwork (Back of Narrow Verge Shutter - install /	Falling objects and people from height.	Employee Public Client Client (Specify)		No working unless fixed edge protection system has been installed and checked.	Red	Amber Green
remove)		X	х			X

Carillion Risk Assessment Document - Version 1.0

	TARGET	WAH	Shee 2	t No. of		Risk Assessment – (continuation This Risk Assessment should be accompanied by a Point of Work Assessment specific location and completed on the day/shift by the person leading to	it relat	ting to	the :
Part 3 – Hazards & Riss What might go wrong? (Hazard)	ks (continued) Outcome or consequence (Risk)	Who could be affected? Select all relevant of Specify "other" in the Safety Information b	Additional	To what ex Select only one This Risk Ratin determined usi Rating Matrix.	e option. ng is	How we will stop this activity from going wrong (Control Measures) Control measures should always seek to eliminate the hazards that are described.	we ha	is how ave ma al Risk. Thing is dete g the Risk	his Risk ermined k Rating
Formwork (Back of Narrow Verge Shutter - install / remove)	Falling objects and people from height	Employee X	X Other (Specify)	X Red Amber	Green	No working unless fixed edge protection system has been installed and checked.	Red	Amber	Matrix.
Hand works - Resoiling / finishing works	Falling objects and people from height.	Employee Vilent	X Other (Specify)	X Red	Green	Individuals installing fixed edge protection system using an harness & lanyard (inertia reel) fixed to safety fencing, fencing posts, concrete or steel structures. Ensure fall arrest system is checked daily prior to using and report any defects if applicable. Exclusion zones implemented	Red	Amber	X
Environmental Screen Panel Installation	. Falling objects and people from height.	X Employees	X Other (Specify)	X Red	Green	Individuals installing fixed edge protection system using an harness & lanyard (inertia reel) fixed to safety fencing, fencing posts, concrete or steel structures. Ensure fall arrest system is checked daily prior to using and report any defects if applicable. Exclusion zones implemented	Red	Amber	X Green
Cable Installation Works (Works within verge accessed from hard shoulder)	Falling objects and people from height	X Employee	X Other (Specify)	X Red	Green	Edge delineation of pegs & orange rope to demarcate edge of slope.	Red	Amber	X
,		Employee Public Client	Other (Specify)	Red Amber	Green Green	A	Red	Amber	Green
		Employee Public Cilent	Other (Specify)	Red	110 Ueeu O		Red	Amber	Green
		Employee Public Client	Other (Specify)	Red	Oreen 0	2.	Red	Amber	Green
		Employee Public Cilent	Other (Specify)	Red	0.00 J	<u> </u>	Red	Amber	Green
© Carillion 2008 carillionplc.com						Carillion Risk Asses	sment Do	cument - \	Version 1 (

TARGET	No. Sheet No. of 1 2	Risk Asses This Risk Assessment should be accompanied by a Point of Work Assessment specific location and completed on the day/shift by the person leading the	t relating to the
Part 1 – Risk Assessment Details Title Working on Motorway inclines with	vertical drop	Part 4 – Additional Safety Information Details of related safety information; i.e. further documents required for the activity. A sheer drop is defined as any area with a leading Risk Rating Matrix All Risk Assessments must be written by a Competent Person	Likelihood of incident or injury 1
	BB3MM Phase 3 Notorway N/B & S/B	edge Fixed edge protection system will be installed by competent people defined by foremen with skill The Risk Rating should be determined using the matrix set out on the right. Hazards should be seemed and right. Hazards should be sees seemed before and after.	Major R R A G wrious R R A G Minor R A G
updated document must be communi	mum, be reviewed annually. Once reviewed the cated to all those who use it. Once a document has ince it was originally created) it must be rewritten. Signature	Fixed edge protection system is classed as temporary works, drawing will be produced and checks carried out by people named on the temporary works check register. Red Do not proceed A Amber Review the Cont Green Proceed with act Contact the IMS Team for further guited.	– Re-assess trol Measures tivity
Part 3 – Hazards & Risks What might go wrong? Outcome or consequence (Risk)	Who could be affected? Select all relevant options. Specify "other" in the Additional Safety Information box. Rating Matrix.	tion. How we will stop this activity from going wrong	This is how safe we have made it! Residual Risk. This Risk Rating is determined using the Risk Rating
Installation of delineation or edge protection system Falling objects and people from height.	X Employee Client Collect Amber Amber	Individuals installing fixed edge protection system using an harness & lanyard (inertia reel) fixed to safety fencing, fencing posts, concrete or steel structures. Ensure fall arrest system is checked daily prior to using and report any defects if applicable. Exclusion zones implemented	Matrix. Watrix. X
Ducting, Chambers and Cabinet Construction within	X X X X X X X Y X Y Y Y Y Y Y Y Y Y Y Y	No working unless fixed edge protection system has been installed and checked. Exclusion zones implemented if applicable.	X Amber Red
Environmental Screen Post people from height.	X X X X X Amber	Individuals installing fixed edge protection system using an harness & lanyard (inertia reel) fixed to safety fencing, fencing posts, concrete or steel structures. Ensure fall arrest system is checked daily prior to using and report any defects if applicable. System for slipping over edge	X Amber Scen
Formwork (Back of Narrow Verge Shutter - install / remove) Falling objects and people from height.	X X X X X X Amber	No working unless fixed edge protection system has been installed and checked. Exclusion zones implemented if applicable.	X Green
Formwork (Back of Narrow Verge Shutter - install / remove) Falling objects and people from height.	X X X X X X X X X X X X X X X X X X X	No working unless fixed edge protection system has been installed and checked. Exclusion zones implemented if applicable	X Amber

	TARGET	ef. No. Shee 2	t No. of	Risk Assessment — (continuate This Risk Assessment should be accompanied by a Point of Work Assessment specific location and completed on the day/shift by the person leading	ent relating to the
Part 3 – Hazards & Ris What might go wrong? ^(Hazard)	oks (continued) Outcome or consequence (Risk)	Who could be affected? Select all relevant options. Specify "other" in the Additional Safety Information box.	To what extent? Select only one option. This Risk Rating is determined using the Risk Rating Matrix.	How we will stop this activity from going wrong (Control Measures) Control measures should always seek to eliminate the hazards that are described.	This is how safe we have made it! Residual Risk. This Risk Rating is determined using the Risk Rating
Concrete (Narrow Verge Works)	Falling objects and people from height.	X Employee Client Client (Specify)	X Red Amber 9	Individuals installing fixed edge protection system using an harness & lanyard (inertia reel) fixed to safety fencing, fencing posts, concrete or steel structures. Ensure fall arrest system is checked daily prior to using and report any defects if applicable. System for slipping over edge	Matrix. Page 4 Bag 5 Ba
Hand works - Re- soiling / finishing works	Falling objects and people from height.	X Employee (Specify)	X Red Amber 2	No working unless fixed edge protection system has been installed and checked. Exclusion zones implemented if applicable.	X Amber
Environmental Screen Panel Installation	Falling objects and people from height.	Employeex Client Client	X Amber Green	No working unless fixed edge protection system has been installed and checked. Exclusion zones implemented if applicable.	X Green
Cable Installation Works (Works within verge accessed from hard shoulder)	Falling objects and people from height.	Employee Client Client Client Client Client	X Red Amber 6	Works are only isolated at Helical Pile platform locations. No working unless fixed edge protection system has been installed and checked	X Green
		Employee Public Client Other (Specify)	Red Amber Green		Red Amber
		Employee Public Client Other	Red Amber 111		Red Amber Green
		Employee Public Client (Specify)	Red Amber Green		Red Amber Green
		Employee Cilent Coner (Specify)	Red Amber Oreen		Red Amber Green
arillion 2008 carillionplc.co	m			Carillion Risk Ass	sessment Document – Version 1.

Appendix 2: BB3MM - M6 S/B departure from perry barr work unit



No protection as flat area.

Activity – environmental screen post Installation.



Edge delineation to top of embankment, slope no steeper than 1:2 with hazards or obstructions.

Activity – no work, awaiting panel installation



Edge protection to top of embankment with slope steeper than 1:2.

Activity – formwork (back of narrow verge shutter -install / remove).



Edge protection to edge of vertical drop on underpass.

Activity – No work, awaiting panel installation.



No protection to top of embankment with slopes steeper than 1:2 with no hazards.

Activity – No work, finished detail.



Edge delineation to top of embankment, slope no steeper than 1:2 with hazards or obstructions.

Activity – no work, awaiting panel installation.



Edge protection to top of embankment with slope steeper than 1:2.

Activity – install concrete apron.



Edge protection to edge of vertical drop.

Activity – gantry base reconstruction.

Appendix 3: Sample harness permit

Harness Permit			Expiry date:		
Contract name:			Contract no:		
Date:			Permit no:		
As a result of risk assessm use of a harness is deemed appropriate for the followin					
At location(s):					
Details of individual who w	II use the h	arness			
Name:					
Employer:					
		Work position	n / restraint	Yes	No
Type of harness to be used:		Fall arrest		Yes	No
		Rescue		Yes	No
Training, Competence and resc	ue: If the ans	wer is 'No' to a	ny question –	the permit cannot	be issue
Evidence of training has beer	verified by	permit issuer:		Yes	No
Is the user trained and compe	etent in:				
The use of the type of harr	ess listed a	bove?		Yes	No
Inspection of the type of ha	arness listed	l above?		Yes	No
Arrangements for rescue are	in place:			Yes	No
Permit Validity					
Date of issue:					
The permit is issued to:					
On behalf of xxxxx by:					
Receipt of Permit					
Signed					
	1				

If you need help using this or any other Highways Agency information, please call **0300 123 5000*** and we will assist you.

© Crown copyright 2013.

You may re-use this information (not including logos) free of charge in any format or medium, under the terms of the Open Government Licence. To view this licence, visit http://www.nationalarchives.gov.uk/doc/open-government-licence/ or write to the lnformation Policy Team, The National Archives, Kew, London TW9 4DU, or email: psi@nationalarchives.gsi.gov.uk.

This document is also available on our website at www.highways.gov.uk

If you have any enquiries about this publication email ha_info@highways.gsi.gov.uk or call 0300 123 5000*
Please quote Highways Agency publications code PR93/13
Highways Agency media services Bedford S130303

* Calls to 03 numbers cost no more than a national rate call to an 01 or 02 number and must count towards any inclusive minutes in the same way as 01 and 02 calls. These rules apply to calls from any type of line including mobile, BT, other fixed line or payphone. Calls may be recorded or monitored.