

Case Study Reference: IEM/2012/003

these case studies highlight actions we are taking to reduce our carbon footprint within the Environment Agency, including benefits and lessons learnt

Swinefleet Carbon Reduction Case Study

Background

The **Swinefleet** project was an £11.9m project where we raised and strengthened 1.1 km of embankment along the Humber Estuary. The flood defence was a steel sheet pile wall clad with European oak, rather than brick. Most of the work was undertaken from the river using barges and pontoons as shown in the photo.



Increase in the Carbon Footprint

The outline design had a carbon footprint of 3,565 tonnes CO₂ (tCO₂). However, the carbon footprint increased by 1,350 tCO₂ to 4,915 tCO₂ due to the lack of availability of recycled products within the market and design changes reacting to unforeseen circumstances.

Steel sheet piling

Sheet piling was intended to be made from imported recycled metal to reduce the CO₂ impact. However, due to defective units being delivered, replacements (with high recycled content) could not be sourced in time. This resulted in an increase of 1,536 tCO₂.

Between the project planning stage and detailed design it was identified that changes were required to the line of the sheet piles to suit local conditions. Heavy use piling was reduced by 1,300 m², but medium use piling increased by 3,100 m². This led to a net embodied CO₂ increase of 150 tCO₂. At the same time an extra 10% of length was added to the project (i.e. increase in scope). The net increase between these two stages was 149 tonnes of CO₂.

Recycled Aggregates

At the outline design stage it was planned to use recycled aggregates on the project. However, at the construction stage recycled material was not available in sufficient quantities locally. This increased the carbon footprint by 89 tonnes of CO₂.

The lessons to take away

Constraints during construction can result in significant design changes. Design changes can increase the carbon footprint on projects. Wherever possible any design changes should have their CO₂ assessed to assist decision making.

When specifying recycled materials the availability of these within the market should be taken into account.

Prepared by: Andy Powell - Innovation Manager

Date of Issue: April 2012

Further information available from Gary Haley or Andrew Powell

GEHO0512BWIY-E-E