



**AFCAP/KEN/089 - TRAINING REPORT ON DCP DESIGN METHOD
D415 Muruka – Kandara, Muranga Region 03-07.12.2012**

Jon Hongve

18 December 2012

This project was funded by the Africa Community Access Programme (AFCAP) which promotes safe and sustainable access to markets, healthcare, education, employment and social and political networks for rural communities in Africa.

Launched in June 2008 and managed by Crown Agents, the five year-long, UK government (DFID) funded project, supports research and knowledge sharing between participating countries to enhance the uptake of low cost, proven solutions for rural access that maximise the use of local resources.

The programme is currently active in Ethiopia, Kenya, Ghana, Malawi, Mozambique, Tanzania, Zambia, South Africa, Democratic Republic of Congo and South Sudan and is developing relationships with a number of other countries and regional organisations across Africa.

This material has been funded by UKaid from the Department for International Development, however the views expressed do not necessarily reflect the department's or the managing agent's official policies.

For further information visit <https://www.afcap.org>

The Africa Community Access Programme (AFCAP) is a regional programme funded by the UK government through the Department for International Development (DFID) which is supporting research, knowledge dissemination and training for improved access for rural communities in Africa.

One of the objectives of AFCAP is to operationalize the SADC Guideline for Low Volume Sealed Roads (LVSR).

A significant portfolio of research activities has now been established in the AFCAP participating countries. AFCAP provides technical assistance for these activities and promotes the uptake of the research findings through revised, country specific LVSR design manuals and specifications.

On this background a proposal was formulated to research on the application of the DCP Design Method in Kenya with the overall objective to support rural development through establishment of appropriate LVSR pavement design standards which in turn can facilitate the expansion of the paved rural road network.

This research project is part of the AFCAP research portfolio and is funded by Kenya Rural Roads Authority (KeRRA), and Crown Agents, UK. For budgetary and logistical reasons, the project initially aims to design and construct three short test sections located in Central Province. The sections are located in areas with different soils, topography and climatic conditions.

The project has a training component in the application of the DCP Design Method.

This report covers the first training exercise for selected trainees from KeRRA, Materials Testing and Research Department as well as private sector consultants.

Table of Contents

Background.....	4
The Training Programme	4
Objectives	4
Trainees	6
Data collection	6
Traffic data	6
DCP tests	6
Moisture tests.....	7
Additional pavement layer(s)	7
Data analysis.....	8
Preliminary design and construction approach.....	10
Annex 1: List of participants	15
Annex 2: Data collection sheets	17
Annex 3: DCP test positions.....	24

Background

The Malawi DCP Design Manual, the first of its kind, was completed in October 2012 following a study and back analysis of a number of Low Volume Sealed Roads in Malawi which concluded that the DCP Design Method and Catalogue is appropriate for the design of LVSRs. The method enables designers to more effectively utilize local materials for LVSR pavements thereby reducing the costs of upgrading gravel and earth roads to sealed road standard.

Under AFCAP/KEN/089/G the Malawi DCP Design Manual was presented to KeRRA, Materials Testing and Research Department and private sector consultants involved in AfD Roads 2000 Central project.

The presentation resulted in a general consensus that a draft Kenya DCP Manual should be produced and that it should be followed up with a more thorough dissemination and training exercise early 2013.

It is evident that extensive training and guidance will be needed for the successful application of the DCP Design Method since it's a new concept breaking quite radically from the conventional CBR base design methods.

A proposal for starting the training on the extension of D415 Muruka – Kandara in Muranga Region already in December 2012 under AFCAP/KEN/089 for selected trainees from KeRRA, Materials Testing and Research Department and private sector consultants was therefore presented to KeRRA with the intention that the data collected from this training exercise could also be used for the upcoming training in 2013.

The extension of D415 from Muruka to Kandara is about 7.5 km long and goes through rolling terrain. It was rehabilitated to gravel standard in Roads 2000 Phase 1 and completed around June 2008. The current condition is fair and the drainage is reasonably good, but very little of the laterite wearing course remains.

The Training Programme

Objectives

The objectives for this training exercise were:

- To give the trainees hands-on experience in carrying out the DCP testing in the field
- Show correct handling of the equipment
- Determination of acceptable tests and which tests to abort and/or reject
- Demonstrate the main features of the DCP software and give the trainees hands-on experience in data entry and analysis.

The first part of training programme covered in this report is shown in table 1 below:

Date	Activity
Day 1 - 03.12.2012	Gathering at Muruka 09.00 AM Brief Visual Assessment DCP tests, Soil sampling
Day 2 - 04.12.2012	DCP tests, Soil sampling
Day 3 - 05.12.2012	DCP tests, Soil sampling
Day 4 - 06.12.2012	Entering data (AFCAP consultant and Max & Partners only)
Day 5 - 07.12.2012	Preliminary design using the DCP software

Table 1: Training programme for the week 03-07 December

The DCP testing is repetitive, hence the trainees needed only one day in the field to get hands-on experience with the DCP test and an orientation about the possible pitfalls when carrying out the tests. On Day 4 the DCP data was entered in the WinDCP software by the AFCAP consultant and Max & Partners to prepare for the common session for all trainees on Day 5 on the use of the programme and doing the preliminary design.

The last day gathered 19 trainees, some of whom had not participated in the field work.

Some delays were encountered since none of the trainees had downloaded and installed the WinDCP Software. It came to light that obtaining the license code free of charge was only for AFCAP participants. This was resolved with CSIR during the morning hours such that many trainees managed to install the software and participate in the training exercises in the use of the programme.

Issue covered were in short:

- Creating a new project, storage location of project files
- Main features of the opening screen
- DCP data entry
- Defining pavement layers
- Pre-defined and User defined DCP Design Curves
- Single point analysis
- Average analysis

The trainees were given DCP DN values to enter for one point and shown how to do a single point analysis. Copies of the data file for all points were then handed out so that they could also define an average analysis for selected points.

The preliminary findings were discussed in light of the pattern that emerged from the average analysis. However, the moisture test results were not available at the time so only an indication of the likely pavement design could be made.

Due to the delays with installation of the software there was no time to do a Cusum Analysis to determine uniform sections. However, the DCP data indicates that the whole road is fairly uniform with the variability in DN values caused by differences in moisture content and local variations in the materials and field densities.

This was deemed to be the most effective way of conducting the training and limit the time the trainees have to stay out of their respective stations.

Table 2 shows the outline of the training programme up to final design and the joint workshop with AFCAP/KEN/089/G in February 2013.

Activities	Responsible/Participants	12-16 Nov	19-23 Nov	26-30 Nov	03-07 Dec	10-14 Dec	17-21 Dec	24-28 Dec	1-4 Jan	7-11 Jan	14-18 Jan	21-24 Jan	27-31 Jan	3-7 Feb	10-14 Feb
Field work, prelim design	All, AFCAP, DCS Consultant														
Field moisture content	Thika lab														
Borrowpit samples, Lab DN value	DCS Consultant, Thika lab														
Final design	All														
AFCAP/KEN/089G Workshop	All														

Table 2: Outline of Training Programme under AFCAP 1 (ending March 2013)

Trainees

Table 3 shows the proposed staff to be included in the initial training programme. Due to the coincidence with the AfD Mission, the actual dates of attendance differ somewhat from the proposed dates. A full list of participants is provided in Annex 1.

Firm/Department	No of persons	Attendance				
Max & Partners (Roads 2000)	2	03.12	04.12	05.12	06.12	07.12
CAS Consultants (Roads 2000)	2	03.12				07.12
Regional Manager Muranga	1		04.12			07.12
Regional Manager Kiambu	1		04.12			07.12
Regional Manager Nyandarua	1	03.12				07.12
Regional Manager Nyeri	1			05.12		07.12
Regional Manager Kirinyaga	1	03.12				07.12
Regional Manager Laikipia	1			05.12		07.12
Egis International/Norcken (Roads 2000)	1			05.12		07.12
KeRRA HQ	1		04.12			07.12
Materials & Testing Department	1	03.12				07.12
Total	13	7	5	5	5	13

Table 3: Proposed trainees and attendance dates

Data collection

Traffic data

Traffic counts and Axle Load Survey was done in October on the completed part of D415. It was intended to use these data for the DCP design exercise. However, the report was not yet out and assumptions on the Design Traffic Loading therefore had to be made. The 15 year Design Traffic loading was set to 0.1 -0.3 MESA for the training exercise based on previous data from the completed section of D415.

DCP tests

For a full DPC design it was estimated that at approx. 75 DCP tests would have to be done, on average one test every 100 m. However, during the DCP testing it became evident that the section was fairly uniform throughout, hence the number of tests was reduced to 41. A

further 13 tests had to be aborted due to stones in the ground or hard layers making it impossible to penetrate to the full depth of 800mm. The DCP tests were completed during the three field days. Copies of the Data Collection sheets are provided in Annex 2. Annex 3 shows the chainage and position of each DCP test. It was found that this format is useful during the data analysis since it is easy to identify all tests done at similar positions (related to offset from centre line) for average analysis.

Moisture tests

The tests were carried out towards the end of the short rains. It was therefore assumed that the pavement would be at or close to its highest relative moisture content.

The three days prior to the field tests and during the morning of the first field

day it was raining quite heavily and persistently. In the afternoon on the first field day the weather cleared up and became quite warm and sunny. It remained warm and sunny for day two and three. The field moisture results should be seen in this light.

The DCP penetration rate (DN value) is highly dependent on the moisture content in the pavement. Sampling of the alignment soils was therefore done at the same time as the DCP tests to determine the relative field moisture content, RMC, compared to OMC at the time of the DCP tests. Samples were taken at 0-150mm, 150-300mm and 300-450mm depth at eight locations with at least one test for every kilometer. The samples were taken and analyzed by the Materials Laboratory in Thika who were present during all three field days. The moisture test results are shown in Table 4 below.

Additional pavement layer(s)

The final design may incorporate one additional pavement layer. The source for the pavement layer should be identified and the material tested in the laboratory using the DCP to determine the DN value at various compaction efforts and moisture contents as described in the Malawi DCP Manual Section B6, Annex 5A: Determination of Laboratory DN value. Representative samples from the borrow pit should be taken and for each sample 9 DCP tests should be carried out. **For testing at 0.75 OMC, it is important that the samples are compacted at OMC, then dried back to 0.75 OMC, sealed and left for four days for the moisture to equilibrate.**



Picture 1: Regional Managers doing DCP test

Trial pit	Km	Position	Depth mm	MDD kg/m ³	FMC %	OMC %	RMC % of OMC	Description
3	0+210	LHS 3 m	0 - 150	1735	28,2 %	17,1 %	165 %	Red soil mixed with gravel
			150 - 300		16,1 %		94 %	
			300 - 450		27,8 %		163 %	
10	0+910	LHS 3 m	0 - 150	1650	24,1 %	21,1 %	114 %	Red soil mixed with gravel
			150 - 300		19,3 %		91 %	
			300 - 450		26,7 %		127 %	
11	1+110	CL	0 - 150	1540	28,0 %	19,7 %	142 %	Red soil mixed with gravel
			150 - 300		21,4 %		109 %	
			300 - 450		25,8 %		131 %	
21	2+600	LHS 3 m	0 - 150	1685	14,2 %	21,5 %	66 %	Red soil mixed with gravel
			150 - 300		26,3 %		122 %	
			300 - 450		20,0 %		93 %	
26	3+500	CL	0 - 150	1560	17,2 %	19,7 %	87 %	Red soil mixed with gravel
			150 - 300		25,0 %		127 %	
			300 - 450		27,6 %		140 %	
31	4+500	RHS 2,5 m	0 - 150	1485	20,2 %	22,6 %	89 %	Red soil mixed with gravel
			150 - 300		30,6 %		135 %	
			300 - 450		22,4 %		99 %	
36	5+500	CL	0 - 150	1678	17,6 %	22,5 %	78 %	Red soil mixed with gravel
			150 - 300		18,5 %		82 %	
			300 - 450		15,1 %		67 %	
40	6+300	LHS 3 m	0 - 150	1538	15,6 %	20,6 %	76 %	Red soil mixed with gravel
			150 - 300		27,2 %		132 %	
			300 - 450		16,6 %		81 %	

Table 4: Relative Moisture Content RMC at the time of DCP tests

Data analysis

Table 5 shows a summary of the DN values per layer sorted on test number and dates.

No effect of drying out during the hot and dry days (half day 1, entire day 2 and 3) can be detected from these data.

Table 6 shows the same data sorted on offset position (offset from centre). The data now clearly shows a distinct difference in strength between points 2.0 m from centre and points 2.5 m from centre. From this we can assume that the old road before rehabilitation in 2007/08 probably had an effective width of about 4.0 m which had been consolidated under traffic.

The pattern of the layer strength diagrams clearly shows the effect of the rain during 3 days prior to the tests. However, some of the moisture data are not consistent with the DN values one would expect for RMC below OMC. The reason for this is not quite clear. Testing of the samples taken for moisture tests with the DCP at various compaction efforts and moisture contents is expected to shed some more light on this and help to determine the measures to be taken for the upgrading of the pavement.

Test no	Chainage	Offset	Date	Weighted average DN per layer				
				0-150 mm	151-300 mm	301-450 mm	451-600 mm	601-800 mm
1	0,010	CL	03.12.12	4,37	2,04	2,97	5,1	7,02
4	0,310	CL	03.12.12	7,07	4,37	3,07	6,06	9,96
7	0,410	CL	03.12.12	4,16	3,76	2,62	4,28	7,66
11	1,110	CL	03.12.12	4,28	3,1	5,1	6,73	9,88
13	1,410	CL	03.12.12	7,35	5,84	6,81	3,45	4,69
15	1,810	CL	03.12.12	14,34	5,5	2,71	3,53	6,73
18	2,300	CL	04.12.12	6,73	6,18	3,09	3,41	6,04
20	2,500	CL	04.12.12	3,89	4,59	4,42	3,16	2,55
23	2,800	2,0 RHS	04.12.12	6,97	8,43	7,1	11,52	13,61
24	3,000	CL	04.12.12	7,61	2,26	2,66	5,22	9,63
25	3,300	2,5 LHS	04.12.12	13,69	12,52	7,67	12,21	19,21
26	3,500	CL	04.12.12	11,36	6,06	1,98	5,96	8,68
28	3,900	2,0 LHS	04.12.12	6,61	4,7	2,82	4,94	9,28
29	4,100	2,0 RHS	04.12.12	7,32	5,29	6,15	3,51	5,36
30	4,300	2,0 LHS	04.12.12	12,73	13,25	4,56	7,00	11,32
31	4,500	2,5 RHS	04.12.12	6,1	6,53	5,47	7,43	10,72
32	4,700	2,5 LHS	04.12.12	11,03	12,29	6,83	11,28	18,81
34	5,100	2,5 LHS	05.12.12	10,77	30,3	16,55	9,39	10,6
35	5,300	2,0 RHS	05.12.12	4,06	2,9	3,08	6,11	9,89
36	5,500	CL	05.12.12	3,39	4,28	2,34	5,15	7,99
37	5,700	2,0 LHS	05.12.12	4,05	3,19	3,33	6,65	9,17
39	6,100	CL	05.12.12	4,07	3,01	4,24	7,13	7,58
41	6,410	2,0 RHS	05.12.12	6,09	3,74	3,36	5,00	6,94
Average DN per layer				7,31	6,70	4,74	6,27	9,27

Table 5: Summary of DN values per layer (sorted on ascending test number and dates)

Test no	Chainage	Offset	Date	Weighted average DN per layer				
				0-150 mm	151-300 mm	301-450 mm	451-600 mm	601-800 mm
1	0,010	CL	03.12.12	4,37	2,04	2,97	5,10	7,02
4	0,310	CL	03.12.12	7,07	4,37	3,07	6,06	9,96
7	0,410	CL	03.12.12	4,16	3,76	2,62	4,28	7,66
11	1,110	CL	03.12.12	4,28	3,10	5,10	6,73	9,88
13	1,410	CL	03.12.12	7,35	5,84	6,81	3,45	4,69
15	1,810	CL	03.12.12	14,34	5,50	2,71	3,53	6,73
18	2,300	CL	04.12.12	6,73	6,18	3,09	3,41	6,04
20	2,500	CL	04.12.12	3,89	4,59	4,42	3,16	2,55
24	3,000	CL	04.12.12	7,61	2,26	2,66	5,22	9,63
26	3,500	CL	04.12.12	11,36	6,06	1,98	5,96	8,68
36	5,500	CL	05.12.12	3,39	4,28	2,34	5,15	7,99
39	6,100	CL	05.12.12	4,07	3,01	4,24	7,13	7,58
31	4,500	2,5 RHS	04.12.12	6,10	6,53	5,47	7,43	10,72
25	3,300	2,5 LHS	04.12.12	13,69	12,52	7,67	12,21	19,21
32	4,700	2,5 LHS	04.12.12	11,03	12,29	6,83	11,28	18,81
34	5,100	2,5 LHS	05.12.12	10,77	30,30	16,55	9,39	10,60
23	2,800	2,0 RHS	04.12.12	6,97	8,43	7,10	11,52	13,61
29	4,100	2,0 RHS	04.12.12	7,32	5,29	6,15	3,51	5,36
35	5,300	2,0 RHS	05.12.12	4,06	2,90	3,08	6,11	9,89
41	6,410	2,0 RHS	05.12.12	6,09	3,74	3,36	5,00	6,94
28	3,900	2,0 LHS	04.12.12	6,61	4,70	2,82	4,94	9,28
30	4,300	2,0 LHS	04.12.12	12,73	13,25	4,56	7,00	11,32
37	5,700	2,0 LHS	05.12.12	4,05	3,19	3,33	6,65	9,17
Average DN per layer				7,31	6,70	4,74	6,27	9,27

Table 6: Summary of DN values per layer (sorted on offset from centre)

In the following are shown average analysis for points at different offsets from centre. The user defined design curve for traffic class LV 0.3 for 0.1 to 0.3 MESA was used:

- 0-150 mm $DN \leq 3.2$
- 151-300 mm $DN \leq 6$
- 301-450 mm $DN \leq 12$
- 451-600 mm $DN \leq 36$
- 601-800 mm $DN \leq 50$

These clearly show the relatively low strength of the upper 150 mm, mostly due to moisture. The layers from 150mm to 450 mm depth within 2.0 m from centre are considerably stronger whereas at 2.5m and 3.0 m from centre these layers are much weaker probably due to a combination of moisture and less compaction under traffic.

Preliminary design and construction approach

Based on these observations preliminary recommendations for the upgrading of this road would be as follows:

From 2.0 m from centre each side:

- Cut to drain invert level at least 750mm below finished crown, windrow the material for the upper layers in the benches
- Bench in 150 mm layers up to 150 mm from the final level using in situ subgrade in the lower layers and the material from the existing pavement in the upper layers. Compact each layer to refusal.


For the middle 4.0 m:

- Scarify the top 150 mm and use the material for the top of the benches on each side
- Shape and proof roll to refusal the subgrade formation

New base layer:

- Import laterite gravel of known quality for a 150 mm thick base for the whole width of the road, shape to 3.5% camber and compact to refusal.

■ User Def. 1 traffic ■ Ave. ■ 20/80th Percentile




Structure number (DSN800)	192	Depth (mm)	W. Ave. Pen (mm/blow)	Blows	SD (mm/blow)	80P (mm/blow)	CBR(%)	UCS(kPa)
Struct. Cap. (MISA)	2.9	0 - 150	6.55	30	0.9	7.3	38	366
RUT Limit	20mm	151 - 300	4.25	45	0.4	4.6	65	593
Balance curve is where	B=6, A=3070	301 - 450	3.50	51	0.2	3.6	83	736
		451 - 600	4.93	34	0.6	5.4	54	502
		601 - 800	7.37	32	0.7	8.0	32	321

MISA = Million Standard Axles. Category VI : Poorly Balanced Deep Structure (PBD)

Figure 1 : Average analysis centre line points

■ User Def. 1 traffic ■ Ave. ■ 20/80th Percentile




Structure number (DSN800)	152	Depth (mm)	W. Ave. Pen (mm/blow)	Blows	SD (mm/blow)	80P (mm/blow)	CBR(%)	UCS(kPa)
Struct. Cap. (MISA)	1.3	0 - 150	6.83	26	0.9	7.6	36	349
RUT Limit	20mm	151 - 300	5.93	35	0.9	6.7	43	409
Balance curve is where	B=6, A=2800	301 - 450	4.34	40	0.3	4.6	63	579
		451 - 600	6.39	27	0.9	7.2	39	376
		601 - 800	9.37	23	0.6	9.9	24	245

MISA = Million Standard Axles. Category V : Averagely Balanced Deep Structure (ABD)

Figure 2: Average analysis of points 2.0 m from centre

■ User Def. 1 traffic ■ Ave. ■ 20/80th Percentile




Structure number (DSN800)	127	Depth (mm)	W. Ave. Pen (mm/blow)	Blows	SD (mm/blow)	80P (mm/blow)	CBR(%)	UCS(kPa)
Struct. Cap. (MISA)	0.7	0 - 150	8.13	23	1.8	9.7	29	287
		151 - 300	9.38	27	1.0	10.2	24	245
RUT Limit	20mm	301 - 450	6.08	33	1.0	6.9	41	397
		451 - 600	7.73	23	0.9	8.5	31	304
Balance curve is where	B=6, A=2268	601 - 800	11.36	20	1.0	12.2	19	198

MISA = Million Standard Axles. Category V : Averagely Balanced Deep Structure (ABD)

Figure 3: Average analysis of points 2.5 m from centre

■ User Def. 1 traffic ■ Ave. ■ 20/80th Percentile



Structure number (DSN800)	107	Depth (mm)	W. Ave. Pen (mm/blow)	Blows	SD (mm/blow)	80P (mm/blow)	CBR(%)	UCS(kPa)
Struct. Cap. (MISA)	0.4	0 - 150	10.19	21	1.2	11.2	22	223
RUT Limit	20mm	151 - 300	10.39	24	1.4	11.5	21	218
Balance curve is where	B=7, A=1832	301 - 450	7.94	26	0.4	8.2	30	295
		451 - 600	10.25	18	0.9	11.0	21	222
		601 - 800	14.04	18	1.5	15.3	14	156

MISA = Million Standard Axles. Category V : Averagely Balanced Deep Structure (ABD)

Figure 4: Average analysis of points 3.0 m from centre

Annex 1: List of participants

Item	Name	Designation	Organisation
<u>5TH DECEMBER 2012</u>			
1.	Julius M. Wambugu	Technologist	MOR material Dept
2.	Caroline Naliaka	Training Technician	MSC
3.	Musuku P. Gaitano	Training Technician	MSC
4.	Eng. P. Githere	RM Laikipia	KeRRA
5.	Eng. J. N. Kabiru	RM Nyeri	KeRRA
6.	Eng. W. K. Mburu	RM Kirinyaga	KeRRA
7.	Stephen J. Ochieno	Road Engineer	Max and Partners
8.	Chomba A. Gateri	Training Technician	MSC
9.	Etale Tunya	TL/Road Engineer	Max and Partners
10.	Richard M. Migwi	CRO Kandara	KeRRA
<u>4TH DECEMBER 2012</u>			
1.	Etale Tunya	TL/Road Engineer	Max and Partners
2.	Julius M. Wambugu	Technologist	MOR Material Dept
3.	Joseph Rugenyi	Superintendent Roads	Kerra Kiambu
<u>3RD DECEMBER 2012</u>			
1.	Julius M. Wambugu	Technologist	MOR material Dept
2.	CRO Nyandarua	KeRRA
3.	Chomba A. Gateri	Training Technician	MSC
4.	Eng. Methu	TL/Road Engineer	CAS Consultants
5.	Kent Kopar	Road Engineer	CAS Consultants
6.	James Nguyo	Road Engineer	Max and Partner

GROUP: KENTA RURAL ROADS AUTHORITY

DATE: 7/12/2012

DESCRIPTION, EXPERIENCE, ATTENDANCE

NAME	TITLE	ROOM NO.	SIGNATURE
1. NAME			
2.			
3. KILINY K. MUMBA	Dist-Keenya	KEERA	
4. Henry Orona	T.A. DADA	MSC	
5. Paul Muthu	AE NJEST	CAS CON	
6. Eng. J. MURUGO	PM-Kisumu	KEERA	
7. RICHARD MURWT	CRO KANAKA	KEERA	
8. CHOMSA AK LARAI	TRAINING TECH	MSC	
9. CAROLINE N. MURWA	"	MSC	
10. MURUKO P. GATARIO	"	MSC	
11. RICHARD K. WAMBURU	Ag. Engr. MSc	KEERA	
12. Eng. Joseph MANGWA	PLM	KEERA	
13. Eng. P. Githare	RM	KEERA	
14. Eng. J.N. KABIRU	RM	KEERA	
15. Julius Wambugu	Technologist	Msc, Material	
16. JAMES NGUYO	BSC. Ed. Engin	MAX	
17. LAWI K. MANGU	Ag. Sea Eng.	KEERA	
18. Julius M. MURUGO	Ag. Eng.	Nexton I Ltd	
19. JOHN STEPHEN OCHIENO	RIASE ENG	MAX	
20. ETALE TUNTA	ROADS ENG	MAX	
21. KENT KOMR	ROAD ENG	CAS CON	
22.			
23.			
24.			
25.			
26.			

Annex 2: Data collection sheets

Road:	2415 Munka Kavčarska									Date:	03-12-2012
Chainage	0+00	0+100	0+200	0+300	0+400	0+500	0+600	0+700	0+800	0+900	0+1000
Offset	E	2m RMB	E	2m LMB	E	2m RMB	2m LMB	E		RMB	3m RMB
No of blows	Test no										
0	85.	81.	80.	86.	83.	86.	83.	75.	90	96.	
5	110.	109.	111	161.	137.	136.	164.	111.	140	152.	
10	135.	205.	137	228.	165.	202.	356.	134.	152	170.	
15	157.	234.	143	279.	191.	272.	419.	152.	300	187.	
20	176.	263.	159	325.	211.	320.	472.	167.		198.	
25	195.	320.	172	356.	231.	349.	515.	181.		208.	
30	219.	389.	186	376.	251.	373.	551.	194.		218.	
35	235.	302.	303	392.	273.	393.	591.	206.		226.	
40	247.	320.	319	406.	296.	413.	634.	219.		236.	
45	256.	345.	385	419.	324.	434.	687.	230.		247.	
50	265.	365.	260	432.	344.	459.	745.	240.		257.	
55	272.	383.	268	442.	365.	472.	812.	259.		271.	
60	280.	404.	282	453.	378.	564.	902.	275.		282.	
65	290.	423.	296	462.	390.	686.		292.		297.	
70	306.	444.	309	472.	402.	829.		310.		314.	
75	309.	465.	329	482.	416.	946.		335.		313.	
80	318.	488.	330	490.	431.			356.		358.	
85	327.	514.	339	509.	447.			377.		378.	
90	327.	537.	346	521.	462.			398.		388.	
95	349.	563.	264	525.	476.			414.		403.	
100	363.	587.	363	550.	491.			427.		418.	
105	373.	616.	370	567.	507.			438.		432.	
110	384.	648.	378	585.	526.			449.		448.	
115	393.	682.	386	601.	547.			460.		466.	
120	401.	714.	391	618.	571.			470.		485.	
125	410.	749.	378	636.	598.			481.		500.	
130	419.	782.	402	653.	631.			493.		527.	
135	430.	817.	405	673.	665.			504.		556.	
140	446.	854.	412	693.	705.			515.		586.	
145	461.	895.	416	715.	758.			527.		627.	
150	477.	—	—	739.	810.			539.		676.	
155	493.			762.	859.			553.		726.	
160	510.			800.	908.			568.		791.	
165	531.			839.	—			586.		831.	
170	552.			884.				607.		910.	
175	576.			—				631.			
180	599.							659.			
185	626.							690.			
190	652.							724.			
195	681.							760.			
200	713.							800.			
205	746.							840.			
210	781.							884.			
215	812.							—			
220	849.										

Road:	DY15 Muruk-Kandara										Date:	03-12-2017	
Chainage	0+70	0+90	0+95	1+10	1+50	1+10	1+30	1+30	1+30	1+30	1+30	1+30	1+30
Offset	3MHS	4E	4E	4E	4E	4E	4E	4E	4E	4E	4E	4E	4E
No of blows	Test no												
		X	X	X				X	X				
0	93.	79	70	85	107.	88.	93	100	85.	82.			
5	140.	125	144	127	169.	127.	153	144	127.	127.			
10	173.	157	192	162	236.	148.	201	184	165.	191.			
15	233.	179	222	186	268.	165.	227	211	195.	202.			
20	276.	200	246	202	300.	181.	236	217	226.	223.			
25	328.	216	272	220	365.	194.	244	240	255.	240.			
30	376.	238	290	247	372.	208.	243	253	285.	257.			
35	425.	261	301	265	330.	219.	255	265	315.	275.			
40	469.	282	313	276	341.	230.		275	352.	300.			
45	635.	299	322	286	352.	242.		285	385.	332.			
50	725.	310	320	292	365.	253.		294	416.	376.			
55	865.	317	326	302	380.	271.		307	447.	415.			
60	1075.	324	326	310	400.	283.		311	480.	462.			
65	—	329	353	312	419.	297.		329	515.	488.			
70	—	—	361	322	438.	311.		337	555.	507.			
75	—	—	368	331	460.	325.		337	590.	522.			
80	—	—	374	336	483.	341.		345	634.	537.			
85	—	—	—	341	509.	352.		344	670.	551.			
90	—	—	—	—	540.	376.		361	711.	566.			
95	—	—	—	—	572.	397.		371	759.	582.			
100	—	—	—	—	621.	420.		378	802.	596.			
105	—	—	—	—	660.	445.		387	848.	614.			
110	—	—	—	—	736.	471.		395	882.	632.			
115	—	—	—	—	856.	498.		403	—	650.			
120	—	—	—	—	981.	525.		412	—	670.			
125	—	—	—	—	—	552.		420	—	692.			
130	—	—	—	—	—	584.		429	—	709.			
135	—	—	—	—	—	619.		440	—	728.			
140	—	—	—	—	—	652.		448	—	746.			
145	—	—	—	—	—	689.		456	—	766.			
150	—	—	—	—	—	734.		—	—	787.			
155	—	—	—	—	—	787.		—	—	809.			
160	—	—	—	—	—	838.		—	—	835.			
165	—	—	—	—	—	886.		—	—	865.			
170	—	—	—	—	—	—		—	—	900.			
175	—	—	—	—	—	—		—	—	—			
180	—	—	—	—	—	—		—	—	—			
185	—	—	—	—	—	—		—	—	—			
190	—	—	—	—	—	—		—	—	—			
195	—	—	—	—	—	—		—	—	—			
200	—	—	—	—	—	—		—	—	—			
205	—	—	—	—	—	—		—	—	—			
210	—	—	—	—	—	—		—	—	—			
215	—	—	—	—	—	—		—	—	—			
220	—	—	—	—	—	—		—	—	—			


Road:		D415 Mumbeka - Vandara			Date:		03-12-2018	
Chainage	1460	1480	1500					
Offset	on left	↓	on right					
No of blows	Test no							
0	52	100	93					
5	129	177	141					
10	156	245	185					
15	177	285	224					
20	195	310	254					
25	213	326	284					
30	232	363	313					
35	253	385	349					
40	273	399	387					
45	293	414	427					
50	312	421	460					
55	332	430	500					
60	353	439	549					
65	375	447	606					
70	400	458	685					
75	429	468	728					
80	459	479	784					
85	493	491	796					
90	530	506	832					
95	561	524	875					
100	587	545	925					
105	610	564	—					
110	632	582						
115	652	593						
120	682	612						
125	705	626						
130	727	644						
135	766	662						
140	800	681						
145	839	702						
150	852	725						
155	—	749						
160		775						
165		807						
170		845						
175		889						
180		935						
185		—						
190								
195								
200								
205								
210								
215								
220								

Road:	D 415 Muroka-Vandara									Date:	04-12-2018
Chainage	2+100	2+300	2+400	2+600	2+600	2+500	2+800	3+000	3+200	3+200	
Offset	1.5m RM	Centre	3M RM	C.C	3M LHS	3M LHS	2 MFS	C	3M LHS	2.5M RM	
No of blows	Test no R11										
0	76	82	78	75	76	78	72	73	X	X	
5	105	121	97	98	102	130	97	119	112	113	
10	134	154	120	119	130	182	125	165	134	122	
15	177	184	142	137	157	254	162	245	154	131	
20	224	221	168	156	191	492	204	216	172	139	
25	261	236	195	173	240	602	248	235	190	149	
30	294	261	221	190	288	684	281	280	204	165	
35	224	290	254	209	341	755	364	268	215	180	
40	352	335	290	229	384	825	370	238	225	197	
45	385	357	317	246	410	900	410	282	232	215	
50	411	381	342	268	437	12	432	215	245	234	
55	437	403	367	281	463		468	304	287	263	
60	457	421	391	301	491		502	310	269	302	
65	476	437	420	322	525		549	319	300	327	
70	496	453	449	349	565		602	326	290	345	
75	516	467	480	383	603		637	336	351	362	
80	536	479	513	417	642		734	345	309	370	
85	560	491	553	440	676		802	353	317	390	
90	587	504	600	457	720		871	357	325	402	
95	615	516	656	479	773		942	365	330	413	
100	647	530	722	490	831			378	335	425	
105	683	544	798	508	918			388	340	435	
110	730	561	879	520				400	345	443	
115	779	580		535				410		452	
120	832	597		549				422		464	
125	895	615		560				433		472	
130	L	631		575				446		480	
135		647		590				457		488	
140		664		602				470		496	
145		682		617				484		505	
150		700		632				500		512	
155		721		652				515		520	
160		743		672				530		530	
165		770		692				541		537	
170		799		710				556		545	
175		835		729				569		553	
180		873		741				585		562	
185		926		753				605		570	
190				763				600		579	
195				772				611		588	
200				782				620		597	
205				791				632		610	
210				804				644		621	
215				814						634	
220				824						647	

Road:	D45 Muzalea - Kamboja							Date:	01.12.12		
Chainage	3+300	3+500	3+700	3+900	4+100	4+300	4+500	4+700	4+900	A+100	
Offset	25 LHS	0	2 RHS	2 LHS	0	20 RHS	0	LHS 2m	RHS 4m	2.5m	
No of blows	Test no										
0	77.	82.	82.	85.	82	82.	80	86.	100.	83.	
5	105.	130.	119.	107.	98	129.	111	123	121.	111.	
10	155.	187.	160.	141.	122	170.	143	174	145.	154.	
15	252.	253.	240.	172.	128	197.	170	264.	182.	225.	
20	324.	297.	326.	214.	151	221.	195	340	214.	300.	
25	359.	322.	362.	265.	162	248.	212	377.	246.	352.	
30	390.	334.	392.	278.	188	278.	237	407.	281.	400.	
35	424.	345.	423.	301.	208	303.	252	430.	319.	431.	
40	460.	354.	459.	323.	222	325.	262	455.	354.	467.	
45	500.	362.	500.	334.	252	348.	280	473.	381.	485.	
50	548.	373.	543.	357.	281	377.	292	490.	403.	523.	
55	605.	380.	605.	376.	299	408.	305	512.	453.	567.	
60	672.	388.	672.	395.	326	441.	312	534.	465.	620.	
65	714.	396.	754.	411.	335	470.	330	560.	489.	680.	
70	854.	400.	864.	422.	381	505.	339	590.	513.	769.	
75	980.	408.	994.	436.	391	530.	350	622.	538.	870.	
80		417.		447.	384	550.	360	662.	566.	987.	
85		427.		459.	399	565.	371	708.	599.		
90		435.		472.	408	581.	383	754.	632.		
95		443.		485.	422	597.	394	812.	673.		
100		452.		500.	429	615.	402	875.	720.		
105		462.		512.	443	633.	412	953.	770.		
110		471.		529.	456	650.	422		821.		
115		481.		544.	469	669.	430		880.		
120		492.		562.	485	687.	441		940.		
125		503.		582.	497	716.	450				
130		514.		605.	469	743.	460				
135		528.		627.	485	771.	471				
140		545.		655.	480	797.	481				
145		570.		690.	483	821.					
150		598.		729.	486	847.					
155		629.		774.	485	875.					
160		663.		824.	480	904.					
165		701.		875.							
170		743.		931.							
175		784.									
180		825.									
185		873.									
190		930.									
195											
200											
205											
210											
215											
220											

Road:	D415 - Supriya - Vandana										Date:	08/12/12
Chainage	4+900	5+100	5+300	5+500	5+700	5+900	6+100	6+300	6+400	6+400		
Offset	3 R.H.S	2.5 L	2.0 R	4	2.0 L	3.0 R	4	3.0 L	2.0 R	2.0 R		
No of blows	Test no											
0	80.	89.	83.	79.	75.	96.	96.	88.	90.	85.		
5	99.	125.	103.	94.	94.	114.	114.	109.	107.	108.		
10	128.	144.	121.	110.	110.	124.	134.	130.	121.	132.		
15	182.	177.	138.	126.	127.	138.	156.	169.	139.	167.		
20	248.	263.	156.	142.	152.	154.	176.	232.	160.	204.		
25	306.	427.	175.	155.	172.	176.	197.	319.	185.	234.		
30	342.	485.	194.	169.	194.	186.	218.	385.	205.	259.		
35	370.	537.	220.	183.	213.	206.	238.	442.	220.	275.		
40	397.	592.	244.	200.	235.	234.	268.	495.	222.	289.		
45	423.	634.	268.	224.	254.	246.	279.	537.	245.	301.		
50	451.	676.	285.	248.	276.	266.	297.	580.	255.	316.		
55	480.	722.	299.	275.	289.	290.	310.	625.	269.	332.		
60	514.	770.	310.	304.	304.	308.	324.	686.	280.	353.		
65	554.	822.	321.	328.	316.	321.	336.	758.	294.	372.		
70	599.	881.	320.	344.	332.	332.	348.	835.	306.	397.		
75	647.	955.	340.	355.	345.	346.	360.	920.	319.	420.		
80	697.		348.	365.	358.	357.	372.		323.	438.		
85	754.		359.	375.	370.	372.	385.		346.	452.		
90	814.		370.	383.	381.	385.	398.		358.	468.		
95	876.		378.	391.	394.	400.	410.		370.	479.		
100	940.		388.	400.	405.	415.	425.		380.	492.		
105			400.	409.	419.	434.	439.		390.	509.		
110			410.	420.	431.	454.	456.		400.	523.		
115			423.	428.	445.	472.	479.		409.	539.		
120			434.	438.	453.	501.	500.		417.	559.		
125			446.	449.	480.	526.	524.		426.	580.		
130			460.	465.	502.	556.	557.		435.	603.		
135			477.	471.	524.	589.	595.		443.	627.		
140			493.	483.	552.	622.	631.		452.	653.		
145			512.	497.	582.	663.	668.		460.	685.		
150			535.	511.	615.	706.	700.		469.	719.		
155			557.	528.	652.	752.	734.		479.	751.		
160			586.	549.	690.	807.	775.		488.	783.		
165			615.	572.	735.	850.	811.		496.	819.		
170			646.	595.	778.	891.	851.		504.	854.		
175			684.	622.	823.		889.		513.	893.		
180			724.	649.	875.				523.			
185			776.	680.								
190			829.	715.								
195			880.	755.								
200			935.	794.								
205				835.								
210				879.								
215												
220												

Annex 3: DCP test positions



Aborted tests