



# SEACAP 21/002 Feasibility Study for a

National Programme to Manage Slope Stability

SEACAP Practitioners' Workshop 4-5 November 2008 Principal Land use –50%

¥

....

Topography, 70% hilly/mountainous, highest point 2820m asl





LocationAARfallRangeVang Vieng3900mm3150-4550mmLuang Prabang1430mm1150-1800mm

Rocks & Soils

# Geomorphology















### **Scope of the Feasibility Study**

- Assess the magnitude of the slope stability issue, and its economic and social impact
- Assess the technical, economic and financial feasibility of a slope management programme
- Review the capacity of the MPWT to provide quality engineering services for landslide prevention and management, and the promotion of hill slope stabilisation
- Define a costed programme with expected outputs and proposed implementation arrangements





#### **Principal Activities Undertaken**

- Collection of landslide incidence and repairs data from MPWT and others
- Review of topographic, geological and rainfall effects on roadside slope stability
- Collection of a Landslide Inventory on selected roads
- Economic evaluation of landslide impacts and justification of pro-active and reactive stabilisation/protection measures
- Review of MPWT capacity for slope stability management
- Recommendations for MPWT capacity strengthening & a slope stability management programme
- Preparation of Typical Details for slope stabilisation and bio-engineering works



## Scott Wilson

### Landslide Inventory

 Notes, photographs and hazard/risk rating for
 >150 landslides

Over 1,500 km of the 7000 km National Road included in Inventory

 Approx 50% of the hilly or mountainous National Road network



## **Risk Ranking for Prioritisation of** Landslide Interventions

Actual (current condition) or expected consequences (without mitigation)		Ranking				
Actual (current condition) or expected consequences (without mitigation)				4	5	
Road completely lost (including road subsidence greater than 1m)	$\checkmark$					
Road partially lost		$\checkmark$				
Road completely blocked	XT	$\checkmark$				
Road subsidence less that 1m	-	$\checkmark$				
Road partially blocked			$\checkmark$			
Productive agricultural or forest land lost or destroyed			$\checkmark$			
Walls damaged or slope drainage blocked or damaged	///			$\checkmark$		
Roadside drainage damaged or blocked					$\checkmark$	
Continued erosion without destroying vegetation cover	A	1			$\checkmark$	
Panking	1 C	A second				

#### Ranking

- 1. Top priority, emergency measures required immediately; buildings may need to be evacuated.
- 2. High priority; realignment may be necessary.
- 3. Moderate priority, but some temporary remedial measures are required immediately, such as slip debris clearance, emergency road signing etc.
- 4. Low priority, but some temporary remedial measures are required quickly, such as slip debris clearance.
- 5. Least priority, but should be tackled as soon as possible under routine maintenance.



#### **Summary of Findings**

- Over 70% of recorded landslides had taken place above the road
- Approximately 60% of total recorded landslides were assigned low risk categories
- 4% of recorded landslides were judged to be rock slope failures,
  i.e. the vast majority were in soil or weathered rock
- 3% of recorded landslides were judged to have resulted in movement of the entire carriageway width, i.e. entire hillside



# What constitutes a landslide management programme?

- Investment in landslide avoidance/mitigation during initial alignment and road DESIGN
- CONSTRUCTION practices sympathetic to slope stability (cut, fill, spoil disposal, drainage control etc)
- Pro-active and reactive measures during OPERATION

## How do we assess the Feasibility of this Management Programme?

- Confirm the practicable and technical feasibility of implementing slope management measures
- Compare costs of slope management with benefits, i.e. reduced engineering, social & environmental costs caused by landslides.

#### Slope management costs:

- Improved alignments
- More stable cut and fill slopes
- Enhanced slope drainage works, etc

#### Landslide costs:

- Repairs/losses caused by landslide impacts to engineering assets
- Landslide debris clearance and access provision in landslide areas
- Traffic delays
- Social and environmental costs



## Summary of emergency maintenance expenditure over recent years (US\$ millions)

Fiscal Year	Landslide removal and repair	Carriageway repairs and road grading	Total emergency maintenance expenditure
2004- 05	5.15	1.19	6.34
2005- 06	3.17	3.43	6.59
2006- 07	3.14	2.08	5.21

# Estimated economic losses incurred by landslide road blockages according to period of blockage and AADT

Blockage Period	Tallation	Economic Losses (US\$)				
		AADT 100		-	AADT 300	
	VOT	VOC	Total	VOT	VOC	Total
3 hrs	93	686	779	280	2,057	2,337
6 hrs	373	2,742	3,115	1,119	8,227	9,346
12 hrs	1,491	10,969	12,460	4,474	32,907	37,381
24 hrs	5,966	43,876	49,842	17,897	131,627	149,524



### **Social and Environmental Costs**

- There have been no known deaths caused by landslides within the Laos road network RoW
- Other social costs, such as disrupted access to schools and health care etc, while important locally and for short periods of time, are not as significant as they might be due to low population density
- Environmental costs, including loss of forest resources, loss of farmland and sediment impacts downstream, are also considered to be low to moderate (<US\$10,000 per average slide)



#### **Economic Feasibility Assessment**

The Net Present Value was used to determine the economic return on investment in:

- Enhanced slope management during DESIGN & CONSTRUCTION
- Proactive/reactive interventions during OPERATION

Due to limited existing landslide data, several assumptions had to be made in terms of engineering intervention costs, landslide frequency and anticipated reduction rates in landslide costs. The costs of repairing damage caused by the various landslide types were derived from SEACAP 21/001 information from Roads 13N & 7



## **Conclusion of the Economic Analysis**

- On the basis of the data available & the assumptions made, the economic return on investment in slope management proved marginal
- However, in areas of the most significant landsliding it is anticipated that this investment will ultimately prove to be economically beneficial
- The analysis was very sensitive to the discount rate used, traffic volumes and the timing of landslide events in relation to the timing of the investments
- Given the anticipated increase in traffic flows over the forthcoming years, the justification in investments in slope management is likely to increase significantly
- There is likely to be a growing public expectation for road access provision with minimum delays and hold-ups
- There is also strategic (nationally and internationally) importance for road access provision



## **Review of MPWT Capacity to Manage** Landslides

- The MPWT and road sector is already in the process of change
- The revised structure could accommodate a stronger slope stabilisation programme
- The current procedures for emergency slope management appear adequate, though pro-active measures should be strengthened
- There is a shortage of technical skills in slope assessment, & the design & construction of slope stabilisation measures
- Skills development needs to be at several levels (management, design, supervision & technical)
- It needs to be both Central & Provincial
- There needs to be adequate coverage of personnel to allow for staff movement (which is increasing in the new organisation)
- There needs to be a way of sustaining the training in the long term (e.g. through strengthening University involvement)
- There is a significant knowledge gap on landslide occurrence & impact



## **Components of the Slope Stability Management Programme**

- Goals:
  - Enhanced Geo-Engineering for New Road Construction and Improvement Projects
  - Targeted and Affordable Slope Stability Interventions (Pro-active and Reactive Measures During Operation)
- Components for Achieving Goals
  - Capacity Development
  - Risk Assessment and Prioritisation of Interventions
  - Selected Rehabilitation Projects to Take the Process Forward



## **Proposed Specific Actions for MPWT**

....

- Confirm service standards (acceptable risk) for landslide management
- Review engineering procedures for landslide management in the light of SEACAP 21 outputs, and disseminate accordingly
- Review geometric standards of all classes of roads with a view to reducing slope instability wherever possible
- Add the proposed staff training to the current Organisational Capacity Development Plan
- Commission specialists to prepare & implement the slope management training required in landslide recognition, assessment & management
- Develop & apply the risk assessment & prioritisation system instigated under SEACAP 21/02. Confirm pilot locations for enhanced slope management & implement works as part of the training programme
- Implement landslide record, impact & monitoring programme, as part of the above.



## Possible Short List of Potential Rehabilitation Projects for Consideration Based on Risk Ranking

Site location	Failure category	Risk ranking (from SW landslide inventory)	Estimated Cost (US\$)*	Priority against MPWT strategy**	Final list?
NR 13N, 262+900	Above road	24	60,000	High	~
NR 12, 136+900	Above road	18	50,000	High	$\checkmark$
NR 12, 138+400	Above road	18	100,000	High	$\checkmark$
NR 12, 141+500	Above road	18	100,000	High	$\checkmark$
Patmong-Luang Prabang, 68+100 from Patmong	Below road	54	100,000	Moderate	~
NR 13N, 239+400	Below road	36	75,000	Moderate	~
NR 13N, 329+100	Below road	36	100,000	Moderate	$\checkmark$

\* Estimates only provisional: will require confirmation during early stages of proposed Programme

\*\* According to the likelihood of a failure causing a total blockage or loss of the road for at least three hours (in the case of National Roads).



Assistance and support by Chanh Bouphalivanh, Sysouvanthong Sengmany, Xayphone Chonephetsarath, Manilay Bouavong and David Salter

....



#### Thank You



# **SEACAP 21/001**

....

# Slope stabilisation trials on Road 13N and Road 7 in Lao PDR



What was the project trying to achieve?

#### The objectives were:

- To use best-practice appropriate slope stabilisation methods using local materials and technologies
- To extend the present technologies to cover specific landslips
- To assist in the procurement and supervision of slope stabilisation trials
- To disseminate the results by means of workshops, manuals and specifications



What were the constraints?

- Choice of sites
- Limited funds for construction
- Limited contractor capability
- Innovation



 Mountainous terrain from 450m to 1450m elevation

 Annual rainfall probably more than 2000mm



Scot+ Wilson



13 sites eventually chosen comprising a mix of failure types.

#### Phase 1

Those sites requiring mainly bio-engineering measures to prevent further instability. This comprised 3 sites, the work carried out just prior to and during the onset of the 2007 wet season.

#### Phase 2

Those sites requiring mainly geotechnical measures to prevent further instability. This comprised 10 sites, the work carried out mainly during the 2007/08 dry season. ....



SEACAP 21/001 PROGRAMME					
Task	06	2007	2008		
Planning & Inception					
Design & Documents	-	- 12 2 ×	AMIN (TRX) E		
Approvals & Bid					
Construction					
Manuals & Training					

Phase 1

Phase 2

....



#### **Engineering Geology Mapping**



36


## **Ground Investigation**







## Design

**Design Spreadsheet for Masonry Gravity Walls** 



### Section of Wall (in metres)

а	b	c	В	Н
0.6	1.091	0.262	1.953	3

Scot+ Wilson

## **Construction drawings**



39



## Construction





































## SEACAP 21 Slope Maintenance Site Handbook

ສາຫາລະນະລັດ ປະຊາທິປະໄຕ ປະຊາຊົນລາວ ສັນດິພາຍ ເອກະລາດ ປະຊາທິປະໄຕ ເອກະພາບ ວັດທະນາຖາວອນ

# ຄູ່ມືປະຈຳສະໜາມ ການສອັມແປງຕະຝັ່ງເຈື້ອນ



ກະຊວງໂຍທາທິການ ແລະ ຂຶ້ນສິ່ງ

ภัม**ย**า 2008





## **Slope Maintenance Site Handbook (1)**

- Written for site staff: technicians, supervisors etc.
- English and Lao language versions
- A5 size, 30 pages, illustrated mainly with photographs
- Structured around the MPWT's Maintenance Activity Codes.

- Definition of Maintenance for Slopes
- Routine Maintenance of Slopes

- Emergency Maintenance of Slopes
- Rehabilitation and Improvement.



Ministry of Public Works and Transport

Slope Malmenance Site Handbook

### Ministry of Public Works and Transport

Slope Maintenance Site Handbook

4.2 Construction of new walls

### What are the main types of walls?

There are three main types of wall constructed in Laos: masonry, gabion and reinforced concrete. Masonry walls can be composite or fully mortared.





Mortared masonry wall



Gabion wall



Reinforced concrete wall

Retaining walls may be constructed below or above the road. They retain the ground behind them. Revetments may also be constructed above the road.

From the road, Revetments and Retaining Walls can both look the same. The difference is that Revetments are very thin (usually only 300mm thick) and only prevent erosion and shallow sliding from occurring at the base of the slope. They are not very strong, and they do not act as retaining structures.



Retaining Wall

Page 16 of 33

Scott Wilson In association with LCG What are the advantages and disadvantages of the main types of walls?

Туре	Advantages	Disadvantages
Composite	Fairly cheap.	No flexibility.
masonry	Dry stone panels very permeable	Not as strong as full mortared masonry.
Mortared	Very durable.	Expensive.
masonry		No flexibility – should always be constructed on good foundations.
		Limited permeability, weep holes should always be provided.
Gabion	Flexible – good where founding	May be too flexible for road supporting
	conditions are variable.	retaining walls.
	Very permeable	Usually requires geotextile on back face to
		reduce fines seeping through wall.
	Cheaper than cemented	Foundation may be softened by water
	masonry	percolating through wall.
		Less durable than mortared masonry.
		Difficult to construct if foundation uneven,
		although this can be overcome by using a
		mortared masonry layer at the base.
		More difficult to construct in curves in plan.
Reinforced	Very durable if good quality	Most expensive option
Concrete	construction	No flexibility - should always be constructed
		on good foundations.
		No permeability, weep holes should always
		be provided

From considerations of cost, durability, appearance and strength, cemented masonry walls are generally recommended except where foundation conditions are soft or expected to move over time. In those cases, gabion walls are recommended.

### What wall shape should be used?

The Slope Maintenance Manual discusses a number of wall shapes and their advantages and disadvantages. For simplicity, two basic wall shapes are recommended - one for cemented masonry walls and the other for gabion walls.



Page 17 of 33

Scott Wilson in association with LCG



### Ministry of Public Works and Transport

Location (road and km): Date of report:

Situation

Above road

Below road

Through road

Slope Maintenance Site Handbook

Failure

Whole road

Part of road

Side drain only

Topography

Original slope angle

Failure angle

Associated retaining wall

LANDSLIDE REPORT

Material

Rock

Debris

Soil

Geometry of slipped area

Length (m perpendicular to road)

Width (m parallel to road)

Depth (m estimated) Estimated volume (L x W x D)

Sketch of failure/additional notes:

Reporter's name:

Blockage Whole road

Part of road

Side drain only

### Ministry of Public Works and Transport

Slope Maintenance Site Handbook

Have traffic warning signs been placed beside the road?         Have barriers been placed alongside the excavation to mark out its extent?         Are these clearly visible at night?         All walls         Have precautions been taken to prevent surface water on the road from entering the excavation?         If excavating into the hillside, has this been done in alternate bays and the wall constructed in short lengths to prevent hillside instability?         Is the excavated material being removed to a safe location and not dumped down the slope?         Has the excavation level been taken deep enough to ensure that the wall is adequately founded? (The use of a DCP may help in this regard).         Mortared and Composite Masonry walls         Does the stone being used meet the specification for durability, size and shape?         Is there sufficient cement in the mortar to meet the specified strength?         Is the mortar sufficiently fluid to ensure that all the voids between the stones are completely filled?         Have the marker blocks at the top of the wall been properly bonded into the rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have horizontal wire trusses (10 SWG or 3.25mm dia wir	Done?
Have barriers been placed alongside the excavation to mark out its extent?         Are these clearly visible at night?         All walls         Have precautions been taken to prevent surface water on the road from entering the excavation?         If excavating into the hillside, has this been done in alternate bays and the wall constructed in short lengths to prevent hillside instability?         Is the excavated material being removed to a safe location and not dumped down the slope?         Has the excavation level been taken deep enough to ensure that the wall is adequately founded? (The use of a DCP may help in this regard).         Mortared and Composite Masonry walls         Does the stone being used meet the specification for durability, size and shape?         Is there sufficient cement in the mortar to meet the specified strength?         Is there sufficiently fluid to ensure that all the voids between the stones are completely filled?         Have the marker blocks at the top of the wall been properly bonded into the rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have all the stones been carefully and densely packed into the basket?         Have horizontal wire trusses (10 SWG or 3.25	
Are these clearly visible at night?       All walls         Have precautions been taken to prevent surface water on the road from entering the excavation?       If excavating into the hillside, has this been done in alternate bays and the wall constructed in short lengths to prevent hillside instability?         Is the excavated material being removed to a safe location and not dumped down the slope?         Has the excavation level been taken deep enough to ensure that the wall is adequately founded? (The use of a DCP may help in this regard).         Mortared and Composite Masonry walls         Does the stone being used meet the specification for durability, size and shape?         Is there sufficient cement in the mortar to meet the specified strength?         Is there sufficiently fluid to ensure that all the voids between the stones are completely filled?         Have the marker blocks at the top of the wall been properly bonded into the rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
Have precautions been taken to prevent surface water on the road from         entering the excavation?         If excavating into the hillside, has this been done in alternate bays and the         wall constructed in short lengths to prevent hillside instability?         Is the excavated material being removed to a safe location and not dumped         down the slope?         Has the excavation level been taken deep enough to ensure that the wall is         adequately founded? (The use of a DCP may help in this regard).         Mortared and Composite Masonry walls         Does the stone being used meet the specification for durability, size and         shape?         Is there sufficient cement in the mortar to meet the specified strength?         Is the marker blocks at the top of the wall been properly bonded into the         rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have he rizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have he gabion baskets been properly connected to each other using 12 SW G (2.64mm dia) wire?	
entering the excavation?       If excavating into the hillside, has this been done in alternate bays and the wall constructed in short lengths to prevent hillside instability?         Is the excavated material being removed to a safe location and not dumped down the slope?       Has the excavation level been taken deep enough to ensure that the wall is adequately founded? (The use of a DCP may help in this regard).         Mortared and Composite Masonry walls       Does the stone being used meet the specification for durability, size and shape?         Is there sufficient cement in the mortar to meet the specified strength?       Is the mortar sufficiently fluid to ensure that all the voids between the stones are completely filled?         Have the marker blocks at the top of the wall been properly bonded into the rest of the wall?       Gabion walls         Is there adequate drainage from the lowest point of the excavation?       Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?       Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?       Stone scheme basket to each other using 12 SWG (2.64mm dia) wire?	
wall constructed in short lengths to prevent hillside instability?       Is the excavated material being removed to a safe location and not dumped down the slope?         Has the excavation level been taken deep enough to ensure that the wall is adequately founded? (The use of a DCP may help in this regard).       Mortared and Composite Masonry walls         Does the stone being used meet the specification for durability, size and shape?       Is there sufficient cement in the mortar to meet the specified strength?         Is there sufficient cement in the mortar to meet the specified strength?       Is the mortar sufficiently fluid to ensure that all the voids between the stones are completely filled?         Have the marker blocks at the top of the wall been properly bonded into the rest of the wall?       Gabion walls         Is there adequate drainage from the lowest point of the excavation?       Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?       Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have the gabion baskets been properly connected to each other using 12 SW G (2.64mm dia) wire?       SW G (2.64mm dia) wire?	
down the slope?         Has the excavation level been taken deep enough to ensure that the wall is adequately founded? (The use of a DCP may help in this regard).         Mortared and Composite Masonry walls         Does the stone being used meet the specification for durability, size and shape?         Is there sufficient cement in the mortar to meet the specified strength?         Is the mortar sufficiently fluid to ensure that all the voids between the stones are completely filled?         Have the marker blocks at the top of the wall been properly bonded into the rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
adequately founded? (The use of a DCP may help in this regard).         Mortared and Composite Masonry walls         Does the stone being used meet the specification for durability, size and shape?         Is there sufficient cement in the mortar to meet the specified strength?         Is the mortar sufficiently fluid to ensure that all the voids between the stones are completely filled?         Have the marker blocks at the top of the wall been properly bonded into the rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
Does the stone being used meet the specification for durability, size and shape?         Is there sufficient cement in the mortar to meet the specified strength?         Is the mortar sufficiently fluid to ensure that all the voids between the stones are completely filled?         Have the marker blocks at the top of the wall been properly bonded into the rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
shape?         Is there sufficient cement in the mortar to meet the specified strength?         Is the mortar sufficiently fluid to ensure that all the voids between the stones are completely filled?         Have the marker blocks at the top of the wall been properly bonded into the rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
Is the mortar sufficiently fluid to ensure that all the voids between the stones are completely filled? Have the marker blocks at the top of the wall been properly bonded into the rest of the wall? Gabion walls Is there adequate drainage from the lowest point of the excavation? Does the gabion baskets contain a transverse mesh at 1.0m centres? Are the stones durable and angular and with a minimum dimension not less than the gabion mesh? Have all the stones been carefully and densely packed into the basket? Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging? Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
are completely filled?         Have the marker blocks at the top of the wall been property bonded into the rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion wire conform to the specifications?         Do the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
rest of the wall?         Gabion walls         Is there adequate drainage from the lowest point of the excavation?         Does the gabion wire conform to the specifications?         Do the gabion baskets contain a transverse mesh at 1.0m centres?         Are the stones durable and angular and with a minimum dimension not less than the gabion mesh?         Have all the stones been carefully and densely packed into the basket?         Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging?         Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
Is there adequate drainage from the lowest point of the excavation? Does the gabion wire conform to the specifications? Do the gabion baskets contain a transverse mesh at 1.0m centres? Are the stones durable and angular and with a minimum dimension not less than the gabion mesh? Have all the stones been carefully and densely packed into the basket? Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging? Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
Does the gabion wire conform to the specifications? Do the gabion baskets contain a transverse mesh at 1.0m centres? Are the stones durable and angular and with a minimum dimension not less than the gabion mesh? Have all the stones been carefully and densely packed into the basket? Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging? Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
Do the gabion baskets contain a transverse mesh at 1.0m centres? Are the stones durable and angular and with a minimum dimension not less than the gabion mesh? Have all the stones been carefully and densely packed into the basket? Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging? Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
Are the stones durable and angular and with a minimum dimension not less than the gabion mesh? Have all the stones been carefully and densely packed into the basket? Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging? Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
than the gabion mesh? Have all the stones been carefully and densely packed into the basket? Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging? Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
Have horizontal wire trusses (10 SWG or 3.25mm dia wire) been installed at 0.33m centres during filling to reduce bulging? Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
at 0.33m centres during filling to reduce bulging? Have the gabion baskets been properly connected to each other using 12 SWG (2.64mm dia) wire?	
SW G (2.64mm dia) wire?	
Howe the apping backets been staggered, as in bledework, and with some	
Have the gabion baskets been staggered, as in blockwork, and with some gabions placed front to back?	
Reinforced Concrete walls	
Has the steel reinforcement been properly cleaned?	
Is there the specified cover between the reinforcement and the shuttering?	
Has the shuttering been properly secured to prevent movement during concreting?	
Does the concrete mix conform to specification?	
Has the concrete been vibrated to exclude all voids?	

Consequences if nothing done:

Probable cause of failure:

Page 29 of 33

Scott Wilson In association with LCG

Scott Wilson In association with LCG



ສາຫາລະນະລັດ ປະຊາທິປະໄຕ ປະຊາຊິນລາວ ສັນຕິພາບ ເອກະລາດ ປະຊາທິປະໄດ ເອກະພາບ ວັດທະນາຖາວອນ

# ຄູ່ມືການສອັມແປງຕະຝັ່ງເຈື່ອນ



ກະຊວງໂຍທາທິການ ແລະ ຂົນສິ່ງ

## SEACAP 21 Slope Maintenance Manual

ກັນຍາ 2008





## **Slope Maintenance Manual**

- Written for road management professionals: engineers
- English and Lao language versions
- A4 size, 110 pages, illustrated with drawings, photographs, typical details
- Covers all relevant aspects of site inspection, design and construction



## **Technical Specifications**

- Complete technical specifications for slope stabilisation and protection
- English and Lao language versions
- Based on international experience and best practices
- Tested through SEACAP 21 trials and modified accordingly



## **Innovation?**

- Approach to problem: site assessment, hazard ranking, ground investigation, design, construction
- Bio-engineering: several techniques
- Wall design and construction: masonry and gabion
- Drainage: roadside, wall, slope
- Manuals: Comprehensive manuals written in Lao and English



# **SEACAP 21/003**

....

# **Mainstreaming Slope Stability Outcomes**



What are the aims of the project?

The objectives are:

- To integrate the SEACAP 21 outputs into the core engineering courses of the National University of Laos
- To field trial the SEACAP 21 approaches, design manuals and specifications within MPWT

## NUoL

- Review and assess undergraduate engineering core curriculum
- Recommend revisions as necessary
- Draft outlines for potential undergraduate and graduate thesis studies, and any new relevant courses
- Include interested students and faculty members in the field trials

Scot+ Wilson

### **MPWT**

 Select six sites representing typical slope stability problems along Roads 13N and 7

- Field trial approaches, design manuals and specifications to preliminary design status
- Carry out in-service training for MPWT and provincial counterparts during survey and design activities







## **SEACAP 21**

# **END OF PRESENTATION**