

## EXHIBIT LIST

Reference No: HOL/10024

Petitioner: Buckinghamshire Standard Pack

Published to Collaboration Area: Tuesday 18-Oct-2016

Page 1 of 58

No	Exhibit Name	Page
1	<a href="#">P3767 Overview Traffic Assessment</a>	2 - 19
2	<a href="#">P3768 Strategic traffic maps</a>	20 - 22
3	<a href="#">P3769 Rainbow traffic maps</a>	23 - 30
4	<a href="#">P3770 CFA 7 Colne Valley daily weekday flows</a>	31
5	<a href="#">P3771 CFA 8 Chalfonts and Amersham daily weekday flows</a>	32 - 35
6	<a href="#">P3772 CFA 9 Central Chilterns daily weekday flows</a>	36 - 39
7	<a href="#">P3773 CFA 10 and 11 weekday flows</a>	40 - 46
8	<a href="#">P3774 CFA 12 Waddesdon and Quainton daily weekday flows</a>	47 - 49
9	<a href="#">P3775 CFA 13 and 14 daily weekday flows</a>	50 - 54
10	<a href="#">P3776 Traffic Management Plan</a>	55 - 58





# Traffic Assessment Overview

---

June 2016



# Transport Assessment (TA) methodology (1)

---

The TA calculates traffic and transport impacts of the Proposed Scheme during construction and operation; traffic and transport *significant effects*<sup>1</sup> are reported in the Environmental Statement (ES)

Key traffic and transport impacts principally arise from construction activities (eg diversions, construction traffic and workforce), compared with a forecast baseline (ie without HS2), which includes committed and planned development

<sup>1</sup> *Significant effects* are defined in the HS2 Phase One Scope and methodology report (CT-001-000/1), November 2013



# Transport Assessment (TA) methodology (2)

---

The following traffic and transport effects have been assessed in the ES:

- traffic flows and delays to vehicle occupants
- pedestrians, cyclists and equestrians severance, delay, amenity and ambience
- public transport delay
- disruption at stations/interchanges
- parking and loading
- accidents and safety
- severance
- waterways.



# Transport Assessment (TA) methodology(3)

---

For consistency, the TA generally assumes a 2021 forecast baseline for the whole Phase One route.

The operation assessments have been carried out for the forecast years of 2026 and 2041 (year of opening plus 15 years).

The forecasts for construction and operation years use strategic models, or DfT standard growth factors, to take account of growth.

The assessments have been carried out for AM (0800-0900) and PM (1700-1800) peak periods, which are typically the busiest times of the day - it does not assume that impacts only occur at this time.



# Transport Assessment (TA) methodology (4)

---

The DfT PLANET demand model has been used to forecast the change in passenger demand at rail stations arising from the operation of HS2.

In the London, Birmingham Interchange and Birmingham Metropolitan areas, where the interactions of transport user behaviour are complex, existing strategic transport models have been used to assess the changes to highway and public transport flows and delays.

The strategic transport models have been developed and used in close collaboration with local transport authorities and inputs agreed with them.

Local junction models have been developed and used in consultation with the relevant highway authority to assess changes to vehicle delays in more detail.



# The TA construction assumptions (1)

---

The TA makes a number of assumptions that are precautionary and based on a realistic worst case; in practice, the impacts are likely to be less than assessed:

- the assessment is based on average daily trips for the peak month of construction activity; for most of the time the actual number of construction trips will be lower than this peak
- all compounds are generally assumed to be in use at the same time; in practice concurrent use will be less frequent
- all the workforce for sites outside of London is assumed to travel to/from the construction compounds by car; however, some of the workforce will use public transport, works buses or other methods
- 50% of the workforce is assumed to arrive between 0800-0900 and depart 1700-1800, overlapping with construction traffic; in practice, most of the workforce is likely to arrive/depart outside these times
- transport of excavated material (mass haul) to/from compounds by road is based on an eight hour day (outside London), for five days each week; in general, core working hours will be 0800 to 1800 on weekdays and 0800 to 1300 on Saturdays



# The TA construction assumptions (2)

---

The assessment:

- does not take into account other potential mitigation such as further opportunities that may arise to remove excavated material by rail at Euston and Langley, and also increased removal by rail at West Ruislip;
- does not include time and capacity controls as set out in Schedule 17 of the Bill;
- excludes measures arising from the implementation of the Code of Construction Practice (CoCP) and any construction workforce travel plan.



# Traffic and Transport exhibits

---

The traffic exhibits are produced to show the routeing and number of construction vehicles along the road network that are generated by the construction of the HS2 scheme.

Where required, exhibits showing other transport impacts have also been produced for certain locations, such as pedestrian and cycle diversions and maps showing road closures

The standard set of traffic exhibits normally comprises:


- access to strategic road network map;
- construction compound routes and vehicle numbers map;
- daily weekday traffic flows construction phase map;
- construction traffic histogram for specific locations.



# Sample traffic exhibits:

## Access to strategic road network


The sample map shows the strategic road network used by construction vehicles (>7.5t), along with the HS2 railway alignment and relevant locations, together with features of the HS2 route





# Sample traffic exhibits:


## Construction compound routes and vehicle trip generation (1)





## Sample traffic exhibits:


Daily weekday traffic flows construction phase (1)





# Sample traffic exhibits:

## Construction traffic histogram (1)





# Mitigation of traffic impacts during construction (1)

---

It is in the Promoter's interest to reduce delays and congestion, as this will also affect HS2 construction traffic.

HS2 has used physical measures to mitigate construction traffic impacts:

- road closures have been avoided by the use of off-line replacements, where practical and necessary, in locations where the HS2 railway crosses existing infrastructure
- use of the HS2 railway trace as a haul road in non-tunnelled areas, where practical
- specific highway improvements at junctions to reduce congestion and delays
- specific highway improvements to address existing road safety issues
- proposed temporary highway measures (eg temporary slip roads from M25 to Colne Valley compounds)



# Mitigation of traffic impacts during construction (2)

---

Operational measures to mitigate construction traffic impacts include:

- use of routes with the most direct access to the strategic road network, where practicable, and approval of routes for large good vehicles by the local highway authority
- Provision of specific assurances, where necessary, to limit construction traffic flows in specific locations
- provision of overnight workforce accommodation at the main construction compounds, where appropriate
- traffic management arrangements, as identified in the draft CoCP including:
  - Local Traffic Management Plans (LTMPs)
  - implementation of site specific measures
  - workforce travel plans



# Local Traffic Management Plans (LTMPs)

---

A draft Route-Wide Traffic Management Plan (RTMP) has been produced which sets out the scope for the LTMPs – it has been developed in consultation with highway authorities, within the Highways Sub Group of the HS2 Planning Forum.

The draft RTMP includes 'Construction Logistics and Cycle Safety (CLOCS)' standards for driver and vehicle safety, to manage work related road risk for vulnerable road users (cyclist and pedestrians) and the 'Freight Operation Registration Scheme (FORS)', where operators are subject to audit to ensure that they meet a number of quality standards in fleet operations around management, operations, vehicles and drivers.

LTMPs will initially be drafted by HS2 and completed by the final contractors - they will include the proposed traffic and construction vehicle management strategy.



# Traffic Management Site Specific Measures

---

Traffic Management sites specific measures as set out in the draft CoCP include:

- phasing of works
- road traffic management layouts and signage
- timing of operations
- arrangements for liaison with the relevant highway authorities and emergency services
- monitoring of vehicles arriving and leaving construction compounds
- emergency access protocols
- proposals for transport of construction workforce and measures to ensure safe access to and from site
- parking controls
- use of internal haul roads for construction vehicles to minimise the need to use public roads
- monitoring for deviation from authorised routes
- requirements relating to the movement of traffic from business and commercial operators of road vehicles, including goods vehicles
- measures for highway reinstatement
- a list of roads that may be used by construction traffic in the vicinity of the site, including any restrictions to construction traffic on these routes, such as the avoidance of large goods vehicles operating adjacent to schools during drop off and pick-up periods, where necessary



# Workforce travel plans

---

Construction workforce travel plans will be prepared by the lead contractors with the aim of encouraging the use of sustainable modes of transport to reduce the impact of workforce travel on local residents and businesses.

The plans will include:

- key issues to consider for each compound/ construction site or group of sites
- site activities and surrounding transport network including relevant context plans
- anticipated workforce trip generation and how it may change during the construction process
- travel mitigation measures that will be introduced to reduce the impact of construction workforce on the transport network
- targets to reduce individual car journeys for the construction workers



# Further engagement

---

Prior to commencement of main construction works, and during the construction phase, regular local Traffic Liaison Group (TLG) meetings will be established with local highway authorities so that matters such as local traffic management schemes can be reviewed prior to submission, or approval, and the implementation of schemes reviewed and other monitoring reported.


Proposed attendees at the TLG meetings include HS2 traffic manager, relevant local highway authority, the police and local bus operator representative.

HS2 Ltd has liaised with stakeholders, where further work is required eg:


- Saltley Viaduct Strategy, Birmingham
- A46/ A452 assessment, Warwickshire
- A413 access road, Great Missenden
- Ickenham study, Hillingdon



## CONSTRUCTION - ACCESS TO STRATEGIC ROAD NETWORK RUISLIP TO SOUTH HEATH



Legends/Notes:

- - - - - Rail alignment (tunnel section)  
 Vent Shaft  
 ————— Rail alignment (open section)  
 - - - - - Construction traffic route




Creator/Originator	
--------------------	--


Atkins

—HOL/10024/0020










Legends/Notes:

- Rail alignment (tunnel section)
- ⬇ Vent Shaft
- Rail alignment (open section)
- — — — Construction traffic route



-HOL/10024/0022




Colne Valley viaduct satellite compound	
Start Date	2018
Duration of Use	3 years 9 months
Duration of Busy Movements	40 months
Peak daily vehicles Cars & LGV	10-20
Peak daily vehicles HGV	10-20

Colne Valley viaduct and south embankment satellite compound/Ickenham auto-transformer feeder station satellite compound	
Start Date	2018
Duration of Use	6 years 6 months
Duration of Busy Movements	11 months
Peak daily vehicles Cars & LGV	90-140
Peak daily vehicles HGV	40-60

Breakspear Road South underbridge satellite compound	
Start Date	2017
Duration of Use	18 months
Duration of Busy Movements	6 months
Peak daily vehicles Cars & LGV	15-20
Peak daily vehicles HGV	150-200

West Ruislip portal satellite compound	
Start Date	2017
Duration of Use	7 years
Duration of Busy Movements	1 year 6 months
Peak daily vehicles Cars & LGV	22-30
Peak daily vehicles HGV	225-300



Northolt tunnel and earthworks main compound	
Start Date	2017
Duration of Use	10 years
Duration of Busy Movements	9 months
Peak daily vehicles Cars & LGV	102-136
Peak daily vehicles HGV	720-770


Harvil Road realignment satellite compound	
Start Date	2017
Duration of Use	5 years
Duration of Busy Movements	1 year
Peak daily vehicles Cars & LGV	8-10
Peak daily vehicles HGV	75-100

HS2 has provided an assurance to the London Borough of Hillingdon to look at options to reduce the number of HGV construction vehicles on Swakeleys Road. This could mean that the peak daily HGVs movements would be lower than as set out in the construction compound tables.

Compound traffic routes indicated on this map only refer to those compounds included within the area shown and do not indicate routes to compounds within adjacent sections of the proposed scheme.

- Legend**
- Construction compounds
  - Route in tunnel
  - Mass haul traffic route
  - Route on surface
  - Compound traffic routes
  - Routes to compounds shown on Colne Valley CFA 7 map

Description Key	
Start Date	Indicative start/set up date.
Duration of Use	Estimated duration of use (years).
Duration of Busy Movements	Estimated duration with busy vehicle movements (months).
Peak daily vehicles Cars & LGV	Average daily combined two-way vehicle trips during busy period and within peak month of activity.
Peak daily vehicles HGV	



High Speed Two South Ruislip to Ickenham CFA6 / Colne Valley CFA7 Construction Compound Routes and Vehicle Numbers	
Petitioner	
Petition number	

**hs2**

Registered in England. Registration number 06791686.  
Registered office: One Canada Square, London E14 5AB.  
Ordnance Survey Licence Number 100049190.  
This material was last updated on [date] and may not be copied, distributed, sold or published without the formal permission of Land Registry and Ordnance Survey. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes. © Crown Copyright Ordnance Survey. This is not a copy of a title plan issued by L.R.

Scale at A3: 1:30,000

0 250 500 750 1,000 Metres

Doc Number: C222-ATK-EV-DPL-020-300001-PET000000





Chiltern tunnel main compound(civil engineering)/Chiltern tunnel south portal (rail systems)	
Start Date	2017
Duration of Use	8 Years
Duration of Busy Movements	17 Months
Peak daily vehicles Cars & LGV	350-430
Peak daily vehicles HGV	490-1050

Colne Valley viaduct laydown satellite compound	
Start Date	2019
Duration of Use	2 Years 3 Months
Duration of Busy Movements	26 Months
Peak daily vehicles Cars & LGV	10-20
Peak daily vehicles HGV	10-20

Colne Valley viaduct main compound	
Start Date	2017
Duration of Use	5 Years 3 Months
Duration of Busy Movements	47 Months
Peak daily vehicles Cars & LGV	70-120
Peak daily vehicles HGV	10-20

Colne Valley viaduct jetty storage satellite compound	
Start Date	2018
Duration of Use	2 Years 9 Months
Duration of Busy Movements	29 Months
Peak daily vehicles Cars & LGV	10-20
Peak daily vehicles HGV	10-20

Routes shown are HGV routes only.

Compound traffic routes indicated on this map only refer to those compounds included within the area shown and do not indicate routes to compounds within adjacent sections of the proposed scheme.

Large Good Vehicles will use North Orbital Road / A412 Denham Way as a construction route prior to the construction of the M25 slip roads, with the purpose of the construction of these, as well as undertaking preparatory site works for compounds in the Colne Valley area. Following the construction of the M25 slip roads Large Goods Vehicles will only use North Orbital Road / A412 Denham Way to access the Colne Valley viaduct jetty storage and Colne Valley viaduct storage satellite compounds, as per the assurance provided to Buckinghamshire County Council.

Harefield Hospital

Harefield

Breakspear Road South underbridge satellite compound

West Ruislip portal satellite compound

Colne Valley viaduct and south embankment satellite compound / Ickeham auto-transformer feeder station satellite compound

Northholt tunnel and earthworks main compound

Harvil Road realignment satellite compound

Chalfont St Peter vent shaft satellite compound

Temporary slip roads to/from M25 for construction traffic

Chalfont Lane

Maple Cross

A412 North Orbital Road

Denham

A413

A40

M40

#### Colne Valley viaduct north embankment satellite compound

Start Date	2017
Duration of Use	4 Years
Duration of Busy Movements	14 Months
Peak daily vehicles Cars & LGV	210-260
Peak daily vehicles HGV	10-20

#### Colne Valley viaduct north launch satellite compound

Start Date	2017
Duration of Use	2 Years 9 Months
Duration of Busy Movements	23 Months
Peak daily vehicles Cars & LGV	50-60
Peak daily vehicles HGV	50-60

#### Colne Valley viaduct storage satellite compound


Start Date	2017
Duration of Use	3 Years 9 Months
Duration of Busy Movements	41 Months
Peak daily vehicles Cars & LGV	50-60
Peak daily vehicles HGV	20-30

#### Legend

- Construction compounds
- Route in tunnel
- Route on surface
- Mass haul traffic route
- Compound traffic routes
- Routes to compounds shown on South Ruislip to Ickenham CFA6, Colne Valley CFA7 and The Chalfonts and Amersham CFA8
- Large Good Vehicles route pre M25 slip road construction

#### Description Key

Start Date	Indicative start/set up date.
Duration of Use	Estimated duration of use (years).
Duration of Busy Movements	Estimated duration with busy vehicle movements (months).
Peak daily vehicles Cars & LGV	Average daily combined two-way vehicle trips during busy period and within peak month of activity.
Peak daily vehicles HGV	



High Speed Two Colne Valley CFA 7 Construction Compound Routes and Vehicle Numbers

Petitioner

Petition number



Registered in England. Registration number 06791686.  
Registered office: One Canada Square, London E14 5AB.  
Ordnance Survey Licence Number 100049190.  
This material was last updated on (date) and may not be copied, distributed, sold or published without the formal permission of Land Registry and Ordnance Survey. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes. © Crown Copyright Ordnance Survey. This is not a copy of a title plan issued by L.R.

HS2 Ltd accept no responsibility for any circumstances, which arise from the reproduction of this map after alteration, amendment or abbreviation or if it is issued in part or issued incomplete in any way.


Scale at A3: 1:30,000



Doc Number: C222-ATK-EV-DPL-020-300002-PET000000

Date: 10/02/2024





Little Missenden vent shaft satellite compound	
Start Date	2018
Duration of Use	6 Years 6 Months
Duration of Busy Movements	3 Months
Peak daily vehicles Cars & LGV	20-30
Peak daily vehicles HGV	210-220

Chalfont St Peter vent shaft satellite compound	
Start Date	2018
Duration of Use	7 Years
Duration of Busy Movements	10 Months
Peak daily vehicles Cars & LGV	80 - 90
Peak daily vehicles HGV	20 - 30


Amersham vent shaft satellite compound	
Start Date	2018
Duration of Use	6 Years 6 Months
Duration of Busy Movements	3 Months
Peak daily vehicles Cars & LGV	Up to 30
Peak daily vehicles HGV	Up to 190

Chalfont St Giles vent shaft satellite compound	
Start Date	2018
Duration of Use	7 Years
Duration of Busy Movements	17 Months
Peak daily vehicles Cars & LGV	80 - 110
Peak daily vehicles HGV	20 - 40

Compound traffic routes indicated on this map only refer to those compounds included within the area shown and do not indicate routes to compounds within adjacent sections of the proposed scheme

- Legend**
- Construction compounds
  - Route in tunnel
  - Mass haul traffic route
  - Route on surface
  - Compound traffic routes

Description Key	
Start Date	Indicative start/set up date.
Duration of Use	Estimated duration of use (years).
Duration of Busy Movements	Estimated duration with busy vehicle movements (months).
Peak daily vehicles Cars & LGV	Average daily combined two-way vehicle trips during busy period and within peak month of activity.
Peak daily vehicles HGV	



High Speed Two  
The Chalfonts and Amersham CFA8  
Construction Compound Routes  
and Vehicle Numbers

Petitioner


Petition number



Registered in England. Registration number 06791686.  
Registered office: One Canada Square, London E14 5AB.  
© Crown copyright and database rights 2015.  
Ordnance Survey Licence Number 100049190.  
This material was last updated on 25/05/16 and may not be copied, distributed, sold or published without the formal permission of Land Registry and Ordnance Survey. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes. © Crown Copyright Ordnance Survey.  
This is not a copy of a title plan issued by Lf.

HS2 Ltd accept no responsibility for any circumstances, which arise from the reproduction of this map after alteration, amendment or abbreviation or if it is issued in part or issued incomplete in any way.

Scale at A3: 1:30,000



Doc Number: C222-ATK-EV-DPL-020-300003-PET000000


HOL/10024/0025



Bowood Lane overbridge satellite compound	
Start Date	2018
Duration of Use	2 Years
Duration of Busy Movements	18 Months
Peak daily vehicles Cars & LGV	90 - 130
Peak daily vehicles HGV	20 - 30

Leather Lane overbridge satellite compound (civil engineering) / South Heath MPATS (rail systems)		
Start Date	2017	2023
Duration of Use	1 Year 3 Months	1 Year 1 Month
Duration of Busy Movements	14 Months	11 Months
Peak daily vehicles Cars & LGV	90-120	80-110
Peak daily vehicles HGV	<10	30-50

Chesham Road vent shaft satellite compound	
Start Date	2019
Duration of Use	6 Years 11 Months
Duration of Busy Movements	4 Months
Peak daily vehicles Cars & LGV	80 - 90
Peak daily vehicles HGV	180 - 220




Compound traffic routes indicated on this map only refer to those compounds included within the area shown and do not indicate routes to compounds within adjacent sections of the proposed scheme.

Chiltern tunnel north portal (civil engineering) / (railway systems)		
Start Date	2017	2023
Duration of Use	4 Years 9 Months	2 Years
Duration of Busy Movements	29 Months	
Peak daily vehicles Cars & LGV	150 - 210	
Peak daily vehicles HGV	70 - 230	

Little Missenden vent shaft satellite compound	
Start Date	2018
Duration of Use	6 Years 6 Months
Duration of Busy Movements	3 Months
Peak daily vehicles Cars & LGV	20 - 30
Peak daily vehicles HGV	210 - 220

- Legend**
- Construction compounds
  - Route in tunnel
  - Mass haul traffic route
  - Route on surface
  - Compound traffic routes

Description Key	
Start Date	Indicative start/set up date.
Duration of Use	Estimated duration of use (years).
Duration of Busy Movements	Estimated duration with busy vehicle movements (months).
Peak daily vehicles Cars & LGV	Average daily combined two-way vehicle trips during busy period and within peak month of activity.
Peak daily vehicles HGV	



High Speed Two  
Central Chilterns CFA 9  
Construction Compounds Routes  
and Vehicle Numbers

Petitioner  
  
Petition number




Registered in England. Registration number 06791686.  
Registered office: One Canada Square, London E14 5AB.  
© Crown copyright and database rights 2015.  
Ordnance Survey Licence Number 100049190.  
This material was last updated on 27/04/16 and may not be copied, distributed, sold or published without the formal permission of Land Registry and Ordnance Survey. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes. © Crown Copyright Ordnance Survey.  
This is not a copy of a title plan issued by L.R.

HS2 Ltd accept no responsibility for any circumstances, which arise from the reproduction of this map after alteration, amendment or abbreviation or if it is issued in part or issued incomplete in any way.



Scale at A3: 1:30,000



Doc Number: C222-ATK-EV-DPL-020-300004-PET0000

HOL/10024/0026




B4009 Nash Lee Road overbridge satellite compound (civil engineering) / (rail systems)		
Start Date	2018	
Duration of Use	7 Years	
Duration of Busy Movements	15 Months	
Peak daily vehicles Cars & LGV	10-20	
Peak daily vehicles HGV	310-450	

Wendover green tunnel (north) satellite compound	
Start Date	2018
Duration of Use	2 Years 6 Months
Duration of Busy Movements	26 Months
Peak daily vehicles Cars & LGV	70-90
Peak daily vehicles HGV	40-50

Wendover green tunnel (south) satellite compound (civil engineering) / Wendover Green tunnel (south portal) satellite compound (rail systems)		
Start Date	2017	2023
Duration of Use	2 Years 9 Months	1 Year 3 Months
Duration of Busy Movements	32 Months	
Peak daily vehicles Cars & LGV	80-100	
Peak daily vehicles HGV	40-50	

Small Dean viaduct launch satellite compound	
Start Date	2018
Duration of Use	2 Years
Duration of Busy Movements	22 Months
Peak daily vehicles Cars & LGV	80-90
Peak daily vehicles HGV	20-30



Risborough Road satellite compound	
Start Date	2017
Duration of Use	3 Years
Duration of Busy Movements	19 Months
Peak daily vehicles Cars & LGV	140-190
Peak daily vehicles HGV	10-20

Small Dean viaduct main compound	
Start Date	2017
Duration of Use	4 Years 3 Months
Duration of Busy Movements	42 Months
Peak daily vehicles Cars & LGV	110-140
Peak daily vehicles HGV	10-20


Rocky Lane underbridge satellite compound (civil engineering) / Wendover auto-transformer station satellite compound (rail systems)	
Start Date	2018
Duration of Use	6 Years 9 Months
Duration of Busy Movements	20 Months
Peak daily vehicles Cars & LGV	30-90
Peak daily vehicles HGV	140-230

Wendover Dean viaduct satellite compound	
Start Date	2018
Duration of Use	2 Years
Duration of Busy Movements	19 Months
Peak daily vehicles Cars & LGV	40-50
Peak daily vehicles HGV	20-30

Compound traffic routes indicated on this map only refer to those compounds included within the area shown and do not indicate routes to compounds within adjacent sections of the proposed scheme.

- Legend**
- Construction compounds
  - Route in tunnel
  - Mass haul traffic route
  - Route on surface
  - Compound traffic routes

Description Key	
Start Date	Indicative start/set up date.
Duration of Use	Estimated duration of use (years).
Duration of Busy Movements	Estimated duration with busy vehicle movements (months).
Peak daily vehicles Cars & LGV	Average daily combined two-way vehicle trips during busy period and within peak month of activity.
Peak daily vehicles HGV	



High Speed Two  
Dunsmore, Wendover and Halton CFA10  
Compound Routes and Vehicle Numbers

Petitioner

Petition number

HS2 Ltd accept no responsibility for any circumstances, which arise from the reproduction of this map after alteration, amendment or abbreviation or if it is issued in part or issued incomplete in any way.

Registered in England. Registration number 06791686.  
Registered office: One Canada Square, London E14 5AB.  
© Crown copyright and database rights 2015.  
Ordnance Survey Licence Number 100049190.  
This material was last updated on 29/04/16 and may not be copied, distributed, sold or published without the formal permission of Land Registry and Ordnance Survey. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes. © Crown Copyright Ordnance Survey.  
This is not a copy of a title plan issued by L.R.

Doc Number: C222-ATK-EV-DPL-020-300005-PET000000

Scale at A3: 1:30,000




A41 Bicester Road Embankment main compound (civil engineering) / Putlowes auto-transformer station satellite compound (rail systems)	
Start Date	2017
Duration of Use	7 Years
Duration of Busy Movements	22 Months
Peak daily vehicles Cars & LGV	180-240
Peak daily vehicles HGV	10-20

Thame Valley viaduct satellite compound	
Start Date	2018
Duration of Use	2 Years 3 months
Duration of Busy Movements	21 Months
Peak daily vehicles Cars & LGV	110-150
Peak daily vehicles HGV	40-50

Compound traffic routes indicated on this map only refer to those compounds included within the area shown and do not indicate routes to compounds within adjacent sections of the proposed scheme.

A418 Oxford Road overbridge satellite compound (civil engineering) / Sedrup express feeder auto-transformer station satellite compound (rail systems)	
Start Date	2018
Duration of Use	6 Years 3 Months
Duration of Busy Movements	11 Months
Peak daily vehicles Cars & LGV	140-220
Peak daily vehicles HGV	20-40




A41 Bicester Road overbridge satellite compound	
Start Date	2017
Duration of Use	2 Years 9 Months
Duration of Busy Movements	11 Months
Peak daily vehicles Cars & LGV	30-50
Peak daily vehicles HGV	310-370

Princes Risborough to Aylesbury rail overbridge satellite compound (civil engineering + rail systems) / Princes Risborough to Aylesbury rail overbridge satellite compound (east and west) (rail systems)		
Start Date	2017	2018
Duration of Use	2 Years 6 Months	9 Months
Duration of Busy Movements	8 Months	
Peak daily vehicles Cars & LGV	100-120	
Peak daily vehicles HGV	10-20	

- Legend**
- Construction compounds
  - Route in tunnel
  - Mass haul traffic route
  - Route on surface
  - Compound traffic routes

Description Key	
Start Date	Indicative start/set up date.
Duration of Use	Estimated duration of use (years).
Duration of Busy Movements	Estimated duration with busy vehicle movements (months).
Peak daily vehicles Cars & LGV	Average daily combined two-way vehicle trips during busy period and within peak month of activity.
Peak daily vehicles HGV	



High Speed Two  
Stoke Mandeville and Aylesbury CFA 11 /  
Waddesdon CFA 12  
Construction Compound Routes and  
Vehicle Numbers

Petitioner

Petition number

**hs2**

Registered in England. Registration number 06791688.  
Registered office: One Canada Square, London E14 5AB.  
© Crown copyright and database right 2015.  
Ordnance Survey Licence Number 100049190.  
This material was last updated on 29/04/16 and may not be copied, distributed, sold or published without the formal permission of Land Registry and Ordnance Survey. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes. © Crown Copyright Ordnance Survey.  
This is not a copy of a title plan issued by L.R.

Scale at A3: 1:30,000

0 250 500 750 1,000 Metres

Doc Number: C222-ATK-EV-DPL-020-300006-PET000000

HOL/10024/0028



West Street overbridge main compound (civil engineering) / Calvert railhead main compound (rail systems) / IMD reception sidings satellite compound (rail systems)

Start Date	2016	2018
Duration of Use	6 Years 9 Months	8 Years
Duration of Busy Movements	24 Months	
Peak daily vehicles Cars & LGV	1030-1280	
Peak daily vehicles HGV	40-60	

School Hill green overbridge satellite compound (civil engineering + rail systems) / Aylesbury Link line satellite compound (rail systems)

Start Date	2016	2019
Duration of Use	7 Years 3 Months	1 Year 9 Months
Duration of Busy Movements	37 Months	
Peak daily vehicles Cars & LGV	220-300	
Peak daily vehicles HGV	30-40	

Station Road overbridge satellite compound

Start Date	2017
Duration of Use	2 Years 9 Months
Duration of Busy Movements	16 Months
Peak daily vehicles Cars & LGV	140-190
Peak daily vehicles HGV	<10

Woodlands Cutting satellite compound (civil engineering) / Quanton auto-transformer feeder station satellite compound (rail systems)

Start Date	2017
Duration of Use	7 Years
Duration of Busy Movements	14 Months
Peak daily vehicles Cars & LGV	130-180
Peak daily vehicles HGV	30-60


Compound traffic routes indicated on this map only refer to those compounds included within the area shown and do not indicate routes to compounds within adjacent sections of the proposed scheme.

Legend

- Construction compounds
- Mass haul traffic route
- Compound traffic routes
- - - Potential compound route for normal indivisible load only
- Route in tunnel
- Route on surface

Description Key

Start Date	Indicative start/set up date.
Duration of Use	Estimated duration of use (years).
Duration of Busy Movements	Estimated duration with busy vehicle movements (months).
Peak daily vehicles Cars & LGV	Average daily combined two-way vehicle trips during busy period and within peak month of activity.
Peak daily vehicles HGV	



High Speed Two  
Quanton CFA 12 / Calvert, Steeple  
Claydon and Twyford CFA 13  
Construction Compound Routes and  
Vehicle Numbers

Petitioner

Petition number




HS2 Ltd accept no responsibility for any circumstances, which arise from the reproduction of this map after alteration, amendment or abbreviation or if it is issued in part or issued incomplete in any way.

Registered in England. Registration number 06791686.  
Registered office: One Canada Square, London E14 5AB.  
Crown copyright and database rights 2015.  
Ordnance Survey Licence Number 100049190.  
This material was last updated on 29/04/16 and may not be copied, distributed, sold or published without the formal permission of Land Registry and Ordnance Survey. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes. © Crown Copyright Ordnance Survey.  
This is not a copy of a title plan issued by LRS.



Doc Number: C222-ATK-EV-DPL-020-300007-PET000000

Scale at A3: 1:30,000



HOL/10024/0029





Petitioner  
Petition number

**hs2**

Registered in England. Registration number 06791686.  
Registered office: One Canada Square, London E14 5AB.  
Ordnance Survey Licence Number 100049190.  
This material was last updated on 29/04/16 and may not be copied, distributed, sold or published without the formal permission of Land Registry and Ordnance Survey. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes. © Crown Copyright Ordnance Survey. This is not a copy of a title plan issued by LRO.

Scale at A3: 1:30,000

0 250 500 750 1,000 Metres

Doc Number: C222-ATK-EV-DPL-020-300008-PET000000

HOL/10024/0030





**DAILY WEEKDAY TRAFFIC FLOWS CONSTRUCTION PHASE**  
**COLNE VALLEY CFA7**




For Continuation Refer to Drawing C222-ATK-CL-DPL-020-309621-PET000000

Map labels include: M25 Junction 17, Chorleywood, NORTH ORBITAL ROAD, A412 DENHAM WAY, M25, Maple Cross, Chalfont Lane road closure during construction phase, West Hyde, Colne Valley viaduct main compound, Colne Valley viaduct north embankment satellite compound, Colne Valley viaduct laydown satellite compound, Colne Valley viaduct, A412 NORTH ORBITAL ROAD, TILEHOUSE LANE, Chiltern tunnel, Temporary M25 slip roads for construction access only, CHESHAM LANE, A413 AMERSHAM ROAD, Chalfont St Peter, DENHAM LANE, JOINERS LANE, Tilehouse Lane overbridge, Chiltern tunnel south portal satellite compound (Rail Installation) and Chiltern tunnel main Compound (Compound and Roadhead), Colne Valley viaduct north launch satellite compound, Harefield, Harefield Hospital, and various traffic flow labels (A, B, C, D, E, F, G, H, I, J).

Scale: METRES @ 1:20000

0 200 500 1000 2000

P00.1		—				<p>HS2 accepts no responsibility for any circumstances which arise from the reproduction of this document after alteration, amendment or abbreviation or if it is issued in part or issued incompletely in any way.</p>
						<p>© Crown Copyright and database right 2015. All rights reserved. Ordnance Survey Licence number 100049190</p>
						<p>© Crown Copyright material is reproduced with the permission of Land Registry under delegated authority from the Controller of HMSO.  This material was last updated on 2015 and may not be copied, distributed, sold or published without the formal permission of Land Registry. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes.</p>
						<p>Scale with caution as distortion can occur.</p>
	Description	Drawn	Checked	Con App	HS2 App	

 Temporary site access route / haul route  
 Construction traffic route  
 Temporary material stockpile



Zone	Country South	Project/Contract			Country South Design
Design Stage	DESIGN-FOR-PETITION	Discipline/Function			Construction and Logistics
Drawing Title	Colne Valley CFA7  Daily Weekday Traffic Flows  Construction Phase	Drawn	Checked	Approved	
		TD			
		Date	Scale	Size	
		29/04/2016	AS SHOWN	A3	
		Drawing No.			Rev.
		C222-ATK-CL-DPL-020-309620-PET000000			P02
		UOL/100001/00			


A412 Denham Way / North Orbital Road (between satellite compounds and Denham Green Lane)					
A	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	4285	290	4575	7%
	HGVs	108	11	120	10%
B	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	5146	494	5641	10%
	HGVs	131	14	145	11%
A412 Denham Way / North Orbital Road (north of satellite compounds)					
C	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	4285	291	4576	7%
	HGVs	108	48	156	44%
D	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	5146	496	5642	10%
	HGVs	131	50	181	39%
A412 Denham Way / North orbital Road					
E	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	5924	142	6067	2%
	HGVs	219	0	219	0%
F	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	5348	142	5491	3%
	HGVs	290	0	290	0%
M25 J17 to J16 (south of temp slip roads)					
G	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	57120	28	57148	0%
	HGVs	7384	523	7908	7%
H	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	52556	28	52585	0%
	HGVs	5671	523	6195	9%
M25 temp slip roads					
I	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	0	0	0	N/A
	HGVs	0	572	572	N/A
J	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	0	0	0	N/A
	HGVs	0	572	572	N/A

-HOL/10024/0031













P3770




# DAILY WEEKDAY TRAFFIC FLOWS CONSTRUCTION PHASE THE CHALFONTS AND AMERSHAM CFA8






Legends/Notes:


	Satellite construction compound		Temporary site access route / haul route
	Main construction compound		Construction traffic route
	Tunnel portal		Temporary material stockpile
	Rail alignment formation		
	Tunnels external extent		
	Rail alignment		
	Engineering earthworks		
	Landscape earthworks		
	Land potentially required during construction		



















U


P3772 (1)

Zone	Country South	Project/Contract		
Design Stage	DESIGN-FOR-PETITION	Country South Design		
Drawing Title	Central Chilterns CFA9  Daily Weekday Traffic Flows  Construction Phase	Discipline/Function	Construction and Logistics	
		Drawn	Checked	Approved
		IE		
		Date	Scale	Size
		27/04/2016	AS SHOWN	A3
		Drawing No.		
		C222-ATK-CL-DPL-020-309623-PET000000		
		Rev.		
		P02		



















# DAILY WEEKDAY TRAFFIC FLOWS CONSTRUCTION PHASE WENDOVER, DUNSMORE AND HALTON CFA10 / STOKE MANDEVILLE AND AYLESBURY CFA11



A413 (south of Dunsmore Lane)				
A	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	10097	174	10271
	HGVs	98	156	254
B	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	10112	174	10285
	HGVs	140	156	296
Rocky Lane				
C	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	662	111	773
	HGVs	3	143	146
D	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	603	112	715
	HGVs	3	143	146
Small Dean Lane				
E	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	55	120	175
	HGVs	1	31	31
F	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	66	120	186
	HGVs	0	31	31
A413 Nash Lee Road				
G	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	7171	175	7346
	HGVs	288	289	577
H	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	6924	175	7099
	HGVs	276	289	565
B4009 Nash Lee Road				
I	Eastbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	4746	110	4856
	HGVs	60	292	352
J	Westbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	4587	110	4697
	HGVs	41	292	334
A4010 Aylesbury Road / Risborough Road				
K*	Eastbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	7724	110	7834
	HGVs	75	73	148
L*	Westbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	7179	110	7289
	HGVs	78	73	151
A4010 Risborough Road (south of North Lee Lane)				
M	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	8084	46	8129
	HGVs	288	5	293
N	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	7870	46	7916
	HGVs	296	5	301
A4010 Risborough Road (south of bypass)				
O*	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	8084	1035	9118
	HGVs	288	10	298
P*	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	7870	996	8867
	HGVs	296	12	308
A4010 Risborough Road (north of bypass)				
Q***	Northbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	8084	1035	9118
	HGVs	288	0	288
R***	Southbound	2021 daily weekday	HS2	2021 daily flow plus HS2
	Cars & LGVs	7870	996	8867
	HGVs	296	0	296

\* HS2 flow inclusive of diverted traffic associated with the closure of Marsh Lane, requiring a diversion via North Lee Lane, the A4010 and Marsh Lane, and represents traffic flows prior to opening of the Stoke Mandeville Bypass.  
\*\* Potential infrequent (less than daily) HS2 HGV movements.

HS2 accepts no responsibility for any circumstances which arise from the reproduction of this document after alteration, amendment or abbreviation or if it is issued in part or issued incompletely in any way.

© Crown Copyright and database right 2015. All rights reserved. Ordnance Survey Licence number 100049190

© Crown Copyright material is reproduced with the permission of Land Registry under delegated authority from the Controller of HMSO.

This material was last updated on 2015 and may not be copied, distributed, sold or published without the formal permission of Land Registry. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes.

Scale with caution as distortion can occur.


- Legends/Notes:
- Satellite construction compound
  - Main construction compound
  - Tunnel portal
  - Rail alignment formation
  - Tunnels external extent
  - Rail alignment
  - Engineering earthworks
  - Landscape earthworks
  - Land potentially required during construction
  - Temporary site access route / haul route
  - Construction traffic route
  - Temporary material stockpile

Registered in England  
Registration No. 06791686  
Registered office:  
One Canada Square,  
London, E14 5AB


Creator/Originator  
Atkins

Zone	Country South	Project/Contract		
Design Stage	DESIGN-FOR-PETITION	Country South Design		
Drawing Title	Wendover, Dunsmore and Halton CFA10 / Stoke Mandeville and Aylesbury CFA11 Daily weekday traffic flows	Discipline/Function Environmental		
Construction Phase		Drawn	Checked	Approved
		TD		
		Date	Scale	Size
		29/04/2016	AS SHOWN	A3
		Drawing No.		Rev.
		C222-ATK-EV-DPL-020-310505-PET000000		P02























BCE

# F











A41 Bicester Road Embankment  
Main Compound and Putlowes  
Auto-transformer Station  
Satellite Compound  
(Compound and Roadhead)


A41 Bicester Road  
Overbridge

## Thame Valley Viaduct Satellite Compound













# Thame Valley Viaduct


A41 Bicester Road  
Overbridge  
Satellite Compound  
(Compound and Roadhead)

Waddesdon



Legends/Notes:


	Satellite construction compound		Temporary site access route / haul route
	Main construction compound		Construction traffic route
	Tunnel portal		Temporary material stockpile
	Rail alignment formation		
	Tunnels external extent		
	Rail alignment		
	Engineering earthworks		
	Landscape earthworks		
	Land potentially required during construction		



-HOL/10024/0047

A41 (east of Blackgrove Road)					
A	Eastbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	7151	118	7269	2%
	HGVs	1101	20	1122	2%
B	Westbound	2021 daily weekday	HS2	2021 daily flow plus HS2	% increase
	Cars & LGVs	7241	118	7359	2%
	HGVs	1132	20	1152	2%









Woodlands Cutting and Quanton  
Auto-transformer Feeder Station  
Satellite Compound


Quainton

## Station Road Overbridge


Edgcott Road  
Overbridge




Station Road  
Overbridge  
Satellite Compound

A map of the Station Road area. A green dashed line indicates the proposed bus lane running diagonally across the road. The text 'STATION ROAD' is written vertically along the road.



P00.1	—				<p>HS2 accepts no responsibility for any circumstances which arise from the reproduction of this document after alteration, amendment or abbreviation or if it is issued in part or issued incompletely in any way.</p> <p>© Crown Copyright and database right 2015. All rights reserved. Ordnance Survey Licence number 100049190</p> <p>© Crown Copyright material is reproduced with the permission of Land Registry under delegated authority from the Controller of HMSO.</p> <p>This material was last updated on 2015 and may not be copied, distributed, sold or published without the formal permission of Land Registry. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes.</p> <p>Scale with caution as distortion can occur.</p>
774 (3)	Description	Drawn	Checked	Con App	HS2 App

 Land potentially required during construction

 Temporary site access route / haul route  
 Construction traffic route  
 Temporary material stockpile



Registered In England  
Registration No. 06791686  
Registered office:  
One Canada Square,  
London, E14 5AB


Creator/Originator	
--------------------	--

Zone	Country South	Project/Contract			Country South Design
Design Stage	DESIGN-FOR-PETITION	Discipline/Function			Construction and Logistics
Drawing Title	Waddesdon and Quainton CFA12  Daily Weekday Traffic Flows  Construction Phase (Sheet 2 of 2)	Drawn	Checked	Approved	
		TD			
		Date	Scale	Size	
		29/04/2016	AS SHOWN	A3	
		Drawing No.			Rev.
		C222-ATK-CL-DPL-020-312011-PET000000			P02

—HOL/10024/0049

P3774 (3)






Country South	Project/Contract Country South Design		
DR-PETITION	Discipline/Function Construction and Logistics		
Steeple Claydon Code CFA13 Traffic Flows	Drawn IE	Checked	Approved
	Date 29/04/2016	Scale AS SHOWN	Size A3
	Drawing No. C222-ATK-CL-DPL-020-312012-PET000000		Rev. P02



# DAILY WEEKDAY TRAFFIC FLOWS CONSTRUCTION PHASE CALVERT, STEEPLE CLAYDON, TWYFORD AND CHETWODE CFA13 / NEWTON PURCELL TO BRACKLEY CFA14



Zone	Country South	Project/Contract			Country South Design
Design Stage	DESIGN-FOR-PETITION	Discipline/Function			Construction and Logistics
Drawing Title	Calvert, Steeple Claydon, Twyford and Chetwode CFA13 / Newton Purcell to Brackley CFA14  Daily Weekday Traffic Flows	Drawn  IE	Checked	Approved	
		Date  29/04/2016	Scale  AS SHOWN	Size  A3	
	Construction Phase	Drawing No.  C222-ATK-CL-DPL-020-313610-PET000000			Rev.  P02





Westbury

FULWELL ROAD

A421 London Road  
Overbridge

Finmere

Barton  
Hartshorn

A4421 Buckingham  
Road Overbridge  
Satellite Compound

## Westbury Viaduct

Westbury Viaduct  
Launch  
Satellite Compound


## Mixbury

A4421 Buckingham  
Road Overbridge










A421 London Road  
Overbridge  
Satellite Compound



Newton  
Purcell

The map shows a section of the A4421 road, which is labeled 'BUCKINGHAM ROAD'. A green line runs parallel to the road, and a red line runs perpendicular to it. Two study sites are marked: 'A' is located on the red line, and 'B' is located on the green line. The map also shows a street grid and a river.

A421 London Road

P00,1		—				<p>HS2 accepts no responsibility for any circumstances which arise from the reproduction of this document after alteration, amendment or abbreviation or if it is issued in part or issued incompletely in any way.</p> <p>© Crown Copyright and database right 2015. All rights reserved. Ordnance Survey Licence number 100049190</p> <p>© Crown Copyright material is reproduced with the permission of Land Registry under delegated authority from the Controller of HMSO.</p> <p>This material was last updated on 2015 and may not be copied, distributed, sold or published without the formal permission of Land Registry. Only an official copy of a title plan or register obtained from the Land Registry may be used for legal or other official purposes.</p> <p>Scale with caution as distortion can occur.</p>
775 (3)	Description	Drawn	Checked	Con App	HS2 App	

 Satellite construction compound  
 Main construction compound  
 Tunnel portal  
 Rail alignment formation  
 Tunnels external extent  
 Rail alignment  
 Engineering earthworks  
 Landscape earthworks  
 Land potentially required during construction

-  Temporary site access route / haul route
-  Construction traffic route
-  Temporary material stockpile



Registered In England  
Registration No. 06791686  
Registered office:  
One Canada Square,  
London, E14 5AB

Creator/Originator	
--------------------	--

Atkins


Zone	Country South	Project/Contract			Country South Design
Design Stage	DESIGN-FOR-PETITION	Discipline/Function			Construction and Logistics
Drawing Title	Newton Purcell to Brackley CFA14  Daily weekday traffic flows  Construction Phase - Sheet 1 of 2	Drawn  IE	Checked	Approved	
		Date 29/04/2016	Scale AS SHOWN	Size A3	
		Drawing No. C222-ATK-CL-DPL-020-314511-PET000000			Rev. P02

\*Temporary HGV movements should alternative access be unavailable.

—HOL/10024/0052

P3775 (3)








# DAILY WEEKDAY TRAFFIC FLOWS CONSTRUCTION PHASE NEWTON PURCELL TO BRACKLEY CFA14



Case - Sheet 2 of 2	Drawing No.	Rev.
	C222-ATK-CL-DPL-020-314521-PET000000	P02



Atkins

Zone	Country South	Project/Contract			Country South Design
Design Stage	DESIGN-FOR-PETITION	Discipline/Function			Construction and Logistics
Drawing Title	<p>Newton Purcell to Brackley CFA14</p> <p>Daily Weekday Traffic Flows</p> <p>Construction Phase - Sheet 2 of 2</p>	Drawn	Checked	Approved	
		IE			
		Date	Scale	Size	
		29/04/2016	AS SHOWN	A3	
		Drawing No.			Rev.
		C222-ATK-CL-DPL-020-314521-PET000000			P02



# Route-wide Traffic Management Plan

---

The CoCP will require the nominated undertaker to prepare a route-wide traffic management plan, in liaison with highway and traffic authorities and the emergency services, will include:

- the means of managing and monitoring lorry flows;
- the requirement for vehicle and driver safety;
- requirements for preparing workforce travel plans;
- the strategy for design and consultation for traffic management (including the signing strategy for emergency service access and lorry wayfinding); and
- the requirements for protecting highways.

A draft route-wide traffic management plan was consulted on with key stakeholders, including all highway authorities along the Phase One route, during 2015 and a final version has been prepared and published:

<https://www.gov.uk/government/publications/hs2-phase-one-route-wide-traffic-management-plan>

**HS2 Information Paper E13:** Management of Traffic during construction



# Local Traffic Management Plan

---

The CoCP will require the nominated undertaker to also prepare local traffic management plans, in liaison with the relevant highway and traffic authorities and the emergency services. As appropriate, these will include:

- the contractors' construction traffic flow assumptions;
- the local routes to be used by large goods vehicles (approved where applicable), including lorry holding areas; and
- significant works affecting roads and public rights of way, including temporary and permanent closures and diversions.

**HS2 Information Paper E13:** Management of Traffic during construction



# Vehicle flows and road safety management, monitoring and control

---

Construction vehicles and their impact on road safety will be managed, monitored and controlled by:

- a vehicle booking system;
- vehicle flow monitoring;
- vehicle identification;
- driver training in vulnerable road user awareness and rural road driving;
- requirements for vehicle safety equipment and blind spot minimisation;
- the implementation of fleet operator quality schemes; and
- the implementation of route and flow monitoring, including monitoring that
- the driver and vehicle safety requirements are being met.

**HS2 Information Paper E30:** Vehicle flow management and safety requirements during construction



# Monitoring of Compliance

---

Monitoring of compliance will be led by a dedicated monitoring and compliance team employed by the Nominated Undertaker.

The administrators of the vehicle booking system will review contractor performance and compliance with driver and vehicle safety, as well as ensuring that contractors comply with approved lorry routes and relevant undertakings and assurances.

In addition, the compliance team will ensure that HS2's policies and procedures are being adhered to.

**HS2 Information Paper E30:** Vehicle flow management and safety requirements during construction