

River Thames - river restriction- revision 04-03-14

Kingston Railway Bridge Between Teddington and Molesey Locks

October 2013 to April 2014

Maintenance Works to Kingston Railway Bridge

Works (Grit blasting, painting, brick and steel work repairs) are required as part of a planned maintaince program to the existing bridge structure. This will incorporate the building of fully sealed purpose built access scaffolding in the respective arches.

Scaffolding will encapsulate the span/arch in which work is being undertaken leaving those remaining arches where work is not being undertaken free to navigation. The works have been programmed to ensure that at least one of the three navigation spans/arches remains open to navigation throughout the program. The Middle arch will remain open to navigation throughout the works with restricted headway.

NOTE: Headway restricted by 1.71m over the central 10m in the Middle Arch.

Please follow directional signage, follow any directions given by the safety boat and/or officers of the Environment Agency and navigate slowly and with caution in the area of these works.

River Users are reminded that **boats going upstream must give way to boats coming downstream.**

NOTE: The visitor moorings on the upstream end of Kingston Wharf will be suspended for the duration of the works.

Matt Carter Harbourmaster 04 March 2014