

Summary of the project

Environmental Management Team
Offshore Petroleum Regulator for Environment & Decommissioning
AB1 Building
Wing C
Crimon Place
Aberdeen
AB10 1BJ

Independent Oil and Gas uk
Endeavour House
189 Shaftesbury Avenue
London WC2H 8JR
T: +44 (0) 2070 361 401
E: info@iog.co.uk

Date: 19/04/2021

BEIS ES reference Number: D/4257/2020

Dear Sir/Madam

THE OFFSHORE OIL AND GAS EXPLORATION, PRODUCTION, UNLOADING AND STORAGE (ENVIRONMENTAL IMPACT ASSESSMENT) REGULATIONS 2020 – Regulation 11

Summary of the project: P1915 – Southwark Pipeline Installation Project

I refer to the above-mentioned licence(s) and the potential Pipeline Installation project mentioned above.

An application for consent has been submitted to the Oil and Gas Authority (OGA) for the above project on 01/04/2021. The summary of the project is accompanied by a copy of the Environmental Statement (ES) for the Southwark Pipeline Installation Project.

The primary nature of this project will be for the installation of a single 24" pipeline between the existing Thames pipeline, and the Southwark platform and a summary of the project is provided below.

Location

- o The project location – Block numbers 49/21c and 49/26
- o The water depth at the proposed location – 22-34m
- o The distance to nearest UK coastline (km) - Norfolk, England - 52km
- o The distance to nearest international median line (km) – UK/Netherlands – 65km

Proposed activities

- o The proposal relates to a new project
- o The main elements of the project will comprise of:
 - A single 24" pipeline (PL4943), 5.67km long




- Seabed clearance and pipeline installation.
- Tie-in spools to allow tie-in to the existing Thames pipeline and the Southwark pipeline.
- Deposition of up to 200 concrete mattresses, nominally 100 at the Thames pipeline (PL370) tie-in and 100 at the Southwark Platform tie-in.
- Deposition of 2,900 grout bags, nominally 1,450 at the Thames pipeline tie-in and 1,450 at the Southwark Platform tie-in.

The project involves connection to the Southwark platform, and the existing Thames pipeline.

Timeline

The proposed timeline for the main project elements are as follows:

- Pre-lay surveys – November 2021
- Seabed preparation and pipeline installation - December 2021 – March 2022
- Tie-in operations – April 2021



HSE Manager