

High Speed Rail (Crewe – Manchester)

Supplementary Environmental Statement 2 and Additional Provision 2 Environmental Statement

Volume 5: Appendix LQ-001-00000

Land quality

Land quality report MA01: Hough to Walley's Green MA02: Wimboldsley to Lostock Gralam MA03: Pickmere to Agden and Hulseheath MA06: Hulseheath to Manchester Airport MA07: Davenport Green to Ardwick MA08: Manchester Piccadilly Station



High Speed Rail (Crewe – Manchester)

Supplementary Environmental Statement 2 and Additional Provision 2 Environmental Statement

Volume 5: Appendix LQ-001-00000

Land quality

Land quality report MA01: Hough to Walley's Green MA02: Wimboldsley to Lostock Gralam MA03: Pickmere to Agden and Hulseheath MA06: Hulseheath to Manchester Airport MA07: Davenport Green to Ardwick MA08: Manchester Piccadilly Station



High Speed Two (HS2) Limited has been tasked by the Department for Transport (DfT) with managing the delivery of a new national high speed rail network. It is a non-departmental public body wholly owned by the DfT.

High Speed Two (HS2) Limited Two Snowhill Snow Hill Queensway Birmingham B4 6GA

Telephone: 08081 434 434

General email enquiries: HS2enquiries@hs2.org.uk

Website: www.hs2.org.uk

A report prepared for High Speed Two (HS2) Limited:

ARUP+ ERM | FOSTER + PARTNERS | JACOBS



High Speed Two (HS2) Limited has actively considered the needs of blind and partially sighted people in accessing this document. The text will be made available in full on the HS2 website. The text may be freely downloaded and translated by individuals or organisations for conversion into other accessible formats. If you have other needs in this regard please contact High Speed Two (HS2) Limited.

© High Speed Two (HS2) Limited, 2023, except where otherwise stated.

Copyright in the typographical arrangement rests with High Speed Two (HS2) Limited.

This information is licensed under the Open Government Licence v3.0. To view this licence, visit www.nationalarchives.gov.uk/doc/ open-government-licence/version/3 **CCL** or write to the Information Policy Team, The National Archives, Kew, London TW9 4DU, or e-mail: psi@nationalarchives.gsi.gov.uk. Where we have identified any thirdparty copyright information you will need to obtain permission from the copyright holders concerned.



Printed in Great Britain on paper containing 100% recycled fibre.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Contents

1	Introduction		
	1.2	Scope of the assessment	5
2	Enga	gement	6
3	Risk	assessment	8
Par	t 1: S	upplementary Environmental Statement 2	10
Par	t 2: A	dditional Provision 2 Environmental Statement	11
	3.2	Baseline risk assessment	11
	3.3	Construction risk assessment	16
	3.4	Post-construction risk assessment	22
	3.5	Assessment of temporary (construction) and permanent (post-construction) effects	27

Tables

Table 1: Engagement on land quality issues undertaken for Hough to Walley's Green (MA01)	6
Table 2: Engagement on land quality issues undertaken for Wimboldsley to Lostock Gralam (MA02)	6
Table 3: Engagement on land quality issues undertaken for Pickmere to Agden and Hulseheath (MA03)	6
Table 4: Engagement on land quality issues undertaken for Hulseheath to Manchester Airport (MA06)	7
Table 5: Engagement on land quality issues undertaken for Davenport Green to Ardwick (MA07)	7
Table 6: Engagement on land quality issues undertaken for Manchester Piccadilly Station (MA08)	7
Table 7: Sites included in the risk assessment within the SES2 and AP2 ES study area	9
Table 8: Baseline CSM and qualitative risk assessment for freight terminal and former depots grouped for assessment (MA07-221, MA07-226 and MA07-229) (on-	
site)	11
Table 9: Baseline CSM and qualitative risk assessment for former depot and existing	
scrap yard grouped for assessment (MA07-165 and MA07-178) (on-site)	13
Table 10: Baseline CSM and qualitative risk assessment for petrol filling stations	
(MA06-209 and MA07-244) (off-site)	14

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Table 11: Construction CSM and qualitative risk assessment for freight terminal and former depots grouped for assessment (MA07-221, MA07-226 and MA07-229) (on-site)	16
Table 12: Construction CSM and qualitative risk assessment for former depot and existing scrap yard grouped for assessment (MA07-165 and MA07-178) (on-site)	18
Table 13: Construction CSM and qualitative risk assessment for petrol filling stations (MA06-209 and MA07-244) (off-site)	20
Table 14: Post-construction CSM and qualitative risk assessment for freight terminal and former depots grouped for assessment (MA07-221, MA07-226 and MA07-229) (on-site)	22
Table 15: Post-construction CSM and qualitative risk assessment for former depot and existing scrap yard grouped for assessment (MA07-165 and MA07-178) (on-site)	24
Table 16: Post-construction CSM and qualitative risk assessment for petrol filling stations (MA06-209 and MA07-244) (off-site)	25
Table 17: Freight terminal and former depots grouped for assessment (MA07-221, MA07-226 and MA07-229) (on-site) – significance of effect assessments	27
Table 18: Former depot and existing scrap yard grouped for assessment (MA07-165 and MA07-178) (on-site) – significance of effect assessment	30
Table 19: Petrol filling stations (MA06-209 and MA07-244) (off-site) – significance of effect assessment	32

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

1 Introduction

- 1.1.1 This report is an appendix to the land quality assessment which forms part of Volume 5 of the Supplementary Environmental Statement 2 (SES2) and Additional Provision 2 Environmental Statement (AP2 ES). It comprises:
 - a summary of engagement undertaken; and
 - detailed risk assessments associated with land contamination.
- 1.1.2 This appendix provides details of changes to the land quality assessment since the production of the High Speed Two (HS2) High Speed Rail (Crewe Manchester)
 Environmental Statement (ES) published in 2022¹ (the main ES), and the Supplementary
 Environmental Statement 1 (SES1) and Additional Provision 1 Environmental Statement (AP1 ES) also published in 2022².
- 1.1.3 This report is structured into two parts: Part 1 SES2, and Part 2 AP2 ES and covers the following community areas (CA):
 - Hough to Walley's Green (MA01);
 - Wimboldsley to Lostock Gralam (MA02);
 - Pickmere to Agden and Hulseheath (MA03);
 - Hulseheath to Manchester Airport (MA06);
 - Davenport Green to Ardwick (MA07); and
 - Manchester Piccadilly Station (MA08).
- 1.1.4 This appendix should be read in conjunction with:
 - the SES2 and AP2 ES Volume 2, Community Area reports; and
 - the Land quality baseline data report in Background Information and Data (BID) accompanying SES2 and AP2 ES³ (see BID LQ-002-00000 SES2 and AP2 ES).

environmental-statement-2-and-additional-provision-2-environmental-statement.

¹ High Speed Two Ltd (2022), High Speed Rail (Crewe – Manchester), *Environmental Statement*. Available online at: <u>https://www.gov.uk/government/collections/hs2-phase2b-crewe-manchester-environmental-statement</u>.

² High Speed Two Ltd (2022), High Speed Rail (Crewe – Manchester), *Supplementary Environmental Statement 1 and Additional Provision 1 Environmental Statement*. Available online at: <u>https://www.gov.uk/government/collections/hs2-phase-2b-crewe-manchester-supplementary-</u> <u>environmental-statement-1-and-additional-provision-1-environmental-statement</u>.

³ High Speed Two Ltd (2023), High Speed Rail (Crewe – Manchester), *Background Information and Data accompanying Supplementary Environmental Statement 2 and Additional Provision 2 Environmental Statement, Land quality baseline data*, BID LQ-002-00000 SES2 and AP2 ES. Available online at: https://www.gov.uk/government/collections/hs2-phase-2b-crewe-manchester-supplementary-

- 1.1.5 In addition, the main ES Volume 5, Appendices: LQ-001, and SES1 and AP1 ES Volume 5, Appendix: LQ-001-00000 should be referred to.
- 1.1.6 Maps referred to throughout this appendix are contained in the SES2 and AP2 ES Volume 5, Land quality Map Book: Map Series LQ-01 – Land Quality. Sites carried through to assessment are given a reference number (Site ID). In this report they are referred to as 'MA07-221' and in the maps they are referred to as '07-221'.
- 1.1.7 Further information regarding receptors in relation to each site or group of sites is set out in the SES2 and AP2 ES Land quality baseline data report (see BID LQ-002-00000 SES2 and AP2 ES³).
- 1.1.8 Minerals baseline data, information about Local Geological Sites and geological Sites of Special Scientific Interest (SSSI) and site visit records are also set out in the main ES BID and the SES2 and AP2 BID.
- 1.1.9 The Environmental Impact Assessment (EIA) Scope and Methodology Report (SMR)⁴, (see main ES, Volume 5, Appendix: CT-001-00001) should be referred to for details of the land quality assessment methodology.
- 1.1.10 The need for a number of corrections to the contents of the main ES and SES1 and AP1 ES have been identified. These are set out in report: Corrections to Volume 5 of the January 2022 Environmental Statement and the July 2022 Supplementary Environmental Statement 1 and Additional Provision 1 Environmental Statement, see SES2 and AP2 ES Volume 5, Appendix: CT-009-00000.
- 1.1.11 In order to differentiate between the original scheme and the subsequent changes, the following terms are used:
 - 'the original scheme' the Bill scheme submitted to Parliament in 2022, which was assessed in the main ES;
 - 'the SES1 scheme' the original scheme with any changes described in SES1 that are within the existing powers of the Bill;
 - 'the AP1 revised scheme' the original scheme as amended by SES1 changes and AP1 amendments;
 - 'the SES2 scheme' the original scheme with any changes described in SES1 (submitted in July 2022) and the SES2; and
 - 'the AP2 revised scheme' the original scheme as amended by SES1 and SES2 changes (as relevant) and AP2 amendments.

⁴ High Speed Two Ltd (2022), High Speed Rail (Crewe – Manchester), *Environmental Statement, Environmental Impact Assessment Scope and Methodology Report*, Volume 5, Appendix: CT-001-00001. Available online at: https://www.gov.uk/government/collections/hs2-phase2b-crewe-manchester-environmental-statement.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

1.2 Scope of the assessment

1.2.1 The scope of the assessment in this report is limited to SES2 design changes and AP2 amendments which are considered likely to introduce a new significant effect, remove a significant effect, or result in a materially different significant effect on land quality than reported in the main ES and SES1 and AP1 ES.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

2 Engagement

2.1.1 Table 1 to Table 6 set out the organisations that have been engaged with during the preparation of the land quality assessment of the SES2 scheme for each of the study areas⁵, the types of information that have been provided to the assessment team and any specific concerns raised.

Table 1: Engagement on land quality issues undertaken for Hough to Walley's Green (MA01)

Organisation	Method/dates of contracts	Information provided and/or specific concerns	
Cheshire East Council (CEC)	Email to CEC (15 August 2022)	Email enquiring about any additional land contamination datasets to inform further studies.	
	Email from CEC (15 September 2022)	Provision of requested data relating to land contamination.	

Table 2: Engagement on land quality issues undertaken for Wimboldsley to Lostock Gralam (MA02)

Organisation	Method/dates of contracts	Information provided and/or specific concerns	
Cheshire West and Chester Council (CWCC)	Email to CWCC (05 August 2022)	Email enquiring about any additional land contamination datasets to inform further studies.	
	Meeting (20 September 2022)	Meeting to discuss land contamination data provision and type and format of dataset that could be provided to inform AP2 baseline.	
	Email to CWCC (23 September 2022)	Email to confirm format of data.	
	Email from CWCC (04 October 2022)	Provision of requested data relating to land contamination.	

Table 3: Engagement on land quality issues undertaken for Pickmere to Agden and Hulseheath (MA03)

Organisation	Method/dates of contracts	Information provided and/or specific concerns		
Cheshire East Council (CEC)	Email to CEC (15 August 2022)	Email enquiring about any additional land contamination datasets to inform further studies.		
	Email from CEC (15 September 2022)	Provision of requested data relating to land contamination		
Cheshire West and Chester Council (CWCC)	Email to CWCC (05 August 2022)	Email enquiring about any additional land contamination datasets to inform further studies.		
	Meeting with CWCC (20 September 2022)	Meeting to discuss land contamination data provision and type and format of dataset that could be provided to inform AP2 baseline.		
	Email to CWCC (23 September 2022)	Email to confirm format of data.		
	Email from CWCC (04 October 2022)	Provision of requested data relating to land contamination.		

⁵ The study area is defined as the land required for the construction of the AP2 revised scheme plus a 250m buffer. In the case of groundwater abstractions, this buffer is increased to 1km.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Table 4: Engagement on land quality issues undertaken for Hulseheath to Manchester Airport(MA06)

Organisation	Method/dates of contracts	Information provided and/or specific concerns
Cheshire East Council (CEC)	Email to CEC (15 August 2022)	Email enquiring about any additional land contamination datasets to inform further studies.
	Email from CEC (15 September 2022)	Provision of requested data relating to land contamination.
Manchester City Council (MCC)	Email to MCC (18 August 2022)	Request for updated datasets in regard to land contamination following request in November 2020.
	Email from MCC (25 August 2022)	Response confirming no known changes regarding land contamination data.

Table 5: Engagement on land quality issues undertaken for Davenport Green to Ardwick (MA07)

Organisation	Method/dates of contracts	Information provided and/or specific concerns	
Manchester City Council (MCC)	Email to MCC (18 August 2022)	Request for updated datasets in regard to land contamination following request in November 2020.	
	Email from MCC (25 August 2022)	Response confirming no known changes regarding land contamination data.	

Table 6: Engagement on land quality issues undertaken for Manchester Piccadilly Station (MA08)

Organisation	Method/dates of contracts	Information provided and/or specific concerns
Manchester City Council (MCC)	Email to MCC (18 August 2022)	Request for updated datasets in regard to land contamination following request in November 2020.
	Email from MCC (25 August 2022)	Response confirming no known changes regarding land contamination data.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

3 Risk assessment

- 3.1.1 A four-stage process, comprising stages A to D, has been carried out in accordance with the methodology set out in the SMR⁴ in the main ES. At each stage, professional judgement has been used to check that the screening and assessment process is highlighting significant land contamination sites.
- 3.1.2 Stage A highlights potentially contaminative sites based on their potential impact. Sites with a moderate to high potential impact move through to stage B where they are assessed based on receptor proximity.
- 3.1.3 Sites with a high potential impact pass through stage B to detailed assessment irrespective of receptor proximity. Sites with a moderate potential impact and moderate to high receptor proximity also go through to detailed assessment.
- 3.1.4 For those sites which pass through stage B, a further detailed risk assessment (stages C and D) has been carried out.
- 3.1.5 The results of stage C are presented in three conceptual site models (CSM) as qualitative risk assessments covering baseline, construction and post-construction scenarios. Stage D then compares the risk of impact at construction and post-construction stages with the baseline to determine the change in risk and hence the potential for a significant effect.
- 3.1.6 Part 1: SES2 and Part 2: AP2 ES (Sections 3.2 to 3.5) present assessments for potentially contaminated sites which have passed through the screening process within the study area. For each site the following data are presented:
 - baseline risk assessment;
 - construction risk assessment;
 - post-construction risk assessment;
 - assessment of temporary (construction) effects; and
 - assessment of permanent (post-construction) effects.
- 3.1.7 The construction and post-construction risk assessments assume that appropriate mitigation has been undertaken and that the operation of the railway is in accordance with environmental legislation.
- 3.1.8 Where sites present a similar contamination risk, they have been grouped and considered together.
- 3.1.9 Where sites have been grouped together, only one CSM has been prepared for those sites.
- 3.1.10 The sites in the SES2 scheme and AP2 revised scheme study areas are listed in Table 7.
- 3.1.11 For clarity, 'on-site' in this document means 'within the land required for the construction of the SES2 scheme and AP2 revised scheme' and 'off-site' refers to 'land beyond this boundary, but within the study area'.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Table 7: Sites included in the risk assessment within the SES2 and AP2 ES study area

Site group	Site title (site ID) and land use class ⁶	SES2 or AP2 study area		
On-site				
Freight terminal and former depots	Freight terminal (MA07-221), Class 2 Former railway depot (MA07-226), Class 2 Former bus depot (MA07-229), Class 2	AP2		
Former depot and scrap yard ⁷	Former depot (MA07-165), Class 2 Scrap yard (MA07-178), Class 2	AP2		
Off-site				
Petrol filling stations	Petrol filling station (MA06-209), Class 3 Petrol filling station (MA07-244), Class 3	AP2		

- 3.1.12 Contaminant types included within the risk assessments are based on the Department of the Environment, Farming and Rural Affairs and Environment Agency (2002); Priority Contaminants Report CLR 8⁸. Although this report has been withdrawn by the Environment Agency, it remains technically valid and there has been no subsequent authoritative replacement.
- 3.1.13 The remainder of this section presents the risk assessment for the sites going through to stages C and D of the assessment. These sites are shown in the SES2 and AP2 ES Volume 5 Land Quality Map Book.
- 3.1.14 The following abbreviations are used in Table 8 to Table 16:
 - CoCP Code of Construction Practice;
 - PAH polycyclic aromatic hydrocarbons;
 - PCB polychlorinated biphenyls; and
 - PPE personal protective equipment.

 $^{^{\}rm 6}$ As defined by the SMR in the main ES.

⁷ Off-site sources from the original scheme which are now on-site sources for the AP2 revised scheme.

⁸ Department for Environment, Food and Rural Affairs and Environment Agency (2002), *Potential Contaminants for the Assessment of Land*, R&D Publication CLR8.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Part 1: Supplementary Environmental Statement 2

3.1.15 There are no sites taken through to detailed assessment for the SES2 scheme.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Part 2: Additional Provision 2 Environmental Statement

3.1.16 The screening process for the AP2 revised scheme has identified seven additional sites (MA07-221, MA07-226, MA07-229, MA07-165, MA07-178, MA06-209, MA07-244) are required to be taken through to detailed assessment.

3.2 Baseline risk assessment

Table 8: Baseline CSM and qualitative risk assessment for freight terminal and former depots grouped for assessment (MA07-221, MA07-226 and MA07-229) (on-site)

Source	Receptor	Pathway	Probability	Consequence	Risk at baseline phase
Potential contamination from former and current activities: contaminants primarily comprising metals, PAH, asbestos, fuel and	Existing site users – Workers in commercial/industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low
lubricating oils, petroleum		Inhalation of ground gases	Unlikely	Medium	Low
hydrocarbons. Potentially low levels of ground gas (methane, carbon dioxide).	Adjacent site users – Residents and workers in commercial/industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low
		Inhalation of ground gases	Unlikely	Medium	Low
	Controlled waters – groundwater	Leaching, vertical and lateral migration from	Low likelihood	Negligible	Very low

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at baseline phase
	Secondary Undifferentiated aquifer of the glacial till	contaminated soils and waters			
	Controlled waters – groundwater Principal aquifer of the Chester Formation and Collyhurst Sandstone Formation Secondary B aquifer of the Manchester Marls Formation	Leaching, vertical and lateral migration from contaminated soils and waters	Unlikely	Minor to medium	Very low to low
	Controlled waters – surface water Corn Brook	Lateral migration through groundwater	Unlikely	Minor	Very low
	Property receptors – buildings, foundations and services (existing and adjacent)	Direct contact with contaminated soils and waters	Low likelihood	Minor	Low
		Exposure to explosive gases	Unlikely	Medium	Low

Notes/assumptions:

• site assessed without construction of the AP2 revised scheme;

• see SES2 and AP2 BID document Table 15 for details of receptors for this group of sites;

• existing site users and adjacent site users in the receptor column refer to users at or near to the areas assessed;

• all receptors are applicable to all sites;

• Corn Brook is in culvert in the vicinity of the sites; and

• all sites are predominantly hardstanding at baseline.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Table 9: Baseline CSM and qualitative risk assessment for former depot and existing scrap yard grouped for assessment (MA07-165 and MA07-178) (on-site)

Source	Receptor	Pathway	Probability	Consequence	Risk at baseline phase
Potential contamination from former and current activities: contaminants primarily comprising heavy metals, asbestos, PAH,	Existing site users – Workers in commercial/industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Low likelihood	Medium	Moderate/low
petroleum and diesel range		Inhalation of ground gases	Unlikely	Medium	Low
hydrocarbons, lubricating oils. Potentially low levels of ground gas (methane and carbon dioxide).	Adjacent site users – Residents, and workers in commercial/industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Low likelihood to unlikely	Medium	Low to moderate/ low
		Inhalation of ground gases	Unlikely	Medium	Low
	Controlled waters – groundwater Secondary Undifferentiated aquifer of the glacial till	Leaching, vertical and lateral migration from contaminated soils and waters	Low likelihood	Negligible	Very low
	Controlled waters – groundwater Principal aquifer of the Chester Formation Secondary A aquifer of the Halesowen Formation	Leaching, vertical and lateral migration from contaminated soils and waters	Unlikely	Medium	Low

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at baseline phase
Property receptors – building foundations and services (existing and adjacent)	Property receptors – buildings, foundations and services (existing and adjacent)	Direct contact with contaminated soils and waters	Low likelihood	Minor	Low
		Exposure to explosive gases	Unlikely	Medium	Low

Notes/assumptions:

- site assessed without construction of the AP2 revised scheme;
- see SES2 and AP2 BID document Table 16 for details of receptors for this group of sites;
- existing site users and adjacent site users in the receptor column refer to users at or near to the areas assessed;
- sites identified as former sources for HB (offsite), now identified as on-site sources for AP2; and
- both sites are underlain by secondary undifferentiated glacial till. Principal aquifer of the Chester Formation underlies the former depot (MA07-165) and Secondary A aquifer of the Halesowen Formation underlies the existing scrap yard (MA07-178).

Table 10: Baseline CSM and qualitative risk assessment for petrol filling stations (MA06-209 and MA07-244) (off-site)

Source	Receptor	Pathway	Probability	Consequence	Risk at baseline phase
Residual contamination from former and current activities: contaminants primarily comprising petroleum and diesel range hydrocarbons,	Existing site users – Petrol station users and workers	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Low likelihood	Medium	Moderate/low

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at baseline phase
lead and methyl-tert butyl ether.	Adjacent site users –Residents, farm workers, walkers and workers in commercial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low
	Controlled waters – groundwater Secondary A aquifer of the glaciofluvial deposits	Leaching, vertical and lateral migration from contaminated soils and waters	Likely	Medium	Moderate
	Controlled waters – groundwater Secondary B aquifer of the Tarporley Siltstone Formation Principal Aquifer of the Wilmslow Sandstone Formation	Leaching, vertical and lateral migration from contaminated soils and waters	Low likelihood to likely	Minor to medium	Low to moderate
	Controlled waters – surface water Pigginshaw Brook and River Mersey	Lateral migration through groundwater Direct runoff from site	Low likelihood	Medium	Moderate/low
	Property receptors – buildings, foundations and services (existing and adjacent)	Direct contact with contaminated soils and waters	Low likelihood	Minor	Low
		Exposure to gases/vapours	Low likelihood	Medium	Moderate/low

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at baseline phase	
Notes/assumptions:						
• site assessed without constru	uction of the SES2 scheme;					
• see SES2 and AP2 BID docum	nent Table 17 for details of recepto	ors for this group of sites; and				
• existing site users and adjace	ent site users in the receptor colur	nn refer to users at or near to	the areas assessed.			

3.3 Construction risk assessment

Table 11: Construction CSM and qualitative risk assessment for freight terminal and former depots grouped for assessment (MA07-221, MA07-226 and MA07-229) (on-site)

Source	Receptor	Pathway	Probability	Consequence	Risk at construction phase
Potential contamination from former and current activities: contaminants primarily comprising heavy metals, PAH, asbestos, fuel and	Existing site users – Workers in commercial/industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low
lubricating oils, petroleum		Inhalation of ground gases	Unlikely	Medium	Low
and diesel range hydrocarbons. Potentially low levels of ground gas (methane, carbon dioxide).	Adjacent site users – Residents and workers in commercial/industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low
		Inhalation of ground gases	Unlikely	Medium	Low

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at construction phase
	Controlled waters – groundwater Secondary Undifferentiated aquifer of the glacial till	Leaching, vertical and lateral migration from contaminated soils and waters	Low likelihood	Negligible	Very low
	Controlled waters – groundwater Principal aquifer of the Chester Formation and Collyhurst Sandstone Formation Secondary B aquifer of the Manchester Marls Formation	Leaching, vertical and lateral migration from contaminated soils and waters	Low likelihood	Minor to medium	Low to moderate/low
	Controlled waters – surface water Corn Brook	Lateral migration through groundwater	Unlikely	Minor	Very low
Pr fc (e	Property receptors – buildings, foundations and services (existing and adjacent)	Direct contact with contaminated soils and waters	Low likelihood	Minor	Low
		Exposure to explosive gases	Unlikely	Medium	Low

Notes/assumptions:

• site investigation may be required for the utility corridor prior to construction of the AP2 revised scheme;

• sites which lie within the land required for construction of the AP2 revised scheme may require remediation;

• it is assumed the site will remain occupied during construction;

• remediation will be restricted to mitigation of land quality effects arising from the AP2 revised scheme;

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at construction phase		
 existing site users and adjace 	nt site users in the receptor colun	nn refer to users at or near to t	he areas assessed;				

• during construction, standard mitigation procedures are assumed to be implemented in accordance with the draft CoCP (main ES Volume 5, Appendix: CT-002-00000⁹). Construction workers have been excluded from assessment due to the use of PPE/risk management protocols and in accordance with the SMR; and

Table 12: Construction CSM and qualitative risk assessment for former depot and existing scrap yard grouped for assessment (MA07-165 and MA07-178) (on-site)

Source	Receptor	Pathway	Probability	Consequence	Risk at construction phase
Potential contamination from former and current activities: contaminants primarily comprising heavy metals, asbestos, PAH, petroleum	Existing site users – Workers in commercial/industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	N/A	N/A	N/A
and diesel range		Inhalation of ground gases	N/A	N/A	N/A

[•] while the draft CoCP will make it unlikely that there will be adverse consequences associated with construction e.g. the control of surface runoff and dust, it is considered that there may still be temporary minor adverse effects during the construction period from ground disturbance in these areas. The adoption of the draft CoCP generally results in a low to unlikely probability of a consequence, but in some cases the actual consequence may temporarily increase from that defined at baseline.

⁹ High Speed Two Ltd (2022), High Speed Rail (Crewe – Manchester), *Environmental Statement, Draft Code of Construction Practice*, Volume 5, Appendix: CT-002-00000. Available online at: <u>https://www.gov.uk/government/collections/hs2-phase2b-crewe-manchester-environmental-statement</u>.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at construction phase
hydrocarbons, lubricating oils. Potentially low levels of ground gas (methane and carbon dioxide).	Adjacent site users – Residents, and workers in commercial/industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Low likelihood to unlikely	Medium	Low to moderate/ low
		Inhalation of ground gases	Unlikely	Medium	Low
	Controlled waters – groundwater Secondary Undifferentiated aquifer of the glacial till	Leaching, vertical and lateral migration from contaminated soils and waters	Low likelihood	Negligible	Very low
	Controlled waters – groundwater Principal aquifer of the Chester Formation Secondary A aquifer of the Halesowen Formation	Leaching, vertical and lateral migration from contaminated soils and waters	Low likelihood	Medium	Moderate/low
	Property receptors – buildings, foundations and services (existing and adjacent)	Direct contact with contaminated soils and waters	Low likelihood	Minor	Low
		Exposure to explosive gases	Unlikely	Medium	Low
Notes/assumptions:					
• site investigation may be req	uired prior to construction of the	AP2 revised scheme;			

• sites which lie within the land required for construction of the AP2 revised scheme may require remediation;

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at construction phase
• it is assumed the site will rem	nain occupied during construction		•		

• remediation will be restricted to mitigation of land quality effects arising from the AP2 revised scheme;

- existing site users and adjacent site users in the receptor column refer to users at or near to the areas assessed;
- during construction, standard mitigation procedures are assumed to be implemented in accordance with the draft CoCP⁹. Construction workers have been excluded from assessment due to the use of PPE/risk management protocols and in accordance with the SMR; and
- while the draft CoCP will make it unlikely that there will be adverse consequences associated with construction e.g. the control of surface runoff and dust, it is considered that there may still be temporary minor adverse effects during the construction period from ground disturbance in these areas. The adoption of the draft CoCP generally results in a low to unlikely probability of a consequence, but in some cases the actual consequence may temporarily increase from that defined at baseline.

Table 13: Construction CSM and qualitative risk assessment for petrol filling stations (MA06-209 and MA07-244) (off-site)

Source	Receptor	Pathway	Probability	Consequence	Risk at construction phase
Residual contamination from former and current activities: contaminants primarily comprising petroleum and diesel range hydrocarbons, lead and methyl-tert butyl	Existing site users – Petrol station users and workers	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Low likelihood	Medium	Moderate/low
etner.	Adjacent site users –Residents, farm workers, walkers and workers in commercial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at construction phase
	Controlled waters – groundwater Secondary A aquifer of the glaciofluvial deposits	Leaching, vertical and lateral migration from contaminated soils and waters	Likely	Medium	Moderate
	Controlled waters – groundwater Secondary B aquifer of the Tarporley Siltstone Formation Principal Aquifer of the Wilmslow Sandstone Formation	Leaching, vertical and lateral migration from contaminated soils and waters Low likelihood to likely Minor to medium	Minor to medium	Low to moderate	
	Controlled waters – surface water Pigginshaw Brook and River Mersey	Lateral migration through groundwater Direct runoff from site	Low likelihood	Medium	Moderate/low
	Property receptors – buildings, foundations and services (existing and adjacent)	Direct contact with contaminated soils and waters	Low likelihood	Minor	Low
		Exposure to gases/vapours	Low likelihood	Medium	Moderate/low

Notes/assumptions:

• site investigation may be required prior to construction of the AP2 revised scheme;

• existing site users and adjacent site users in the receptor column refer to users at or near to the areas assessed;

• during construction, standard mitigation procedures are assumed to be implemented in accordance with the draft CoCP⁹. Construction workers have been excluded from assessment due to the use of PPE/risk management protocols and in accordance with the SMR; and

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at construction phase
 while the draft CoCP will make	ke it unlikely that there will be advo	erse consequences associated	with construction e.g. the cont	rol of surface runoff and dus	t, it is considered
that there may still be tempore	prary minor adverse effects during	the construction period from g	ground disturbance in these ar	eas. The adoption of the draf	ft CoCP generally
results in a low to unlikely pr	pobability of a consequence, but in	some cases the actual consequ	uence may temporarily increas	e from that defined at baseli	ne.

3.4 Post-construction risk assessment

Table 14: Post-construction CSM and qualitative risk assessment for freight terminal and former depots grouped for assessment (MA07-221, MA07-226 and MA07-229) (on-site)

Source	Receptor	Pathway	Probability	Consequence	Risk at post- construction phase
Potential contamination from former and current activities: contaminants primarily comprising heavy metals, PAH, asbestos, fuel and	Existing site users – Workers in commercial/ industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low
lubricating oils, petroleum		Inhalation of ground gases	Unlikely	Medium	Low
hydrocarbons. Potentially low levels of ground gas (methane, carbon dioxide).	Adjacent site users – Residents and workers in commercial/ industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at post- construction phase
		Inhalation of ground gases	Unlikely	Medium	Low
	Controlled waters – groundwater Secondary Undifferentiated aquifer of the glacial till	Leaching, vertical and lateral migration from contaminated soils and waters	Low likelihood	Negligible	Very low
	Controlled waters – groundwater Principal aquifer of the Chester Formation and Collyhurst Sandstone Formation Secondary B aquifer of the Manchester Marls Formation	Leaching, vertical and lateral migration from contaminated soils and waters	Unlikely	Minor to medium	Very low to low
	Controlled waters – surface water Corn Brook	Lateral migration through groundwater	Unlikely	Minor	Very low
	Property receptors – buildings, foundations and services (existing and adjacent)	Direct contact with contaminated soils and waters	Low likelihood	Minor	Low
		Exposure to explosive gases	Unlikely	Medium	Low
Notes/assumptions:					
 assumes construction works 	are complete and remediation ha	s been carried out where nece	ssary. No pathways are left ope	en; and	

• existing site users and adjacent site users in the receptor column refer to users at or near to the areas assessed.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Table 15: Post-construction CSM and qualitative risk assessment for former depot and existing scrap yard grouped for assessment (MA07-165 and MA07-178) (on-site)

Source	Receptor	Pathway	Probability	Consequence	Risk at post- construction phase
Potential contamination from former and current activities: contaminants primarily comprising heavy metals, asbestos, PAH, petroleum	Existing site users – Workers in commercial/industrial area Users of public realm	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low
and diesel range		Inhalation of ground gases	Unlikely	Medium	Low
hydrocarbons, lubricating oils. Potentially low levels of ground gas (methane and carbon dioxide).	Adjacent site users – Residents, and workers in commercial/industrial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low
		Inhalation of ground gases	Unlikely	Medium	Low
	Controlled waters – groundwater Secondary Undifferentiated aquifer of the glacial till	Leaching, vertical and lateral migration from contaminated soils and waters	Low likelihood	Negligible	Very low
	Controlled waters – groundwater Principal aquifer of the Chester Formation Secondary A aquifer of the Halesowen Formation	Leaching, vertical and lateral migration from contaminated soils and waters	Unlikely	Medium	Low

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at post- construction phase
	Property receptors – buildings, foundations and services (existing and adjacent)	Direct contact with contaminated soils and waters	Low likelihood	Minor	Low
		Exposure to explosive gases	Unlikely	Medium	Low

Notes/assumptions:

- assumes construction works are complete and remediation has been carried out where necessary. No pathways are left open;
- in the completed scheme MA07-165 will become grassland/habitat planting and MA08-178 will be released for future redevelopment use. The draft CoCP⁹ measures will apply equally to land used for construction and land used temporarily, for example, for site offices and works compounds. However, for temporary works land, risk assessment and remediation will only be designed for the temporary use, rather than any long-term post-construction use; and
- existing site users and adjacent site users in the receptor column refer to users at or near to the areas assessed.

Table 16: Post-construction CSM and qualitative risk assessment for petrol filling stations (MA06-209 and MA07-244) (off-site)

Source	Receptor	Pathway	Probability	Consequence	Risk at post- construction phase
Residual contamination from former and current activities: contaminants primarily comprising petroleum and diesel range hydrocarbons,	Existing site users – Petrol station users and workers	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Low likelihood	Medium	Moderate/low

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at post- construction phase
lead and methyl-tert butyl ether.	Adjacent site users –Residents, farm workers, walkers and workers in commercial area	Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters	Unlikely	Medium	Low
	Controlled waters – groundwater Secondary A aquifer of the glaciofluvial deposits	Leaching, vertical and lateral migration from contaminated soils and waters	Likely	Medium	Moderate
	Controlled waters – groundwater Secondary B aquifer of the Tarporley Siltstone Formation Principal Aquifer of the Wilmslow Sandstone Formation	Leaching, vertical and lateral migration from contaminated soils and waters	Low likelihood to likely	Minor to medium	Low to moderate
	Controlled waters – surface water Pigginshaw Brook and River Mersey	Lateral migration through groundwater Direct runoff from site	Low likelihood	Medium	Moderate/low
	Property receptors – buildings, foundations and services (existing and adjacent)	Direct contact with contaminated soils and waters	Low likelihood	Minor	Low
Notes/assumptions:		Exposure to gases/vapours	Low likelihood	Medium	Moderate/low
Notes/assumptions.					

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Source	Receptor	Pathway	Probability	Consequence	Risk at post- construction phase
assumes baseline conditions	s will not change at post-construct	ion; and			
• existing site users and adjace	ent site users in the receptor colu	mn refer to users within/near to	o the areas assessed.		

3.5 Assessment of temporary (construction) and permanent (postconstruction) effects

3.5.1 The significance of the effects of land contamination is assessed by comparing the difference in risk of each contaminant linkage at baseline to those at construction and at post-construction stages. This provides a way of assessing both the adverse and beneficial effects during construction and the post-construction period.

Table 17: Freight terminal and former depots grouped for assessment (MA07-221, MA07-226 and MA07-229) (on-site) – significance of effect assessments

Contaminant linkage	Baseline risk	Construction risk	Post-construction risk	Construction significance	Post-construction significance
Exposure of existing site users to contamination by direct contact, ingestion and inhalation of dusts and vapours from contaminated soils and waters.	Low	Low	Low	Neutral effect	Neutral effect

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Contaminant linkage	Baseline risk	Construction risk	Post-construction risk	Construction significance	Post-construction significance
Exposure of existing site users through inhalation of ground gases.	Low	Low	Low	Neutral effect	Neutral effect
Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters impacting adjacent site users.	Low	Low	Low	Neutral effect	Neutral effect
Exposure of adjacent site users through inhalation of ground gases.	Low	Low	Low	Neutral effect	Neutral effect
Lateral and vertical migration of mobile contamination to groundwater (glacial till – Secondary undifferentiated aquifer).	Very low	Very low	Very low	Neutral effect	Neutral effect
Lateral and vertical migration of mobile contamination to groundwater (Chester Formation and Collyhurst Sandstone Formation – Principal aquifer and Manchester Marls	Very low to low	Low to moderate/low	Very low to low	Neutral effect	Neutral effect

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Contaminant linkage	Baseline risk	Construction risk	Post-construction risk	Construction significance	Post-construction significance
Formation – Secondary B aquifer).					
Discharge of contaminants to surface water by lateral migration through groundwater and direct runoff from site (Corn Brook).	Very low	Very low	Very low	Neutral effect	Neutral effect
Exposure of property via direct contact to contaminated soils and waters.	Low	Low	Low	Neutral effect	Neutral effect
Exposure of property and underground structures/services to explosive gases.	Low	Low	Low	Neutral effect	Neutral effect
Overall significance				Neutral effect	Neutral effect
Notes/assumptions:					

Notes/assumptions:

• the significance column may report a range of outcomes for a site. The draft CoCP⁹ is designed to mitigate effects, and it is considered that only temporary minor adverse effects during the construction period will occur from ground disturbance;

• construction of the AP2 revised scheme at the site is related to utilities only and so it is assumed the site will remain occupied during construction; and

• it is assumed that existing properties will not be demolished during the construction stage.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Table 18: Former depot and existing scrap yard grouped for assessment (MA07-165 and MA07-178) (on-site) – significance of effect assessment

Contaminant linkage	Baseline risk	Construction risk	Post-construction risk	Construction significance	Post-construction significance
Exposure of existing site users to contamination by direct contact, ingestion and inhalation of dusts and vapours from contaminated soils and waters.	Moderate/low	N/A	Low	N/A	Minor beneficial effect
Exposure of existing site users through inhalation of ground gases.	Low	N/A	Low	N/A	Neutral effect
Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters impacting adjacent site users.	Low to moderate/low	Low to moderate/low	Low	Neutral effect	Minor beneficial effect
Exposure of adjacent site users through inhalation of ground gases.	Low	Low	Low	Neutral effect	Neutral effect
Lateral and vertical migration of mobile contamination to groundwater (glacial till – Secondary undifferentiated aquifer).	Very low	Very low	Very low	Neutral effect	Neutral effect

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Contaminant linkage	Baseline risk	Construction risk	Post-construction risk	Construction significance	Post-construction significance
Lateral and vertical migration of mobile contamination to groundwater (Chester Formation – Principal aquifer and Halesowen Formation – Secondary A Aquifer).	Low	Moderate/low	Low	Minor adverse effect	Neutral effect
Exposure of property via direct contact to contaminated soils and waters.	Low	Low	Low	Neutral effect	Neutral effect
Exposure of property and underground structures/services to explosive gases.	Low	Low	Low	Neutral effect	Neutral effect
Overall significance				Neutral to minor adverse effect	Neutral to minor beneficial effect
Notes/assumptions:					

• the significance column may report a range of outcomes for a site. The draft CoCP⁹ is designed to mitigate effects, and it is considered that only temporary minor adverse effects during the construction period will occur from ground disturbance;

• where human health receptors are no longer present during the construction and post-construction stages the risks are labelled as not applicable (N/A); and

• it is assumed that existing properties are demolished during the construction and post-construction stages and so risks to them have not been assessed.

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Table 19: Petrol filling stations (MA06-209 and MA07-244) (off-site) – significance of effect assessment

Contaminant linkage	Baseline risk	Construction risk	Post-construction risk	Construction significance	Post-construction significance
Exposure of existing site users to contamination by direct contact, ingestion and inhalation of dusts and vapours from contaminated soils and waters.	Moderate/low	Moderate/low	Moderate/low	Neutral effect	Neutral effect
Direct contact, ingestion, inhalation of dusts and vapours from contaminated soils and waters impacting adjacent site users.	Low	Low	Low	Neutral effect	Neutral effect
Lateral and vertical migration of mobile contamination to groundwater (glaciofluvial deposits – Secondary A aquifer).	Moderate	Moderate	Moderate	Neutral effect	Neutral effect
Lateral and vertical migration of mobile contamination to groundwater (Tarporley Siltstone Formation – Secondary B aquifer and Wilmslow Sandstone	Low to moderate	Low to moderate	Low to moderate	Neutral effect	Neutral effect

SES2 and AP2 ES Volume 5, Appendix: LQ-001-00000 Land quality MA01, MA02, MA03, MA06, MA07 and MA08 Land quality report

Contaminant linkage	Baseline risk	Construction risk	Post-construction risk	Construction significance	Post-construction significance
Formation – Principal Aquifer).					
Discharge of contaminants to surface water by lateral migration through groundwater and direct runoff from site (Pigginshaw Brook and River Mersey).	Moderate/low	Moderate/low	Moderate/low	Neutral effect	Neutral effect
Exposure of property via direct contact to contaminated soils and waters.	Low	Low	Low	Neutral effect	Neutral effect
Exposure of property and underground structures/services to explosive vapours/gases.	Moderate/low	Moderate/low	Moderate/low	Neutral effect	Neutral effect
Overall significance				Neutral effect	Neutral effect
Notes/assumptions:					
• the significance column may report a range of outcomes for a site. The draft CoCP ⁹ is designed to mitigate effects, and it is considered that only temporary minor adverse					

effects during the construction period will occur from ground disturbance.

hs2.org.uk

High Speed Two (HS2) Limited

Two Snowhill Snow Hill Queensway Birmingham B4 6GA Freephone: 08081 434 434 Minicom: 08081 456 472 Email: HS2enquiries@hs2.org.uk