

Moors Field Sitewide Tree Schedule

Number	Abbreviation	Species	Specification	Density
15	ACE cam	Acer campestre	Heavy Standard. min 2m clear stem. Rootball. Underground guying.	Counted
28	ACE pla	Acer platanoides 'Crimson King'	Select Standard. min 2m clear stem. Rootball. Underground guying.	Counted
35	ACE pse	Acer pseudoplatanus 'Eskimo Sunset'	Semi Mature. min 2m clear stem. Rootball. Underground guying.	Counted
6	ALN glu	Alnus glutinosa	Heavy Standard. min 2m clear stem. Rootball. Underground guying.	Counted
51	CAR bet	Carpinus betulus	Select Standard. min 2m clear stem. Rootball. Underground guying.	Counted
9	COR col	Corylus colurna	Select Standard. min 2m clear stem. Rootball. Underground guying.	Counted
10	JUG reg	Juglans regia 'Buccaneer' (F)	Semi Mature. min 2m clear stem. Rootball. Underground guying.	Counted
2	MAL dis	Malus domestica 'Discovery'	Select Standard. min 1.5m clear stem. Rootball. Underground guying.	Counted
9	MAL ess	Malus domestica 'Essex Pippin'	Select Standard. min 1.5m clear stem. Rootball. Underground guying.	Counted
3	MAL geo	Malus domestica 'George Cave'	Select Standard. min 1.5m clear stem. Rootball. Underground guying.	Counted
3	MAL syl	Malus sylvestris	Select Standard. min 1.5m clear stem. Rootball. Underground guying.	Counted
29	PIN syl	Pinus sylvestris	Heavy Standard. min 2m clear stem. Rootball. Underground guying.	Counted
44	POP trem	Populus tremula	Select Standard. min 2m clear stem. Rootball. Underground guying.	Counted
11	PRU avi	Prunus avium	Select Standard. min 1.5m clear stem. Rootball. Underground guying.	Counted
42	PUR sub	Prunus x subhirtella 'Autumnalis'	Semi Mature. min 2m clear stem. Rootball. Underground guying.	Counted
3	PYR com	Pyrus communis 'Red Sensation Bartlett'	Select Standard. min 1.5m clear stem. Rootball. Underground guying.	Counted
45	QUE may	Quercus 'Maya'	Semi Mature. min 2m clear stem. Rootball. Underground guying.	Counted
43	QUE ile	Quercus ilex	Semi Mature. min 2m clear stem. Rootball. Underground guying.	Counted
37	QUE rob	Quercus robur	Heavy Standard. min 2m clear stem. Rootball. Underground guying.	Counted
8	SOR ari	Sorbus aria 'Lutescens'	Select Standard. min 2m clear stem. Rootball. Underground guying.	Counted
4	TIL cor	Tilia cordata 'Greenspire'	Select Standard. min 1.8m clear stem. Rootball. Underground guying.	Counted

© This drawing is the copyright of Macfarlane Assocs. All Dimensions are to be verified on site. Do not scale from this drawing. Macfarlane Assocs accept no liability for any expense, loss, or damage, regardless of its nature, where variations to the details of this drawing have been made without prior written consent from the originating office of the company.

MAINTENANCE AND IMPLEMENTATION

GENERAL

All planting tree and shrub planting to be certified British stock or have been kept in a UK nursery for at least 1no. growing season. All trees and shrubs to comply with BS 3936. All plants shall be transported and manoeuvred in accordance with the Code of Practice for Plant Handling (CPSE).

Handling should be to HTS 'Handling and Establishing Landscape Plants'

Planting shall be carried out between October and March. The soil condition should be moist, friable and (excepting aquatic/marginal planting) not waterlogged.

Planting should be set out in a staggered grid pattern to avoid bare areas. Contractor should allow for 10% over purchase to ensure suitable coverage is met.

Compacted soil should be ripped through before topsoiling.

Percolation tests should be carried out prior to trees and shrub planting, to ensure the soils is not prone to waterlogging.

All planting to be set out on site as directed by the project landscape architect

NOTE: TO BE READ IN CONJUNCTION WITH DRAWINGS 3261.MA.3001-3007 PLANTING PLANS AND 3261.MA.3000 PLANTING STRATEGY PLAN, SITEWIDE

PLANTING CHARACTER AREA 1- RESIDENTIAL PLOT PLANTING - TYPICAL SPECIES

PLANTING CHARACTER AREA 2 - MARGINAL PLANTING - TYPICAL SPECIES

SHRUBS

HERBACEOUS / GRASS / FERN

MIXES

Choisya ternata	Molinia caerulea	Emorsgate Meadow Mixture for Wetlands EM8 as supplied by Emorsgate Seeds
Ilex aquifolium	Achillea millefolium	Pond Edge Mixture EP1 as supplied by Emorsgate Seeds
Lonicera nitida 'Baggenses Gold'	Choisya ternata	
Ligustrum vulgare	Veronicastrum virginicum 'Fascination'	
Cornus sanguinea 'Midwinter Fire'	Filipendula ulmaria	
Lavandula angustifolia 'Arctic Snow'	Briza media	
Hebe 'Red Edge'	Festuca glauca	

PLANTING CHARACTER AREA 4 - WILDIFE AREA - TYPICAL SPECIES

MIXES

HEDGE

Emorsgate Special General Purpose Meadow Mixture EM3 as supplied by Emorsgate Seeds
Emorsgate Special Cornfield Mixture EC2 as supplied by Emorsgate Seeds

Crataegus monogyna		
Viburnum opulus		
Prunus spinosa		
Ilex crenata		

PLANTING CHARACTER AREA 3 - NATIVE GREEN EDGE - TYPICAL SPECIES

PLANTING CHARACTER AREA 5 - COUNTRYSIDE PARK - TYPICAL SPECIES

SHRUBS

HERBACEOUS / GRASS / FERN

SHRUBS

HERBACEOUS / GRASS / FERN

Ilex aquifolium	Dryopteris filix-mas	Cornus sanguinea 'Midwinter Fire'	Allium sphaerocephalon
Lonicera nitida 'Baggenses Gold'	Geranium macrorrhizum 'Spessart'	Lavandula angustifolia 'Arctic Snow'	Crocus biflorus
Ligustrum vulgare	Persicaria bistorta 'Superba'	Choisya ternata	Galanthus 'Magnet'
Cornus sanguinea 'Midwinter Fire'	Achillea filipendulina 'Gold Plate'	Santolina pinnata	Galanthus nivalis
Salix viminalis	Achillea 'Lucky Break'	Rosmarinus officinalis	Narcissus papyraceus

MIXES

Emorsgate Woodland Mixture EW1 as supplied by Emorsgate Seeds

MIXES

Basic General Purpose Meadow Mixture EM1 as supplied by Emorsgate Seeds

C	01.03.24	LB	UPDATED PEGASUS G. LAYOUT
B	21.11.23	TR	UPDATED LAYOUT
A	04.10.23	HWR	UPDATED LAYOUT

Rev	Date	By	Notes

Client **DANDARA EASTERN LTD**

Project **MOORS FIELD UTTFLESDORF**

Title **PLANT SCHEDULE**

Status **FOR PLANNING**

Drawing No. **3261.MA.3008** Scale **N/A@A2**

Drawn **ML** Date **JULY 2023** Checked **AW**

