

# Notice of variation and consolidation with introductory note

The Environmental Permitting (England & Wales) Regulations 2016

---

3C Waste Limited

Maw Green Landfill Site  
Maw Green Road  
Coppenhall  
Crewe  
Cheshire  
CW1 5NG

**Variation application number**

EPR/BS7722ID/V009

**Permit number**

EPR/BS7722ID

# Maw Green Landfill Site

## Permit number EPR/BS7722ID

### Introductory note

#### **This introductory note does not form a part of the notice**

Under the Environmental Permitting (England & Wales) Regulations 2016 (schedule 5, part 1, paragraph 19) a variation may comprise a consolidated permit reflecting the variations and a notice specifying the variations included in that consolidated permit.

Schedule 1 of the notice specifies the conditions that have been varied and schedule 2 comprises a consolidated permit which reflects the variations being made. Only the variations specified in schedule 1 are subject to a right of appeal.

Specifically, the variation is to:

- Add an activity for the treatment of soils containing asbestos - Section 5.3A(1)(a)(ii) Disposal or recovery of hazardous waste with a capacity exceeding 10 tonnes per day involving physico-chemical treatment.
- Add new hazardous waste codes for acceptance at the Soil Treatment Facility. These include:
  - 17 05 03\* soil and stones containing hazardous substances. This code is restricted to those wastes which contain identifiable pieces of bonded asbestos – this being any particle size that can be identified as potentially being asbestos by a competent person if examined by the naked eye.
  - 17 06 05\* construction materials containing asbestos. This code is restricted to wastes containing discrete pieces of bonded asbestos within the soil matrix only.
- Increase the storage capacity for hazardous waste from 2000 tonnes up to 38,000 tonnes at any one time.

The installation operates as follows.

This site undertakes the landfilling of non-hazardous wastes and will be subject to restoration.

In addition, there are a number of waste treatment activities within the boundary of the landfill. This includes a Soil Treatment Facility located within the boundary, this undertakes the sorting and separation of asbestos from contaminated soils along with biological treatment activities taking leachate and hazardous and non-hazardous wastes.

The schedules specify the changes made to the permit.

The status log of a permit sets out the permitting history, including any changes to the permit reference number.

<b>Status log of the permit</b>		
<b>Description</b>	<b>Date</b>	<b>Comments</b>
Application EPR/BS7722ID/A001	09/10/2003	Received
Request for information	17/06/2004	Response received 19/07/2004
Request for information	23/06/2004	Response received 06/07/2004
Request for information	06/07/2004	Response received 20/07/2004
Request for information	25/08/2004	Response received 06/10/2004 and 11/10/2004
Request for information	30/12/2004	Response received 14/01/2005 and 27/01/2005
Permit determined EPR/BS7722ID	15/02/2005	
Variation notice UP3232LQ determined (EPR/BS7722ID/V002)	17/03/2005	
Application for Permit variation (EPR/BS7722ID/V003)	10/10/2007	Application received
Variation notice FP3931XK determined (EPR/BS7722ID/V003)	30/05/2008	
Environment Agency variation determined (EPR/BS7722ID/V005)	14/05/2013	Agency variation to implement changes introduced by IED
Environment Agency Landfill Sector Review Permit reviewed Variation notice determined EPR/BS7722ID/V006	15/02/2017	Permit varied and consolidated permit issued in the modern format
Application EPR/BS7722ID/V008	Duly made 11/07/2019	Application to vary Permit to include soil treatment facility and associated Activities on site.
Request for information in Schedule 5 Notice	23/08/2019	Response received 23/10/2019
Request for information in Schedule 5 Notice	22/11/2019	Responses received 13/12/2019 and 10/01/2020
Request for information by email	20/01/2020	Response received 12/02/2020
Variation determined EPR/BS7722ID/V007	18/03/2020	Varied permit issued.
Application EPR/BS7722ID/V008 (variation and consolidation)	Duly made 27/09/2022	Application to vary and update the permit. Increasing the treatment capacity for hazardous soils at the Soil Treatment Facility. Operator registered office change of address incorporated as administrative change.
Variation determined and consolidation issued EPR/BS7722ID	25/01/2023	Varied and consolidated permit issued in modern format.
Application EPR/BS7722ID/V009 (variation and consolidation)	Duly Made 13/04/2023	Application to add an additional listed activity for the treatment and storage of soils contaminated with asbestos at the Soil Treatment Facility (STF), add associated waste codes and increase hazardous storage capacity at any one time.
Variation determination and consolidation issued EPR/BS7722ID Billing Reference: MP3940QG	20/07/2023	Varied and Consolidated permit issued

End of introductory note

# Notice of variation and consolidation

## The Environmental Permitting (England and Wales) Regulations 2016

The Environment Agency in exercise of its powers under regulation 20 of the Environmental Permitting (England and Wales) Regulations 2016 varies

### Permit number

EPR/BS7722ID

### Issued to

**3C Waste Limited** (“the operator”)

whose registered office is

**3 Sidings Court  
White Rose Way  
Doncaster  
DN4 5NU**

company registration number 02632581

to operate a regulated facility at

**Maw Green Landfill Site  
Maw Green Road  
Coppenhall  
Crewe  
Cheshire  
CW1 5NG**

to the extent set out in the schedules.

The notice shall take effect from 20/07/2023

Name	Date
Eleanor Blackeby	20/07/2023

Authorised on behalf of the Environment Agency

## **Schedule 1**

The following conditions were varied as a result of the application made by the operator:

- Condition 1.5.1 and 1.5.2 have been updated
- Condition 2.1.2, 3.1.6, 4.1.1, 4.2.3, and 4.3.3 have been amended to reference the updated relevant activity codes
- Condition 2.6.4 has been updated to reference the new table of permitted waste codes
- Condition 3.5.5 has been added because it is relevant to the activities
- Condition 4.2.4 has been updated
- Condition 4.3.1 has been added because it is relevant to the new scheduled activity
- Table S1.1, as referenced in conditions 2.1.1 and 2.1.2, has been amended to include the new scheduled activity, specify the waste tables, amend the activity references, outline and update the activity limits and correct previous errors
- Table S1.2 as referenced in conditions 2.1.1 and 2.1.2 has been amended to include the relevant information submitted as part of this variation as operational techniques.
- Table S2.4 referenced in condition 2.6.4 has been added to incorporate the new asbestos hazardous waste codes

The following conditions were varied as a result of an Environment Agency initiated variation:

- Activity AR3, AR4, AR5 in Table S1.1 has been amended to include the maximum treatment capacity, permitted waste types and quantities as specified in table S2.3a and table S2.3b
- Table S2.3a and table S2.3b has been amended to state the relevant activities in table S1.1 and annual throughput
- Table S2.4 has been renumbered to S2.5

## **Schedule 2 – consolidated permit**

Consolidated permit issued as a separate document.

# Permit

## The Environmental Permitting (England and Wales) Regulations 2016

### Permit number

**EPR/BS7722ID**

This is the consolidated permit referred to in the variation and consolidation notice for application EPR/BS7722ID/V009 authorising,

**3C Waste Limited** (“the operator”),

whose registered office is

**3 Sidings Court  
White Rose Way  
Doncaster  
DN4 5NU**

company registration number 02632581

to operate an installation at

**Maw Green Landfill Site  
Maw Green Road  
Coppenhall  
Crewe  
Cheshire  
CW1 5NG**

to the extent authorised by and subject to the conditions of this permit.

Name	Date
Eleanor Blackeby	20/07/2023

Authorised on behalf of the Environment Agency

# Conditions

## 1 Management

### 1.1 General management

- 1.1.1 The operator shall manage and operate the activities:
- (a) in accordance with a written management system that identifies and minimises risks of pollution, including those arising from operations, maintenance, accidents, incidents, non-conformances, closure and those drawn to the attention of the operator as a result of complaints; and
  - (b) using sufficient competent persons and resources.
- 1.1.2 Records demonstrating compliance with condition 1.1.1 shall be maintained.
- 1.1.3 Any person having duties that are or may be affected by the matters set out in this permit shall have convenient access to a copy of it kept at or near the place where those duties are carried out.
- 1.1.4 The operator shall comply with the requirements of an approved competence scheme.

### 1.2 Finance

- 1.2.1 The financial provision for meeting the obligations under this permit shall be as set out in the Deed of Performance dated 17 October 2007 between the Waste Recycling Group Limited (now known as FCC Environment (UK) Limited) and the Environment Agency as varied by a Deed of Variation dated 15 October 2010 (as varied by further Deeds of Variation from time to time). The operator shall accordingly ensure that the Permit is and remains throughout its subsistence a Permit to which the Deed relates and the operator shall produce evidence of such provision whenever required by the Environment Agency.
- 1.2.2 The operator shall ensure that the charges it makes for the disposal of waste in the landfill cover all of the following:
- (a) the costs of setting up and operating the landfill;
  - (b) the costs of the financial provision required by condition 1.2.1; and
  - (c) the estimated costs for the closure and aftercare of the landfill.

### 1.3 Energy efficiency

- 1.3.1 The operator shall:
- (a) take appropriate measures to ensure that energy is used efficiently in the activities;
  - (b) review and record at least every four years whether there are suitable opportunities to improve the energy efficiency of the activities; and
  - (c) implement any appropriate measures identified by a review.

### 1.4 Efficient use of raw materials

- 1.4.1 The operator shall:
- (a) take appropriate measures to ensure that raw materials and water are used efficiently in the activities;
  - (b) maintain records of raw materials and water used in the activities;

- (c) review and record at least every four years whether there are suitable alternative materials that could reduce environmental impact or opportunities to improve the efficiency of raw material and water use; and
- (d) take any further appropriate measures identified by a review.

## **1.5 Avoidance, recovery and disposal of wastes produced by the activities**

- 1.5.1 The operator shall take appropriate measures to ensure that:
  - (a) the waste hierarchy referred to in Article 4 of the Waste Framework Directive is applied to the generation of waste by the activities; and
  - (b) any waste generated by the activities is treated in accordance with the waste hierarchy referred to in Article 4 of the Waste Framework Directive; and
  - (c) where disposal is necessary, this is undertaken in a manner which minimises its impact on the environment
- 1.5.2 The operator shall review and record at least every four years whether changes to those measures should be made and take any further appropriate measures identified by a review.

## **2 Operations**

### **2.1 Permitted activities**

- 2.1.1 The operator is only authorised to carry out the activities specified in schedule 1 table S1.1 (the “activities”).
- 2.1.2 For the following activities referenced in schedule 1, table S1.1 (AR3 to AR8 and AR16) waste authorised by this permit shall be clearly distinguished from any other waste on the site.

### **2.2 The site**

- 2.2.1 The activities shall not extend beyond the site, being the land shown edged in blue on the site plan at schedule 7 to this permit.

### **2.3 Operating techniques**

- 2.3.1 The activities shall, subject to the conditions of this permit, be operated using the techniques and in the manner described in the documentation specified in schedule 1, table S1.2, unless otherwise agreed in writing by the Environment Agency.
- 2.3.2 If notified by the Environment Agency that the activities are giving rise to pollution, the operator shall submit to the Environment Agency for approval within the period specified, a revision of any plan or other documentation (“plan”) specified in schedule 1, table S1.2 or otherwise required under this permit which identifies and minimises the risks of pollution relevant to that plan, and shall implement the approved revised plan in place of the original from the date of approval, unless otherwise agreed in writing by the Environment Agency.
- 2.3.3 Any raw materials or fuels listed in schedule 2 table S2.5 shall conform to the specifications set out in that table.

### **2.4 Pre-operational conditions**

- 2.4.1 The operations specified in schedule 1 table S1.4 shall not commence until the measures specified in that table have been completed.



## 2.5 Landfill Engineering

- 2.5.1 No construction of any new cell of the landfill shall commence until the operator has submitted construction proposals and the Environment Agency has confirmed that it is satisfied with the construction proposals.
- 2.5.2 Where the operator proposes to construct any new cell other than the first cell, but proposes no change from the design of the most recently approved cell which could have any impact on the performance of any element of the design, no construction of the new cell shall commence until the operator has submitted a cell layout drawing and the Environment Agency has confirmed that it is satisfied with the cell layout drawing.
- 2.5.3 The construction of a new cell shall take place only in accordance with the approved construction proposals unless:
- (a) any change to the approved construction proposals would have no impact on the performance of any element of the design; or
  - (b) a change has otherwise been agreed in writing by the Environment Agency.
- 2.5.4 No disposal of waste shall take place in a new cell until the operator has submitted a CQA Validation Report and the Environment Agency has confirmed that it is satisfied with the CQA Validation Report.
- 2.5.5 No construction of landfill infrastructure shall commence until the operator has submitted relevant construction proposals or a written request to use previous construction proposals and the Environment Agency has confirmed that it is satisfied with the construction proposals.
- 2.5.6 The construction of the landfill infrastructure shall take place only in accordance with the approved construction proposals unless:
- (a) any change to the approved construction proposals would have no impact on the performance of any element of the design; or
  - (b) a change has otherwise been agreed in writing by the Environment Agency.
- 2.5.7 The operator shall submit a CQA Validation Report within four weeks of the completion of the construction of the relevant landfill infrastructure or other time period agreed in writing with the Environment Agency.
- 2.5.8 Where pollution controls are immediately necessary to prevent an incident or accident, then conditions 2.5.5 and 2.5.6 do not apply and the relevant landfill infrastructure may be constructed, provided that the construction proposals are submitted to the Environment Agency as soon as practicable.
- 2.5.9 For the purposes of conditions 2.5.1, 2.5.2, 2.5.4 and 2.5.5, the Environment Agency shall be deemed to be satisfied where it has not, within the period of four weeks from the date of receipt of the relevant construction proposals or CQA Validation Report, either:
- (a) confirmed whether or not it is satisfied; or
  - (b) informed the operator that it requires further information.
- 2.5.10 Where the Environment Agency has required further information under condition 2.5.9(b), the Environment Agency shall be deemed to be satisfied where it has not, within the period of four weeks from the date of receipt of the further information, either:
- (a) confirmed whether or not it is satisfied; or
  - (b) informed the operator that it requires further information.

## 2.6 Waste acceptance

- 2.6.1 For the following activities referenced in Schedule 1, Table S1.1 (AR1), wastes shall only be accepted for disposal if:
- (a) they are listed in schedule 2, Table S2.1, and
  - (b) they are non-hazardous waste, and
  - (c) they are not whole used tyres (other than bicycle tyres and tyres with an outside diameter of more than 1400 mm), and
  - (d) they are not shredded used tyres, and
  - (e) they are not liquid waste (including waste waters but excluding sludge), and
  - (f) they are not chemical substances from research and development or teaching activities, for example laboratory residues, which are unidentified and/or which are new and whose effects on man and/or the environment are unknown, and
  - (g) all the relevant waste acceptance procedures have been completed, and
  - (h) they fulfil the relevant waste acceptance criteria, and
  - (i) they have not been diluted or mixed solely to meet the relevant waste acceptance criteria, and
  - (j) they are wastes which have been treated, except for: inert wastes for which treatment is not technically feasible; or it is waste other than inert waste and treatment would not reduce its quantity or the hazards which it poses to human health or the environment, and
  - (k) they are wastes with a code beginning with 07 05 and 16 03, they shall exclude waste medicinal products and pharmaceutically active waste materials arising from their manufacture.
- 2.6.2 Wastes shall only be accepted for restoration where:
- (a) they are listed in schedule 2, table S2.2 and
  - (b) they are accepted in accordance with a restoration plan approved in writing by the Environment Agency.
- 2.6.3 The operator shall:
- (1) visually inspect without unloading it, waste that is not in an enclosed container or enclosed vehicle on arrival at the landfill and waste at the point of deposit; and
  - (2) be satisfied that the waste conforms to the requirements of condition 2.6.1.
- 2.6.4 For the following activities referenced in schedule 1, Table S1.1 (AR3 – AR8 and AR16) waste shall only be accepted if:
- (a) it is of a type and quantity listed in schedule 2, Tables S2.3a and S2.3b and S2.4
  - (b) it conforms to the description in the documentation supplied by the producer and holder.
- 2.6.5 Where the operator has taken samples to establish that the waste is in conformity with the documentation submitted by the holder then the samples taken shall be retained for at least one month and results of any analysis for at least two years.
- 2.6.6 The operator on accepting each delivery of waste shall provide a receipt to the person delivering it.
- 2.6.7 The total quantity of waste that shall be deposited in the landfill shall be limited by the pre-settlement levels shown on drawing reference 1351-01-08 Final Restoration Plan-.
- 2.6.8 The quantity of waste that is deposited or recovered in the landfill in any year shall not exceed the limits in schedule 1 table S1.5.
- 2.6.9 The operator shall maintain and implement a system which ensures that a record is made of the quantity, characteristics, date of delivery and, where practicable, origin of any waste that is received

for disposal or recovery and of the identity of the producer, or in the case of municipal waste and multiple collection vehicles, of the collector of such waste. Any information regarded by the operator as commercially confidential shall be clearly identified in the record.

- 2.6.10 Hazardous waste shall not be mixed, either with a different category of hazardous waste or with other waste, substances or materials, unless it is authorised by schedule 1 table S1.1 and appropriate measures are taken.
- 2.6.11 The operator shall ensure that where waste produced by the activities is sent to a relevant waste operation, that operation is provided with the following information, prior to the receipt of the waste:
- (1) the nature of the process producing the waste;
  - (2) the composition of the waste;
  - (3) the handling requirements of the waste;
  - (4) the hazardous property associated with the waste, if applicable; and
  - (5) the waste code of the waste.
- 2.6.12 The operator shall ensure that where waste produced by the activities is sent to a landfill site, it meets the waste acceptance criteria for that landfill.

## **2.7 Leachate levels**

- 2.7.1 The limits for the level of leachate listed in schedule 3 table S3.1 shall not be exceeded.

## **2.8 Closure and aftercare**

- 2.8.1 The operator shall maintain a closure and aftercare management plan.

## **2.9 Landfill gas management**

- 2.9.1 The operator shall take appropriate measures, including, but not limited to, those specified in any approved landfill gas management plan, to:
- (a) collect landfill gas; and
  - (b) control the migration of landfill gas.
- 2.9.2 The operator shall use the collected landfill gas to produce energy. If the collected landfill gas cannot be used to produce energy, the operator shall use appropriate measures to flare or treat the gas in accordance with an approved landfill gas management plan.
- 2.9.3 The operator shall:
- (a) if notified by the Environment Agency, submit to the Environment Agency for approval within the period specified, a revised landfill gas management plan;
  - (b) implement the revised landfill gas management plan, from the date of approval, unless otherwise agreed in writing by the Environment Agency.

## **3 Emissions and monitoring**

### **3.1 Emissions to water, air or land**

- 3.1.1 The limits in Schedule 3 shall not be exceeded.
- 3.1.2 There shall be no point source emissions to water, air or land except from the sources and emission points listed in schedule 3 tables S3.2, S3.3 and S3.4.
- 3.1.3 The limits given in Table S3.2 shall not be exceeded, save that compliance with an emission limit in that table shall include incorporation of the uncertainty allowance stated in Environment Agency guidance LFTGN 05 and LFTGN 08.
- 3.1.4 The operator shall prevent the input of any hazardous substances from the activities into groundwater.
- 3.1.5 The operator shall submit to the Environment Agency a review of the Hydrogeological Risk Assessment:
  - (a) between nine and six months prior to the sixth anniversary of the granting of the permit, and
  - (b) between nine and six months prior to every subsequent six years after the fourth anniversary of the granting of the permit.
- 3.1.6 For the following activities referenced in schedule 1, table S1.1 (AR3 to AR8 and AR16) periodic monitoring shall be carried out at least once every 5 years for groundwater and 10 years for soil, unless such monitoring is based on systematic appraisal of the risk of contamination.

### **3.2 Emissions of substances not controlled by emission limits**

- 3.2.1 Emissions of substances not controlled by emission limits (excluding odour) shall not cause pollution. The operator shall not be taken to have breached this condition if appropriate measures, including, but not limited to, those specified in any approved emissions management plan, have been taken to prevent or where that is not practicable, to minimise, those emissions.
- 3.2.2 The operator shall:
  - (a) if notified by the Environment Agency that the activities are giving rise to pollution, submit to the Environment Agency for approval within the period specified, an emissions management plan which identifies and minimises the risks of pollution from emissions of substances not controlled by emission limits;
  - (b) implement the approved emissions management plan, from the date of approval, unless otherwise agreed in writing by the Environment Agency.
- 3.2.3 All liquids in containers, whose emission to water or land could cause pollution, shall be provided with secondary containment, unless the operator has used other appropriate measures to prevent or where that is not practicable, to minimise, leakage and spillage from the primary container.

### **3.3 Odour**

- 3.3.1 Emissions from the activities shall be free from odour at levels likely to cause pollution outside the site, as perceived by an authorised officer of the Environment Agency, unless the operator has used appropriate measures, including, but not limited to, those specified in any approved odour management plan, to prevent or where that is not practicable to minimise the odour.
- 3.3.2 The operator shall:
  - (a) if notified by the Environment Agency that the activities are giving rise to pollution outside the site due to odour, submit to the Environment Agency for approval within the period specified, an odour management plan which identifies and minimises the risks of pollution from odour;

- (b) implement the approved odour management plan, from the date of approval, unless otherwise agreed in writing by the Environment Agency.

### **3.4 Noise and vibration**

- 3.4.1 Emissions from the activities shall be free from noise and vibration at levels likely to cause pollution outside the site, as perceived by an authorised officer of the Environment Agency, unless the operator has used appropriate measures, including, but not limited to, those specified in any approved noise and vibration management plan to prevent or where that is not practicable to minimise the noise and vibration.
- 3.4.2 The operator shall:
  - (a) if notified by the Environment Agency that the activities are giving rise to pollution outside the site due to noise and vibration, submit to the Environment Agency for approval within the period specified, a noise and vibration management plan which identifies and minimises the risks of pollution from noise and vibration;
  - (b) implement the approved noise and vibration management plan, from the date of approval, unless otherwise agreed in writing by the Environment Agency.

### **3.5 Monitoring**

- 3.5.1 The operator shall, unless otherwise agreed in writing by the Environment Agency, undertake the monitoring and any other actions specified in the following tables in schedule 3 to this permit:
  - (a) Leachate specified in tables S3.1 and S3.11;
  - (b) Point source emissions specified in tables S3.2, S3.3 and S3.4;
  - (c) Groundwater specified in tables S3.5 and S3.9;
  - (d) Landfill gas specified in tables S3.6, S3.8 and S3.10;
  - (e) Surface water specified in table S3.12;
  - (f) Particulate matter specified in table S3.7.
- 3.5.2 The operator shall maintain records of all monitoring required by this permit including records of the taking and analysis of samples, instrument measurements (periodic and continual), calibrations, examinations, tests and surveys and any assessment or evaluation made on the basis of such data.
- 3.5.3 Monitoring equipment, techniques, personnel and organisations employed for the emissions monitoring programme and the environmental or other monitoring specified in condition 3.5.1 shall have either MCERTS certification or MCERTS accreditation (as appropriate), where available, unless otherwise agreed in writing by the Environment Agency.
- 3.5.4 A topographical survey of the site referenced to ordnance datum shall be carried out and shall be used to produce a plan of a scale adequate to show the surveyed features of the site:
  - (a) annually, and
  - (b) prior to the disposal of waste in any new cell or new development area of the landfill, and
  - (c) following closure of the landfill or part of the landfill.
- 3.5.5 Permanent means of access shall be provided to enable sampling/monitoring to be carried out in relation to the emission points specified in schedule 3 tables S3.1 to S3.13 unless otherwise agreed in writing by the Environment Agency.

## **3.6 Pests**

3.6.1 The activities shall not give rise to the presence of pests which are likely to cause pollution, hazard or annoyance outside the boundary of the site. The operator shall not be taken to have breached this condition if appropriate measures, including, but not limited to, those specified in any approved pests management plan, have been taken to prevent or where that is not practicable, to minimise the presence of pests on the site.

3.6.2 The operator shall:

- (a) if notified by the Environment Agency, submit to the Environment Agency for approval within the period specified, a pests management plan which identifies and minimises risks of pollution hazard or annoyance from pests;
- (b) implement the pests management plan, from the date of approval, unless otherwise agreed in writing by the Environment Agency.

## **3.7 Fire prevention**

3.7.1 The operator shall take all appropriate measures to prevent fires on site and minimise the risk of pollution from them including, but not limited to, those specified in any approved fire prevention plan.

3.7.2 The operator shall:

- (a) if notified by the Environment Agency that the activities are giving rise to a risk of fire, submit to the Environment Agency for approval within the period specified, a fire prevention plan which prevents fires and minimises the risk of pollution from fires;
- (b) implement the fire prevention plan, from the date of approval, unless otherwise agreed in writing by the Environment Agency.

# **4 Information**

## **4.1 Records**

4.1.1 All records required to be made by this permit shall:

- (a) be legible;
- (b) be made as soon as reasonably practicable;
- (c) if amended, be amended in such a way that the original and any subsequent amendments remain legible, or are capable of retrieval; and
- (d) be retained, unless otherwise agreed in writing by the Environment Agency, for at least 6 years from the date when the records were made, or in the case of the following records until permit surrender:
  - (i) the results of groundwater monitoring;
  - (ii) sub-surface landfill gas monitoring;
  - (iii) leachate levels, quality and quantities;
  - (iv) landfill gas generation and collection;
  - (v) waste types and quantities;
  - (vi) the specification and as built drawings of the basal, sidewall and capping engineering systems.

for the following activities referenced in schedule 1, table S1.1 (AR3 to AR8 and AR16):

- (vii) off-site environmental effects; and

(viii) matters which affect the condition of the land and groundwater.

4.1.2 The operator shall keep on site all records, plans and the management system required to be maintained by this permit, unless otherwise agreed in writing by the Environment Agency.

## 4.2 Reporting

4.2.1 The operator shall send reports and notifications required by the permit to the Environment Agency using the contact details supplied in writing by the Environment Agency.

4.2.2 For the following activities referenced in schedule 1, Table S1.1 (AR1 and AR2), a report or reports on the performance of the activities over the previous year ('the annual report') shall be submitted to the Environment Agency by 31st January each year or such other date as may be agreed in writing by the Agency, with the exception of 4.2.2(c) that must be provided by the end of February each year. The report(s) shall include as a minimum:

- (a) a review of the results of the monitoring and assessment carried out in accordance with this permit against the relevant assumptions, parameters and results in the risk assessments submitted in relation to this installation and any agreed amendments thereto. The review will include written descriptions of the improvements made to operational performance during the year, action plans developed and planned improvements for the coming year;
- (b) the energy consumed at the site, reported in the format set out in schedule 4 table S4.3;
- (c) the annual production/treatment set out in schedule 4 table S4.2;
- (d) the topographical surveys required by condition 3.5.3 other than those submitted as part of a CQA validation report;
- (e) the volumetric difference (reported in cubic metres) between the most recent topographical survey and the previous annual topographical survey i.e. the additional volume of the landfill void that is occupied by waste;
- (f) an assessment of the settlement behaviour of the landfill body based on the difference between the most recent topographical survey and previous annual topographical survey for the areas of the landfill which did not receive waste between the surveys;
- (g) a calculation of the remaining capacity (reported in cubic metres) derived from the pre-settlement contours and the most recent topographical survey;
- (h) a plan(s) ('the monitoring and extraction point plan – MEPP') showing the locations of existing and any new leachate and landfill gas extraction and all monitoring points.

4.2.3 For the following activities referenced in schedule 1, table S1.1 (AR3 to AR8 and A16) a report or reports on the performance of the activities over the previous year shall be submitted to the Environment Agency by 31<sup>st</sup> January (or other date agreed in writing by the Environment Agency) each year. The report(s) shall include as a minimum:

- (a) a review of the results of the monitoring and assessment carried out in accordance with the permit including an interpretive review of that data;
- (b) the annual production/treatment data set out in schedule 4 table S4.2; and
- (c) the performance parameters set out in schedule 4 table S4.3 using the forms specified in table S4.4 of that schedule.

4.2.4 Within 28 days of the end of the reporting period the operator shall, unless otherwise agreed in writing by the Environment Agency, submit reports of the monitoring and assessment carried out in accordance with the conditions of this permit, as follows:

- (a) in respect of the parameters and emission points specified in schedule 4 table S4.1;
- (b) for the reporting periods specified in schedule 4 table S4.1 and using the forms specified in schedule 4 table S4.4; and

- (c) giving the information from such results and assessments as may be required by the forms specified in those tables.

4.2.5 Within one month of the end of each quarter, the operator shall submit to the Environment Agency using the form made available for the purpose, the information specified on the form relating to the site and the waste accepted and removed from it during the previous quarter.

4.2.6 The operator shall, unless notice under this condition has been served within the preceding four years, submit to the Environment Agency, within six months of receipt of a written notice, a report assessing whether there are other appropriate measures that could be taken to prevent, or where that is not practicable, to minimise pollution.

### 4.3 Notifications

4.3.1 In the event:

- (a) that the operation of the activities gives rise to an incident or accident which significantly affects or may significantly affect the environment, the operator must immediately—
  - (i) inform the Environment Agency,
  - (ii) take the measures necessary to limit the environmental consequences of such an incident or accident, and
  - (iii) take the measures necessary to prevent further possible incidents or accidents.
- (b) in the event of a breach of any permit condition the operator must immediately—
  - (i) inform the Environment Agency, and
  - (ii) take the measures necessary to ensure that compliance is restored within the shortest possible time;
- (c) in the event of a breach of permit condition which poses an immediate danger to human health or threatens to cause an immediate significant adverse effect on the environment, the operator must immediately suspend the operation of the activities or the relevant part of it until compliance with the permit conditions has been restored.

4.3.2 Any information provided under condition 4.3.1 (a)(i), or 4.3.1 (b)(i) where the information relates to the breach of a limit specified in the permit, shall be confirmed by sending the information listed in schedule 5 to this permit within the time period specified in that schedule.

4.3.3 For the following activities referenced in schedule 1, table S1.1 (AR3 to AR8 and AR16) where the Environment Agency has requested in writing that it shall be notified when the operator is to undertake monitoring and/or spot sampling, the operator shall inform the Environment Agency when the relevant monitoring and/or spot sampling is to take place. The operator shall provide this information to the Environment Agency at least 14 days before the date the monitoring is to be undertaken.

4.3.4 The Environment Agency shall be notified within 14 days of the occurrence of the following matters, except where such disclosure is prohibited by Stock Exchange rules:

Where the operator is a registered company:

- (a) any change in the operator's trading name, registered name or registered office address; and
- (b) any steps taken with a view to the operator going into administration, entering into a company voluntary arrangement or being wound up.

Where the operator is a corporate body other than a registered company:

- (a) any change in the operator's name or address; and
- (b) any steps taken with a view to the dissolution of the operator.

In any other case:



- (a) the death of any of the named operators (where the operator consists of more than one named individual);
- (b) any change in the operator's name(s) or address(es); and
- (c) any steps taken with a view to the operator, or any one of them, going into bankruptcy, entering into a composition or arrangement with creditors, or, in the case of them being in a partnership, dissolving the partnership.

4.3.5 Where the operator proposes to make a change in the nature or functioning, or an extension of the activities, which may have consequences for the environment and the change is not otherwise the subject of an application for approval under the Regulations or this permit:

- (a) the Environment Agency shall be notified at least 14 days before making the change; and
- (b) the notification shall contain a description of the proposed change in operation.

4.3.6 The Environment Agency shall be given at least 14 days notice before implementation of any part of the site closure plan.

## **4.4 Interpretation**

4.4.1 In this permit the expressions listed in schedule 6 shall have the meaning given in that schedule.

4.4.2 In this permit references to reports and notifications mean written reports and notifications, except where reference is made to notification being made "immediately", in which case it may be provided by telephone.

# Schedule 1 – Operations

<b>Table S1.1 activities</b>				
<b>Activity reference</b>	<b>WFD Annex I and II operations (where applicable)</b>	<b>Activity listed in Schedule 1 of the EP Regulations</b>	<b>Description of specified activity</b>	<b>Limits of specified activity</b>
AR1	D5 –Specially engineered landfill; R5 - the recycling or reclamation of inorganic material and R10 – Land treatment resulting in benefit to agriculture or ecology	Section 5.2 Part A(1) (a), The disposal of waste in a landfill.	Landfill for non-hazardous waste and landfill restoration.	Receipt, handling, storage and disposal of wastes, consisting of the types and quantities specified in conditions 2.7, as an integral part of landfilling.
AR2	D8 – Biological treatment of waste	Section 5.4, Part A(1)(a)(i), Biological treatment of non-hazardous waste.	Treatment of leachate in a facility with a capacity of >50 tonnes/day.	Leachate arising from the landfill.
AR3	D8 – Biological treatment of waste and R5 - the recycling or reclamation of inorganic material	Section 5.3 Part A(1)(a)(ii)	Bioremediation process for hazardous waste.	A maximum treatment capacity of 38,000 tonnes at any one time. Hazardous waste types and quantities as specified in table S2.3b.
AR4	D8 – Biological treatment of waste and R5 - the recycling or reclamation of inorganic material	Section 5.4 Part A(1)(b)(i), Biological treatment of non-hazardous waste.	Recovery or a mix of recovery and disposal of non-hazardous waste with a capacity exceeding 75 tonnes per day involving biological treatment.	A maximum treatment capacity of 38,000 tonnes at any one time. Non-hazardous waste types and quantities as specified in table S2.3b.

AR5	D8 – Biological treatment of waste and R5 - the recycling or reclamation of inorganic material	Section 5.3 Part A(1)(a)(ii)	Screening to remove oversize material.	A maximum treatment capacity of 38,000 tonnes at any one time. Hazardous waste types and quantities as specified in table S2.3a.
AR6	R13 - Storage of waste pending any of the operations numbered R1 to R12	Section 5.6 Part A(1)(a)	Temporary storage of hazardous waste.	A maximum of 38,000 tonnes at any one time on site for wastes due to undergo treatment as per Activities AR3, AR4, AR5 or AR7. Hazardous waste types and quantities as specified in table S2.3a, S2.3b and S2.4.
AR7	R5 - the recycling or reclamation of inorganic material	Section 5.3 Part A(1)(a)(ii)	Disposal or recovery of hazardous waste with a capacity exceeding 10 tonnes per day involving physico-chemical treatment.	From receipt of waste through to storage of treated waste. Including storage and use of process additives.  All treatment and storage shall take place on an impermeable surface with a sealed drainage system as shown on site plan in schedule 7. Hazardous waste types and quantities as specified in table S2.4.
AR8	R5 - the recycling or reclamation of inorganic material	Section 5.4 Part A (1)(a)(ii) Physico-chemical treatment of non-hazardous waste with a capacity exceeding 50 tonnes per day.	Screening of non-hazardous waste to remove oversized material for recovery.	Non-hazardous waste following treatment on site by Activity AR4.  Non-hazardous waste types and quantities as specified in table S2.3b.
<b>Directly Associated Activities</b>				
AR9	R1 – use principally as a fuel to generate energy		Pre-treatment and utilisation of landfill gas for energy recovery in an appliance with a rated thermal input < 50MW.	Treatment and utilisation of landfill gas arising from the landfill.
AR10	N/A		Temporary storage of waste (leachate).	Leachate arising from the landfill.
AR11	N/A		Flaring of landfill gas for disposal in an appliance.	Landfill gas arising from the landfill.

AR12	D6 – release to water body except seas/ oceans		Discharges of site drainage from the landfill.	From surface water management system to point of entry to controlled waters.
AR13	N/A		Fuel Storage.	Storage of diesel for use in mobile plant at Soil Treatment Facility.
AR14	N/A		Water Storage.	Collection and storage of process water.
AR15	N/A		Pipework between the leachate treatment plant and public sewerage system.	From the point of discharge from the leachate treatment plant to the point where the pipework leaves the land under the control of the operator.
AR16	R13 – Storage of wastes pending any of the operations numbered R1 to R12 (excluding temporary storage, pending collection, on the site where it is produced)		Storage of waste.	Temporary storage of non-hazardous waste prior to treatment on site.

<b>Table S1.2 Operating techniques</b>		
<b>Description</b>	<b>Parts</b>	<b>Date Received</b>
Application	The response to questions 1.2, 2.1, 2.2, 2.3, 2.4 and 2.5 in part B of the Application Form, excluding the following sections:  2.2.4 to 2.2.6, 2.3.32, 2.3.33, 2.3.34, 2.3.35, 2.3.39, 2.3.43, 2.3.50 to 2.3.54, 2.3.68, 2.3.69, 2.3.71, 2.3.72 and 2.3.78	09/10/2003
SLR letter and supporting documents regarding requests for information dated 17/06/2004.	All Parts	19/07/2004
SLR letter and supporting documents regarding requests for information dated 06/07/2004.	All Parts	20/07/2004
SLR letter and supporting documents regarding requests for information dated 25/08/2004.	All Parts	11/10/2004
SLR e-mail and supporting documents regarding revised waste list.	All Parts	14/01/2005
SLR e-mail and supporting documents  All parts 14/01/2005 and 27/01/2005 regarding requests for information dated 30/12/2004.	All Parts	28/02/2006
Correspondence dated 27/02/2006 re: 27/02/2006 re: Improvement condition 1.4.1.1	All Parts	28/02/2006
Correspondence dated 03/04/2006 re: Improvement condition 1.4.1.2	All Parts	03/04/2006
Correspondence dated 01/03/2006 re: Improvement condition 1.4.1.3	All Parts	06/03/2006
Correspondence dated 15/02/2006, (ref: 404- 0197-00178) re: Improvement condition 1.4.1.5	All Parts	16/02/2006
Correspondence dated 02/2006 (ref 404-0197-00178), CQA plan for downstream monitoring wells)	All Parts	02/2006
Correspondence dated 06/04/2006 (ref:402.0197.00423) re: Improvement condition 1.4.1.7	All Parts	12/04/2006
Correspondence dated 13/04/2006 (ref: 404.0197.00178)  Re: improvement condition 1.4.1.9	All Parts	18/04/2006
Correspondence dated 15/03/2005 (ref: 4D-197-178) re improvement condition 1.4.1.12	All Parts	21/05/2005

<b>Table S1.2 Operating techniques</b>		
<b>Description</b>	<b>Parts</b>	<b>Date Received</b>
Correspondence 'Maw Green Leachate Extraction Review' re improvement condition 1.4.1.13	All parts	06/2006
Revised monitoring location plan (drawing no. ESID 14, dated August 2007)	All parts	22/01/2008
Monitoring reduction letter Ref ALM/MG/EAL53	All Parts	22/01/2014
FCC letter ref MG/LC2.2AR/20140829	All Parts	29/08/2014
FCC Document E mail from FCC 29 Jan 2016 Attached updated tables for Doc ref: ALM/MG/EAL53	All Parts	29/01/2015
Landfill Restoration Plan (referenced report 10228-R07 and dated May 2017)	All Parts	15/05/2017
Application	Application Forms (All Parts) ESID Amendment Site Condition Report (referenced 3695-CAU-XX-XX-RP-V-0305.A0-C2 and dated March 2019) Soil Treatment Facility Amenity and Accident Plan (referenced 3695-CAU-XX-XX-RP-V-0302.A0-C2 and dated March 2019)	01/04/2019
Response to Schedule 5 Notice (1) dated 23/08/2019	Soil Treatment Facility Dust Management Plan (reference 3695-CAU-XX-XX-RP-V-0307-A0-C1 and dated October 2019) Soil Treatment Facility Operating Techniques (reference 3695-CAU-XX-XX-RP-V-0303 and dated October 2019) Response includes clarification on area drainage, clarification on waste codes and biofilter/air quality monitoring details.	02/10/2019
Response to Schedule 5 Notice (2) follow up request dated 22/11/2019 and 02/01/2020	STC Soil Characterisation Procedure (referenced WI-003) and dated 26/11/2019) Response includes further detail on waste code acceptance, biofilter and air quality monitoring.	13/12/2019
	Soil Treatment Facility Odour Management Plan (reference 3695-CAU-XX-XX-RP-V-0308-	10/01/2020

<b>Table S1.2 Operating techniques</b>		
<b>Description</b>	<b>Parts</b>	<b>Date Received</b>
	A0-C3 OMP Combined and dated December 2019)	
Response to request for more information dated 20/01/2020	Drawings Leachate Pipeline Route (ref. 3695-CAU-XX-XX-DR-V-1802 P1) and Proposed Layout Plan (ref. 3695-CAU-XX-XX-DR-V-1801 P3) detailing sewer connections to site and proposed monitoring locations respectively.	12/02/2020
Response to Improvement Condition 4	H1 Assessment (referenced 5193-CAU-XX-XX-RP-V-0308.A0.C1 Final and dated November 2021)	08/11/2021
Application	<p>Application Forms (All Parts)</p> <p>Updated Supporting Document (reference 5193-CAU-XX-XX-RP-V-0300.A0.C1 and dated December 2021)</p> <p>Updated Amenity and Accident Plan (reference 5193-CAU-XX-XX-RP-V-0301-A0.C1 and dated December 2021)</p> <p>Addendum to ESID Report (referenced 5193-CAU-XX-XX-RP-V-0302-A0.C1 and dated December 2021)</p> <p>Updated Operating Techniques Document (referenced 5193-CAU-XX-XX-RP-V-0306.A0.C1 and dated December 2021)</p> <p>Updated BAT Review (referenced 5193-CAU-XX-XX-RP-V-0307.A0.C1 and dated December 2021)</p>	15/12/2021
Application EPR/BS7722ID/V009	<p>Documents received in response to Section 3a of form Part C3:</p> <ul style="list-style-type: none"> <li>• Picking Station Specification – Site plan (Document Reference: 5193-CAU-XX-XX-RP-V-0313.A0.C1)</li> <li>• Treatment process &amp; BAT review - reference 10012023</li> <li>• Dust &amp; Emissions Management Plan (Document Ref: 5193-CAU-XX-XX-RP-V-0313.A0.C1)</li> <li>• Environmental Setting and Installation Design (ESID) - Addendum 2022 (Document Ref: 5193-CAU-XX-XX-RP-V-0309.A0.C1) (Page 3 – Asbestos Soil Treatment)</li> <li>• Amenity &amp; Accidents Risk Assessment (Document Ref: 5193-CAU-XX-XX-RP-V-0310.A0.C1)</li> </ul>	10/01/2023

Table S1.2 Operating techniques		
Description	Parts	Date Received
	<ul style="list-style-type: none"> <li>Activities &amp; Operating Techniques Report (Document Ref: 5193-CAU-XX-XX-RP-V-0311.A0.C1)</li> </ul>	

Table S1.3 Improvement programme requirements		
Reference	Requirement	Date
4	(b) The operator shall submit to the Environment Agency in writing for approval, a report detailing monthly chemical analysis monitoring results of collected waters from the Soil Treatment Facility (STF) at the point of discharge from the STF. The report should contain details of comparison of results from the chemical analysis to existing discharge consent limits and the Environment Agency's H1 Guidance.	Complete

Table S1.4 Pre-operational measures for future development		
Reference	Operation	Pre-operational Measures
1	Deposit of wastes in any area of the Permitted installation where waste deposit commences after the issue of the permit	As part of any construction proposals required by condition 2.5.1 the operator shall include a design for leachate collection infrastructure, which includes details of the leachate collection layer, drainage pipework, collection systems and drilling targets.
2	Deposit of waste over previously completed areas of phase 1	A leachate drainage layer shall be incorporated into the design of the internal slope between phase 1 and future phases. The design specification of this layer shall be approved in accordance with condition 2.5.1.
3	Engineering of any new cell	As part of any construction proposals required by condition 2.5.1, the operator shall submit a report investigating the existence of sand horizons beneath the cell base. The report shall detail the thickness of any encountered sand horizon, the presence of groundwater including the piezometric head and shall also include an assessment into the possibility of basal heave and any necessary preventative action required for the cell, together with any required amendments to CQA procedures for engineering at the site. If in the preparation of the report, extra intrusive site investigation is undertaken, the report shall contain all relevant borehole logs and descriptions.

Table S1.5 Annual waste input limits	
Category	Limit Tonnes/ Year
Non-hazardous waste	450,000
Inert waste	450,000
Waste for restoration	75,000



## Schedule 2 – List of permitted wastes

Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste	
Waste code	Description
<b>01</b>	<b>Wastes resulting from exploration, mining, quarrying, and physical and chemical treatment of minerals</b>
<b>01 01</b>	<b>wastes from mineral excavation</b>
01 01 01	wastes from mineral metalliferous excavation
01 01 02	wastes from mineral non-metalliferous excavation
<b>01 03</b>	<b>wastes from physical and chemical processing of metalliferous minerals</b>
01 03 06	tailings other than those mentioned in 01 03 04 and 01 03 05
01 03 08	dusty and powdery wastes other than those mentioned in 01 03 07
01 03 09	red mud from alumina production other than the wastes mentioned in 01 03 10
<b>01 04</b>	<b>wastes from physical and chemical processing of non-metalliferous minerals</b>
01 04 08	waste gravel and crushed rocks other than those mentioned in 01 04 07
01 04 09	waste sand and clays
01 04 10	dusty and powdery wastes other than those mentioned in 01 04 07
01 04 11	wastes from potash and rock salt processing other than those mentioned in 01 04 07
01 04 12	tailings and other wastes from washing and cleaning of minerals other than those mentioned in 01 04 07 and 01 04 11
01 04 13	wastes from stone cutting and sawing other than those mentioned in 01 04 07
<b>01 05</b>	<b>drilling muds and other drilling wastes</b>
01 05 04	freshwater drilling muds and wastes
01 05 07	barite-containing drilling muds and wastes other than those mentioned in 01 05 05 and 01 05 06
01 05 08	chloride-containing drilling muds and wastes other than those mentioned in 01 05 05 and 01 05 06
<b>02</b>	<b>Wastes from agriculture, horticulture, aquaculture, forestry, hunting and fishing, food preparation and processing</b>
<b>02 01</b>	<b>wastes from agriculture, horticulture, aquaculture, forestry, hunting and fishing</b>
02 01 01	sludges from washing and cleaning
02 01 02	animal-tissue waste
02 01 03	plant-tissue waste
02 01 04	waste plastics (except packaging)
02 01 06	animal faeces, urine and manure (including spoiled straw), effluent, collected separately and treated off-site
02 01 07	wastes from forestry
02 01 09	agrochemical waste other than those mentioned in 02 01 08
02 01 10	waste metal
<b>02 02</b>	<b>wastes from the preparation and processing of meat, fish and other foods of animal origin</b>

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
02 02 01	sludges from washing and cleaning
02 02 02	animal-tissue waste
02 02 03	materials unsuitable for consumption or processing
02 02 04	sludges from on-site effluent treatment
<b>02 03</b>	<b>wastes from fruit, vegetables, cereals, edible oils, cocoa, coffee, tea and tobacco preparation and processing; conserve production; yeast and yeast extract production, molasses preparation and fermentation</b>
02 03 01	sludges from washing, cleaning, peeling, centrifuging and separation
02 03 02	wastes from preserving agents
02 03 03	wastes from solvent extraction
02 03 04	materials unsuitable for consumption or processing
02 03 05	sludges from on-site effluent treatment
<b>02 04</b>	<b>wastes from sugar processing</b>
02 04 01	soil from cleaning and washing beet
02 04 02	off-specification calcium carbonate
02 04 03	sludges from on-site effluent treatment
<b>02 05</b>	<b>wastes from the dairy products industry</b>
02 05 01	materials unsuitable for consumption or processing
02 05 02	sludges from on-site effluent treatment
<b>02 06</b>	<b>wastes from the baking and confectionery industry</b>
02 06 01	materials unsuitable for consumption or processing
02 06 02	wastes from preserving agents
02 06 03	sludges from on-site effluent treatment
<b>02 07</b>	<b>wastes from the production of alcoholic and non-alcoholic beverages (except coffee, tea and cocoa)</b>
02 07 01	wastes from washing, cleaning and mechanical reduction of raw materials
02 07 02	wastes from spirits distillation
02 07 03	wastes from chemical treatment
02 07 04	materials unsuitable for consumption or processing
02 07 05	sludges from on-site effluent treatment
<b>03</b>	<b>Wastes from wood processing and the production of panels and furniture, pulp, paper and cardboard</b>
<b>03 01</b>	<b>wastes from wood processing and the production of panels and furniture</b>
03 01 01	waste bark and cork
03 01 05	sawdust, shavings, cuttings, wood, particle board and veneer other than those mentioned in 03 01 04
<b>03 03</b>	<b>wastes from pulp, paper and cardboard production and processing</b>
03 03 01	waste bark and wood
03 03 02	green liquor sludge (from recovery of cooking liquor)
03 03 05	de-inking sludges from paper recycling

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
03 03 07	mechanically separated rejects from pulping of waste paper and cardboard
03 03 08	wastes from sorting of paper and cardboard destined for recycling
03 03 09	lime mud waste
03 03 10	fibre rejects, fibre-, filler- and coating-sludges from mechanical separation
03 03 11	sludges from on-site effluent treatment other than those mentioned in 03 03 10
<b>04</b>	<b>Wastes from the leather, fur and textile industries</b>
<b>04 01</b>	<b>wastes from the leather and fur industry</b>
04 01 01	fleshings and lime split wastes
04 01 02	liming waste
04 01 06	sludges, in particular from on-site effluent treatment containing chromium
04 01 07	sludges, in particular from on-site effluent treatment free of chromium
04 01 08	waste tanned leather (blue sheetings, shavings, cuttings, buffing dust) containing chromium
04 01 09	wastes from dressing and finishing
<b>04 02</b>	<b>wastes from the textile industry</b>
04 02 09	wastes from composite materials (impregnated textile, elastomer, plastomer)
04 02 10	organic matter from natural products (for example grease, wax)
04 02 15	wastes from finishing other than those mentioned in 04 02 14
04 02 17	dyestuffs and pigments other than those mentioned in 04 02 16
04 02 20	sludges from on-site effluent treatment other than those mentioned in 04 02 19
04 02 21	wastes from unprocessed textile fibres
04 02 22	wastes from processed textile fibres
<b>05</b>	<b>Wastes from petroleum refining, natural gas purification and pyrolytic treatment of coal</b>
<b>05 01</b>	<b>wastes from petroleum refining</b>
05 01 10	sludges from on-site effluent treatment other than those mentioned in 05 01 09
05 01 13	boiler feedwater sludges
05 01 14	wastes from cooling columns
05 01 16	sulphur-containing wastes from petroleum desulphurisation
05 01 17	bitumen
<b>05 06</b>	<b>wastes from the pyrolytic treatment of coal</b>
05 06 04	waste from cooling columns
<b>05 07</b>	<b>wastes from natural gas purification and transportation</b>
05 07 02	wastes containing sulphur
<b>06</b>	<b>Wastes from inorganic chemical processes</b>
<b>06 03</b>	<b>wastes from the MFSU of salts and their solutions and metallic oxides</b>
06 03 14	solid salts and solutions other than those mentioned in 06 03 11 and 06 03 13
06 03 16	metallic oxides other than those mentioned in 06 03 15
<b>06 05</b>	<b>sludges from on-site effluent treatment</b>

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
06 05 03	sludges from on-site effluent treatment other than those mentioned in 06 05 02
<b>06 06</b>	<b>wastes from the MFSU of sulphur chemicals, sulphur chemical processes and desulphurisation processes</b>
06 06 03	wastes containing sulphides other than those mentioned in 06 06 02
<b>06 09</b>	<b>wastes from the MSFU of phosphorous chemicals and phosphorous chemical processes</b>
06 09 02	phosphorous slag
06 09 04	calcium-based reaction wastes other than those mentioned in 06 09 03
<b>06 11</b>	<b>wastes from the manufacture of inorganic pigments and opacifiers</b>
06 11 01	calcium-based reaction wastes from titanium dioxide production
<b>06 13</b>	<b>wastes from inorganic chemical processes not otherwise specified</b>
06 13 03	carbon black
<b>07</b>	<b>Wastes from organic chemical processes</b>
<b>07 01</b>	<b>wastes from the manufacture, formulation, supply and use (MFSU) of basic organic chemicals</b>
07 01 12	sludges from on-site effluent treatment other than those mentioned in 07 01 11
<b>07 02</b>	<b>wastes from the MFSU of plastics, synthetic rubber and man-made fibres</b>
07 02 12	sludges from on-site effluent treatment other than those mentioned in 07 02 11
07 02 13	waste plastic
07 02 15	wastes from additives other than those mentioned in 07 02 14
07 02 17	waste containing silicones other than those mentioned in 07 02 16
<b>07 03</b>	<b>wastes from the MFSU of organic dyes and pigments (except 06 11)</b>
07 03 12	sludges from on-site effluent treatment other than those mentioned in 07 03 11
<b>07 04</b>	<b>wastes from the MFSU of organic plant protection products (except 02 01 08 and 02 01 09), wood preserving agents (except 03 02) and other biocides</b>
07 04 12	sludges from on-site effluent treatment other than those mentioned in 07 04 11
<b>07 05</b>	<b>wastes from the MFSU of pharmaceuticals</b>
07 05 12	sludges from on-site effluent treatment other than those mentioned in 07 05 11
07 05 14	solid wastes other than those mentioned in 07 05 13
<b>07 06</b>	<b>wastes from the MFSU of fats, grease, soaps, detergents, disinfectants and cosmetics</b>
07 06 12	sludges from on-site effluent treatment other than those mentioned in 07 06 11
<b>07 07</b>	<b>wastes from the MFSU of fine chemicals and chemical products not otherwise specified</b>
07 07 12	sludges from on-site effluent treatment other than those mentioned in 07 07 11
<b>08</b>	<b>Wastes from the manufacture, formulation, supply and use (MFSU) of coatings (paints, varnishes and vitreous enamels), adhesives, sealants and printing inks</b>
<b>08 01</b>	<b>wastes from MFSU and removal of paint and varnish</b>
08 01 12	waste paint and varnish other than those mentioned in 08 01 11
08 01 14	sludges from paint or varnish other than those mentioned in 08 01 13

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
08 01 16	aqueous sludges containing paint or varnish other than those mentioned in 08 01 15
08 01 18	wastes from paint or varnish removal other than those mentioned in 08 01 17
<b>08 02</b>	<b>wastes from MFSU of other coatings (including ceramic materials)</b>
08 02 01	waste coating powders
08 02 02	aqueous sludges containing ceramic materials
<b>08 03</b>	<b>wastes from MFSU of printing inks</b>
08 03 07	aqueous sludges containing ink
08 03 13	waste ink other than those mentioned in 08 03 12
08 03 15	ink sludges other than those mentioned in 08 03 14
08 03 18	waste printing toner other than those mentioned in 08 03 17
<b>08 04</b>	<b>wastes from MFSU of adhesives and sealants (including water proofing products)</b>
08 04 10	waste adhesives and sealants other than those mentioned in 08 04 09
08 04 12	adhesive and sealant sludges other than those mentioned in 08 04 11
08 04 14	aqueous sludges containing adhesives or sealants other than those mentioned in 08 04 13
<b>09</b>	<b>Wastes from the photographic industry</b>
<b>09 01</b>	<b>wastes from the photographic industry</b>
09 01 07	photographic film and paper containing silver or silver compounds
09 01 08	photographic film and paper free of silver or silver compounds
09 01 10	single-use cameras without batteries
09 01 12	single-use cameras containing batteries other than those mentioned in 09 01 11
<b>10</b>	<b>Wastes from thermal processes</b>
<b>10 01</b>	<b>wastes from power stations and other combustion plants (except 19)</b>
10 01 01	bottom ash, slag and boiler dust (excluding boiler dust mentioned in 10 01 04)
10 01 02	coal fly ash
10 01 03	fly ash from peat and untreated wood
10 01 05	calcium-based reaction wastes from flue-gas desulphurisation in solid form
10 01 07	calcium-based reaction wastes from flue-gas desulphurisation in sludge form
10 01 15	bottom ash, slag and boiler dust from co-incineration other than those mentioned in 10 01 14
10 01 17	fly ash from co-incineration other than those mentioned in 10 01 16
10 01 19	wastes from gas cleaning other than those mentioned in 10 01 05, 10 01 07 and 10 01 18
10 01 21	sludges from on-site effluent treatment other than those mentioned in 10 01 20
10 01 23	aqueous sludges from boiler cleansing other than those mentioned in 10 01 22
10 01 24	sands from fluidised beds
10 01 25	wastes from fuel storage and preparation of coal-fired power plants
10 01 26	wastes from cooling-water treatment

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
<b>10 02</b>	<b>wastes from the iron and steel industry</b>
10 02 01	wastes from the processing of slag
10 02 02	unprocessed slag
10 02 08	solid wastes from gas treatment other than those mentioned in 10 02 07
10 02 10	mill scales
10 02 12	wastes from cooling-water treatment other than those mentioned in 10 02 11
10 02 14	sludges and filter cakes from gas treatment other than those mentioned in 10 02 13
10 02 15	other sludges and filter cakes
<b>10 03</b>	<b>wastes from aluminium thermal metallurgy</b>
10 03 02	anode scraps
10 03 05	waste alumina
10 03 16	skimmings other than those mentioned in 10 03 15
10 03 18	carbon-containing wastes from anode manufacture other than those mentioned in 10 03 17
10 03 20	flue-gas dust other than those mentioned in 10 03 19
10 03 22	other particulates and dust (including ball-mill dust) other than those mentioned in 10 03 21
10 03 24	solid wastes from gas treatment other than those mentioned in 10 03 23
10 03 26	sludges and filter cakes from gas treatment other than those mentioned in 10 03 25
10 03 28	wastes from cooling-water treatment other than those mentioned in 10 03 27
10 03 30	wastes from treatment of salt slags and black drosses other than those mentioned in 10 03 29
<b>10 04</b>	<b>wastes from lead thermal metallurgy</b>
10 04 10	wastes from cooling-water treatment other than those mentioned in 10 04 09
<b>10 05</b>	<b>wastes from zinc thermal metallurgy</b>
10 05 01	slags from primary and secondary production
10 05 04	other particulates and dust
10 05 09	wastes from cooling-water treatment other than those mentioned in 10 05 08
10 05 11	dross and skimmings other than those mentioned in 10 05 10
<b>10 06</b>	<b>wastes from copper thermal metallurgy</b>
10 06 01	slags from primary and secondary production
10 06 02	dross and skimmings from primary and secondary production
10 06 04	other particulates and dust
10 06 10	wastes from cooling-water treatment other than those mentioned in 10 06 09
<b>10 07</b>	<b>wastes from silver, gold and platinum thermal metallurgy</b>
10 07 01	slags from primary and secondary production
10 07 02	dross and skimmings from primary and secondary production
10 07 03	solid wastes from gas treatment
10 07 04	other particulates and dust

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
10 07 05	sludges and filter cakes from gas treatment
10 07 08	wastes from cooling-water treatment other than those mentioned in 10 07 07
<b>10 08</b>	<b>wastes from other non-ferrous thermal metallurgy</b>
10 08 04	particulates and dust
10 08 09	other slags
10 08 11	dross and skimmings other than those mentioned in 10 08 10
10 08 13	carbon-containing wastes from anode manufacture other than those mentioned in 10 08 12
10 08 14	anode scrap
10 08 16	flue-gas dust other than those mentioned in 10 08 15
10 08 18	sludges and filter cakes from flue-gas treatment other than those mentioned in 10 08 17
10 08 20	wastes from cooling-water treatment other than those mentioned in 10 08 19
<b>10 09</b>	<b>wastes from casting of ferrous pieces</b>
10 09 03	furnace slag
10 09 06	casting cores and moulds which have not undergone pouring other than those mentioned in 10 09 05
10 09 08	casting cores and moulds which have undergone pouring other than those mentioned in 10 09 07
10 09 10	flue-gas dust other than those mentioned in 10 09 09
10 09 12	other particulates other than those mentioned in 10 09 11
10 09 14	waste binders other than those mentioned in 10 09 13
10 09 16	waste crack-indicating agent other than those mentioned in 10 09 15
<b>10 10</b>	<b>wastes from casting of non-ferrous pieces</b>
10 10 03	furnace slag
10 10 06	casting cores and moulds which have not undergone pouring, other than those mentioned in 10 10 05
10 10 08	casting cores and moulds which have undergone pouring, other than those mentioned in 10 10 07
10 10 10	flue-gas dust other than those mentioned in 10 10 09
10 10 12	other particulates other than those mentioned in 10 10 11
10 10 14	waste binders other than those mentioned in 10 10 13
10 10 16	waste crack-indicating agent other than those mentioned in 10 10 15
<b>10 11</b>	<b>wastes from manufacture of glass and glass products</b>
10 11 03	waste glass-based fibrous materials
10 11 05	particulates and dust
10 11 10	waste preparation mixture before thermal processing, other than those mentioned in 10 11 09
10 11 12	waste glass other than those mentioned in 10 11 11
10 11 14	glass-polishing and -grinding sludge other than those mentioned in 10 11 13

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
10 11 16	solid wastes from flue-gas treatment other than those mentioned in 10 11 15
10 11 18	sludges and filter cakes from flue-gas treatment other than those mentioned in 10 11 17
10 11 20	solid wastes from on-site effluent treatment other than those mentioned in 10 11 19
<b>10 12</b>	<b>wastes from manufacture of ceramic goods, bricks, tiles and construction products</b>
10 12 01	waste preparation mixture before thermal processing
10 12 03	particulates and dust
10 12 05	sludges and filter cakes from gas treatment
10 12 06	discarded moulds
10 12 08	waste ceramics, bricks, tiles and construction products (after thermal processing)
10 12 10	solid wastes from gas treatment other than those mentioned in 10 12 09
10 12 12	wastes from glazing other than those mentioned in 10 12 11
10 12 13	sludge from on-site effluent treatment
<b>10 13</b>	<b>wastes from manufacture of cement, lime and plaster and articles and products made from them</b>
10 13 01	waste preparation mixture before thermal processing
10 13 04	wastes from calcination and hydration of lime
10 13 06	particulates and dust (except 10 13 12 and 10 13 13)
10 13 07	sludges and filter cakes from gas treatment
10 13 10	wastes from asbestos-cement manufacture other than those mentioned in 10 13 09
10 13 11	wastes from cement-based composite materials other than those mentioned in 10 13 09 and 10 13 10
10 13 13	solid wastes from gas treatment other than those mentioned in 10 13 12
10 13 14	waste concrete and concrete sludge
<b>11</b>	<b>Wastes from chemical surface treatment and coating of metals and other materials; non-ferrous hydro-metallurgy</b>
<b>11 01</b>	<b>wastes from chemical surface treatment and coating of metals and other materials (for example galvanic processes, zinc coating processes, pickling processes, etching, phosphating, alkaline degreasing, anodising)</b>
11 01 10	sludges and filter cakes other than those mentioned in 11 01 09
11 01 14	degreasing wastes other than those mentioned in 11 01 13
<b>11 02</b>	<b>wastes from non-ferrous hydrometallurgical processes</b>
11 02 03	wastes from the production of anodes for aqueous electrolytical processes
11 02 06	wastes from copper hydrometallurgical processes other than those mentioned in 11 02 05
<b>11 05</b>	<b>wastes from hot galvanising processes</b>
11 05 01	hard zinc
11 05 02	zinc ash
<b>12</b>	<b>Wastes from shaping and physical and mechanical surface treatment of metals and plastics</b>



<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
<b>12 01</b>	<b>wastes from shaping and physical and mechanical surface treatment of metals and plastics</b>
12 01 01	ferrous metal filings and turnings
12 01 02	ferrous metal dust and particles
12 01 03	non-ferrous metal filings and turnings
12 01 04	non-ferrous metal dust and particles
12 01 05	plastics shavings and turnings
12 01 13	welding wastes
12 01 15	machining sludges other than those mentioned in 12 01 14
12 01 17	waste blasting material other than those mentioned in 12 01 16
12 01 21	spent grinding bodies and grinding materials other than those mentioned in 12 01 20
<b>15</b>	<b>Waste packaging, absorbents, wiping cloths, filter materials and protective clothing not otherwise specified</b>
<b>15 01</b>	<b>packaging (including separately collected municipal packaging waste)</b>
15 01 01	paper and cardboard packaging
15 01 02	plastic packaging
15 01 03	wooden packaging
15 01 04	metallic packaging
15 01 05	composite packaging
15 01 06	mixed packaging
15 01 07	glass packaging
15 01 09	textile packaging
<b>15 02</b>	<b>absorbents, filter materials, wiping cloths and protective clothing</b>
15 02 03	absorbents, filter materials, wiping cloths and protective clothing other than those mentioned in 15 02 02
<b>16</b>	<b>Wastes not otherwise specified in the list</b>
<b>16 01</b>	<b>end-of-life vehicles from different means of transport (including off-road machinery) and wastes from dismantling of end-of-life vehicles and vehicle maintenance (except 13, 14, 16 06 and 16 08)</b>
16 01 03	end-of-life tyres
16 01 12	brake pads other than those mentioned in 16 01 11
16 01 17	ferrous metal
16 01 18	non-ferrous metal
16 01 19	plastic
16 01 20	glass
<b>16 02</b>	<b>wastes from electrical and electronic equipment</b>
16 02 14	discarded equipment other than those mentioned in 16 02 09 to 16 02 13
16 02 16	components removed from discarded equipment other than those mentioned in 16 02 15

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
<b>16 03</b>	<b>off-specification batches and unused products</b>
16 03 04	inorganic wastes other than those mentioned in 16 03 03
16 03 06	organic wastes other than those mentioned in 16 03 05
<b>16 08</b>	<b>spent catalysts</b>
16 08 01	spent catalysts containing gold, silver, rhenium, rhodium, palladium, iridium or platinum (except 16 08 07)
16 08 03	spent catalysts containing transition metals or transition metal compounds not otherwise specified
<b>16 11</b>	<b>waste linings and refractories</b>
16 11 02	carbon-based linings and refractories from metallurgical processes others than those mentioned in 16 11 01
16 11 04	other linings and refractories from metallurgical processes other than those mentioned in 16 11 03
16 11 06	linings and refractories from non-metallurgical processes others than those mentioned in 16 11 05
<b>17</b>	<b>Construction and demolition wastes (including excavated soil from contaminated sites)</b>
<b>17 01</b>	<b>concrete, bricks, tiles and ceramics</b>
17 01 01	concrete
17 01 02	bricks
17 01 03	tiles and ceramics
17 01 07	mixtures of concrete, bricks, tiles and ceramics other than those mentioned in 17 01 06
<b>17 02</b>	<b>wood, glass and plastic</b>
17 02 01	wood
17 02 02	glass
17 02 03	plastic
<b>17 03</b>	<b>bituminous mixtures, coal tar and tarred products</b>
17 03 02	bituminous mixtures other than those mentioned in 17 03 01
<b>17 04</b>	<b>metals (including their alloys)</b>
17 04 01	copper, bronze, brass
17 04 02	aluminium
17 04 03	lead
17 04 04	zinc
17 04 05	iron and steel
17 04 06	tin
17 04 07	mixed metals
17 04 11	cables other than those mentioned in 17 04 10
<b>17 05</b>	<b>soil (including excavated soil from contaminated sites), stones and dredging spoil</b>
17 05 04	soil and stones other than those mentioned in 17 05 03

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
17 05 06	dredging spoil other than those mentioned in 17 05 05
17 05 08	track ballast other than those mentioned in 17 05 07
<b>17 06</b>	<b>insulation materials and asbestos-containing construction materials</b>
17 06 04	insulation materials other than those mentioned in 17 06 01 and 17 06 03
<b>17 09</b>	<b>other construction and demolition wastes</b>
17 09 04	mixed construction and demolition wastes other than those mentioned in 17 09 01, 17 09 02 and 17 09 03
<b>18</b>	<b>Wastes from human or animal health care and/or related research (except kitchen and restaurant wastes not arising from immediate health care)</b>
<b>18 01</b>	<b>wastes from natal care, diagnosis, treatment or prevention of disease in humans</b>
18 01 04	wastes whose collection and disposal is not subject to special requirements in order to prevent infection (for example dressings, plaster casts, linen, disposable clothing, diapers)
<b>18 02</b>	<b>wastes from research, diagnosis, treatment or prevention of disease involving animals</b>
18 02 03	wastes whose collection and disposal is not subject to special requirements in order to prevent infection
18 02 06	chemicals other than those mentioned in 18 02 05
<b>19</b>	<b>Wastes from waste management facilities, off-site waste water treatment plants and the preparation of water intended for human consumption and water for industrial use</b>
<b>19 01</b>	<b>wastes from incineration or pyrolysis of waste</b>
19 01 02	ferrous materials removed from bottom ash
19 01 12	bottom ash and slag other than those mentioned in 19 01 11
19 01 14	fly ash other than those mentioned in 19 01 13
19 01 16	boiler dust other than those mentioned in 19 01 15
19 01 18	pyrolysis wastes other than those mentioned in 19 01 17
19 01 19	sands from fluidised beds
<b>19 02</b>	<b>wastes from physico/chemical treatments of waste (including dechromatation, decyanidation, neutralisation)</b>
19 02 03	premixed wastes composed only of non-hazardous wastes
19 02 06	sludges from physico/chemical treatment other than those mentioned in 19 02 05
19 02 10	combustible wastes other than those mentioned in 19 02 08 and 19 02 09
<b>19 03</b>	<b>stabilised/solidified wastes</b>
19 03 05	stabilised wastes other than those mentioned in 19 03 04
19 03 07	solidified wastes other than those mentioned in 19 03 06
<b>19 04</b>	<b>vitrified waste and wastes from vitrification</b>
19 04 01	vitrified waste
<b>19 05</b>	<b>wastes from aerobic treatment of solid wastes</b>
19 05 01	non-composted fraction of municipal and similar wastes
19 05 02	non-composted fraction of animal and vegetable waste

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
19 05 03	off-specification compost
<b>19 06</b>	<b>wastes from anaerobic treatment of waste</b>
19 06 04	digestate from anaerobic treatment of municipal waste
19 06 06	digestate from anaerobic treatment of animal and vegetable waste
<b>19 08</b>	<b>wastes from waste water treatment plants not otherwise specified</b>
19 08 01	screenings
19 08 02	waste from desanding
19 08 05	sludges from treatment of urban waste water
19 08 09	grease and oil mixture from oil/water separation containing only edible oil and fats
19 08 12	sludges from biological treatment of industrial waste water other than those mentioned in 19 08 11
19 08 14	sludges from other treatment of industrial waste water other than those mentioned in 19 08 13
<b>19 09</b>	<b>wastes from the preparation of water intended for human consumption or water for industrial use</b>
19 09 01	solid waste from primary filtration and screenings
19 09 02	sludges from water clarification
19 09 03	sludges from decarbonation
19 09 04	spent activated carbon
19 09 05	saturated or spent ion exchange resins
19 09 06	solutions and sludges from regeneration of ion exchangers
<b>19 10</b>	<b>wastes from shredding of metal-containing wastes</b>
19 10 01	iron and steel waste
19 10 02	non-ferrous waste
19 10 04	fluff-light fraction and dust other than those mentioned in 19 10 03
19 10 06	other fractions other than those mentioned in 19 10 05
<b>19 11</b>	<b>wastes from oil regeneration</b>
19 11 06	sludges from on-site effluent treatment other than those mentioned in 19 11 05
<b>19 12</b>	<b>wastes from the mechanical treatment of waste (for example sorting, crushing, compacting, pelletising) not otherwise specified</b>
19 12 01	paper and cardboard
19 12 02	ferrous metal
19 12 03	non-ferrous metal
19 12 04	plastic and rubber
19 12 05	glass
19 12 07	wood other than that mentioned in 19 12 06
19 12 08	textiles
19 12 09	minerals (for example sand, stones)
19 12 10	combustible waste (refuse derived fuel)

<b>Table S2.1 Permitted waste types for disposal at a landfill for non-hazardous waste</b>	
<b>Waste code</b>	<b>Description</b>
19 12 12	other wastes (including mixtures of materials) from mechanical treatment of wastes other than those mentioned in 19 12 11
<b>19 13</b>	<b>wastes from soil and groundwater remediation</b>
19 13 02	solid wastes from soil remediation other than those mentioned in 19 13 01
19 13 04	sludges from soil remediation other than those mentioned in 19 13 03
19 13 06	sludges from groundwater remediation other than those mentioned in 19 13 05
<b>20</b>	<b>Municipal wastes (household waste and similar commercial, industrial and institutional wastes) including separately collected fractions</b>
<b>20 01</b>	<b>separately collected fractions (except 15 01)</b>
20 01 01	paper and cardboard
20 01 02	glass
20 01 08	biodegradable kitchen and canteen waste
20 01 10	clothes
20 01 11	textiles
20 01 25	edible oil and fat
20 01 28	paint, inks, adhesives and resins other than those mentioned in 20 01 27
20 01 30	detergents other than those mentioned in 20 01 29
20 01 36	discarded electrical and electronic equipment other than those mentioned in 20 01 21, 20 01 23 and 20 01 35
20 01 38	wood other than that mentioned in 20 01 37
20 01 39	plastics
20 01 40	metals
20 01 41	wastes from chimney sweeping
<b>20 02</b>	<b>garden and park wastes (including cemetery waste)</b>
20 02 01	biodegradable waste
20 02 02	soil and stones
20 02 03	other non-biodegradable wastes
<b>20 03</b>	<b>other municipal wastes</b>
20 03 01	mixed municipal waste
20 03 02	waste from markets
20 03 03	street-cleaning residues
20 03 04	septic tank sludge
20 03 06	waste from sewage cleaning
20 03 07	bulky waste

<b>Table S2.2 Permitted waste types for restoration</b>	
<b>Waste code</b>	<b>Description</b>
<b>01</b>	<b>Wastes resulting from exploration, mining, quarrying, and physical and chemical treatment of minerals</b>
01 04	wastes from physical and chemical processing of non-metalliferous minerals
01 04 08	waste gravel and crushed rocks other than those mentioned in 01 04 07
01 04 09	waste sand and clays
<b>02</b>	<b>Wastes from agriculture, horticulture, aquaculture, forestry, hunting and fishing, food preparation and processing</b>
02 04	wastes from sugar processing
02 04 01	soil from cleaning and washing beet
<b>03</b>	<b>Wastes from wood processing and the production of panels and furniture, pulp, paper and cardboard</b>
03 03	wastes from pulp, paper and cardboard production and processing
03 03 05	de-inking sludges from paper recycling
03 03 09	lime mud waste
<b>17</b>	<b>Construction and demolition wastes (including excavated soil from contaminated sites)</b>
17 05	soil (including excavated soil from contaminated sites), stones and dredging spoil
17 05 04	soil and stones other than those mentioned in 17 05 03
17 05 06	dredging spoil other than those mentioned in 17 05 05
<b>19</b>	<b>Wastes from waste management facilities, off-site waste water treatment plants and the preparation of water intended for human consumption and water for industrial use</b>
19 05	wastes from aerobic treatment of solid wastes
19 05 03	off-specification compost
19 08	wastes from waste water treatment plants not otherwise specified
19 08 05	sludges from treatment of urban waste water
19 09	wastes from the preparation of water intended for human consumption or water for industrial use
19 09 02	sludges from water clarification
19 12	wastes from the mechanical treatment of waste (for example sorting, crushing, compacting, pelletising) not otherwise specified
19 12 09	minerals (for example sand, stones)
19 13	wastes from soil and groundwater remediation
19 13 02	solid wastes from soil remediation other than those mentioned in 19 13 01
19 13 04	sludges from soil remediation other than those mentioned in 19 13 03
<b>20</b>	<b>Municipal wastes (household waste and similar commercial, industrial and institutional wastes) including separately collected fractions</b>
20 02	garden and park wastes (including cemetery waste)
20 02 02	soil and stones

<b>Table S2.3a Permitted waste types for Physico-Chemical Treatment (Activity A5 in Table S1.1) at Soil Treatment Facility</b>	
<b>Maximum Quantity</b>	<b>Annual throughput shall not exceed 50,000 tonnes for activities AR3, AR4, AR5, AR6, AR7, AR8, AR16</b>
<b>Waste code</b>	<b>Description</b>
<b>01</b>	<b>Wastes resulting from exploration, mining, quarrying, and physical and chemical treatment of minerals</b>
<b>01 04</b>	<b>wastes from physical and chemical processing of non-metalliferous minerals</b>
01 04 09	waste sand and clays
<b>01 05</b>	<b>Drilling muds and other wastes</b>
01 05 05*	oil-containing drilling muds and wastes
01 05 06*	drilling muds and other drilling wastes containing hazardous substances
<b>05</b>	<b>Wastes from petroleum refining, natural gas purification and pyrolytic treatment of coal</b>
<b>05 01</b>	<b>wastes from petroleum refining</b>
05 01 05*	oil spills
<b>13</b>	<b>Oil wastes and wastes of liquid fuels (except edible oils, and those in chapters 05, 12 and 19)</b>
<b>13 05</b>	<b>Oil/water separator contents</b>
13 05 01*	solids from grit chambers and oil/water separators
13 05 02*	sludges from oil/water separators
13 05 03*	interceptor sludges
13 05 08*	mixtures of wastes from grit chambers and oil/water separators
<b>17</b>	<b>Construction and demolitions wastes (including excavated soil from contaminated sites)</b>
<b>17 02</b>	<b>Wood, glass and plastic</b>
17 02 01	wood
<b>17 05</b>	<b>Soil (including excavated soil from contaminated sites), stones and dredging spoil</b>
17 05 03*	soil and stones containing hazardous substances
17 05 04	soil and stones other than those mentioned in 17 05 03
17 05 05*	dredging spoil containing hazardous substances
17 05 06	dredging spoil other than those mentioned in 17 05 05
17 05 07*	track ballast containing hazardous substances
17 05 08	track ballast other than those mentioned in 17 05 07
<b>19</b>	<b>Wastes from waste management facilities, off-site waste water treatment plants and the preparation of water intended for human consumption and water for industrial use</b>
<b>19 02</b>	<b>Wastes from physico/chemical treatment treatments of waste (including dechromatation, decyanidation, neutralisation)</b>
19 02 05*	sludges from physico/chemical treatment containing hazardous substances – wastes suitable for biological treatment only
19 02 06	sludges from physico/chemical treatment other than those mentioned in 19 02 05 – wastes suitable for biological treatment only

<b>Table S2.3a Permitted waste types for Physico-Chemical Treatment (Activity A5 in Table S1.1) at Soil Treatment Facility</b>	
<b>Maximum Quantity</b>	<b>Annual throughput shall not exceed 50,000 tonnes for activities AR3, AR4, AR5, AR6, AR7, AR8, AR16</b>
<b>Waste code</b>	<b>Description</b>
<b>19 05</b>	<b>wastes from aerobic treatment of solid wastes</b>
19 05 03	off-specification compost
<b>19 08</b>	<b>wastes from waste water treatment plants not otherwise specified</b>
19 08 02	waste from desanding
19 08 13*	sludges containing hazardous substances from other treatment of industrial waste water
19 08 14	sludges from other treatment of industrial waste water other than those mentioned in 19 08 13
<b>19 12</b>	<b>wastes from the mechanical treatment of waste (for example sorting, crushing, compacting, pelletising) not otherwise specified</b>
19 12 07	wood other than those mentioned in 19 12 06
<b>19 13</b>	<b>Wastes from soil and groundwater remediation</b>
19 13 01*	solid wastes from soil remediation containing hazardous substances
19 13 02	solid wastes from soil remediation other than those mentioned in 19 13 01
19 13 03*	sludges from soil remediation containing hazardous substances
19 13 04	sludges from soil remediation other than those mentioned in 19 13 03
<b>20</b>	<b>Municipal wastes (household waste and similar commercial, industrial and institutional wastes) including separately collected fractions</b>
<b>20 01</b>	<b>Separately collected fractions (except 15 01)</b>
20 01 38	wood other than that mentioned in 20 01 37
<b>20 02</b>	<b>Garden and park wastes (including cemetery waste)</b>
20 02 01	biodegradable waste
20 02 02	soil and stones
<b>20 03</b>	<b>Other municipal wastes</b>
20 03 03	street cleaning residues



<b>Table S2.3b Permitted waste types for Biological Treatment (Activity A3/A4 in Table S1.1) at Soil Treatment Facility</b>	
<b>Maximum Quantity</b>	<b>Annual throughput shall not exceed 50,000 tonnes for activities AR3, AR4, AR5, AR6, AR7, AR8, AR16</b>
<b>Waste code</b>	<b>Description</b>
<b>01</b>	<b>Wastes resulting from exploration, mining, quarrying, and physical and chemical treatment of minerals</b>
<b>01 04</b>	<b>wastes from physical and chemical processing of non-metalliferous minerals</b>
01 04 09	waste sand and clays
<b>01 05</b>	<b>Drilling muds and other wastes</b>
01 05 05*	oil-containing drilling muds and wastes
01 05 06*	drilling muds and other drilling wastes containing hazardous substances
<b>05</b>	<b>Wastes from petroleum refining, natural gas purification and pyrolytic treatment of coal</b>
<b>05 01</b>	<b>wastes from petroleum refining</b>
05 01 05*	oil spills
<b>13</b>	<b>Oil wastes and wastes of liquid fuels (except edible oils, and those in chapters 05, 12 and 19)</b>
<b>13 05</b>	<b>Oil/water separator contents</b>
13 05 01*	solids from grit chambers and oil/water separators
13 05 02*	sludges from oil/water separators
13 05 03*	interceptor sludges
13 05 08*	mixtures of wastes from grit chambers and oil/water separators
<b>17</b>	<b>Construction and demolitions wastes (including excavated soil from contaminated sites)</b>
<b>17 02</b>	<b>Wood, glass and plastic</b>
17 02 01	wood
<b>17 05</b>	<b>Soil (including excavated soil from contaminated sites), stones and dredging spoil</b>
17 05 03*	soil and stones containing hazardous substances
17 05 04	soil and stones other than those mentioned in 17 05 03
17 05 05*	dredging spoil containing hazardous substances
17 05 06	dredging spoil other than those mentioned in 17 05 05
17 05 07*	track ballast containing hazardous substances
17 05 08	track ballast other than those mentioned in 17 05 07
<b>19</b>	<b>Wastes from waste management facilities, off-site waste water treatment plants and the preparation of water intended for human consumption and water for industrial use</b>
<b>19 02</b>	<b>Wastes from physico/chemical treatment treatments of waste (including dechromatation, decyanidation, neutralisation)</b>
19 02 05*	sludges from physico/chemical treatment containing hazardous substances – wastes suitable for biological treatment only
19 02 06	sludges from physico/chemical treatment other than those mentioned in 19 02 05 – wastes suitable for biological treatment only
<b>19 05</b>	<b>wastes from aerobic treatment of solid wastes</b>

<b>Table S2.3b Permitted waste types for Biological Treatment (Activity A3/A4 in Table S1.1) at Soil Treatment Facility</b>	
<b>Maximum Quantity</b>	<b>Annual throughput shall not exceed 50,000 tonnes for activities AR3, AR4, AR5, AR6, AR7, AR8, AR16</b>
<b>Waste code</b>	<b>Description</b>
19 05 03	off-specification compost
<b>19 08</b>	<b>wastes from waste water treatment plants not otherwise specified</b>
19 08 02	waste from desanding
19 08 13*	sludges containing hazardous substances from other treatment of industrial waste water
19 08 14	sludges from other treatment of industrial waste water other than those mentioned in 19 08 13
<b>19 12</b>	<b>wastes from the mechanical treatment of waste (for example sorting, crushing, compacting, pelletising) not otherwise specified</b>
19 12 07	wood other than those mentioned in 19 12 06
19 12 11*	other wastes (including mixtures of materials) from mechanical treatment of waste containing hazardous substances
<b>19 13</b>	<b>Wastes from soil and groundwater remediation</b>
19 13 01*	solid wastes from soil remediation containing hazardous substances
19 13 02	solid wastes from soil remediation other than those mentioned in 19 13 01
19 13 03*	sludges from soil remediation containing hazardous substances
19 13 04	sludges from soil remediation other than those mentioned in 19 13 03
<b>20</b>	<b>Municipal wastes (household waste and similar commercial, industrial and institutional wastes) including separately collected fractions</b>
<b>20 01</b>	<b>Separately collected fractions (except 15 01)</b>
20 01 38	wood other than that mentioned in 20 01 37
<b>20 02</b>	<b>Garden and park wastes (including cemetery waste)</b>
20 02 01	biodegradable waste
<b>20 03</b>	<b>Other municipal wastes</b>
20 03 03	street cleaning residues

<b>Table S2.4 Permitted waste types for Site Treatment Facility for the acceptance of bonded asbestos contaminated soil</b>	
<b>Maximum quantity</b>	<b>Annual throughput shall not exceed 50,000 tonnes for activities AR3, AR4, AR5, AR6, AR7, AR8, AR16</b>
<b>Waste code</b>	<b>Description</b>
<b>17</b>	<b>CONSTRUCTION AND DEMOLITION WASTES (INCLUDING EXCAVATED SOIL FROM CONTAMINATED SITE)</b>
<b>17 05</b>	<b>soil (including excavated soil from contaminated sites), stones and dredging spoil</b>

<b>Table S2.4 Permitted waste types for Site Treatment Facility for the acceptance of bonded asbestos contaminated soil</b>	
<b>Maximum quantity</b>	<b>Annual throughput shall not exceed 50,000 tonnes for activities AR3, AR4, AR5, AR6, AR7, AR8, AR16</b>
<b>Waste code</b>	<b>Description</b>
<b>17</b>	<b>CONSTRUCTION AND DEMOLITION WASTES (INCLUDING EXCAVATED SOIL FROM CONTAMINATED SITE)</b>
17 05 03*	soil and stones containing hazardous substances
<b>17 06</b>	<b>insulation materials and asbestos-containing construction materials</b>
17 06 05*	other construction materials containing asbestos

<b>Table S2.5 Raw materials and fuels</b>	
<b>Raw materials and fuel description</b>	<b>Specification</b>
NPK fertilizers	50 tonnes storage maximum at any one time

## Schedule 3 – Emissions and monitoring

Monitoring point reference/Description	Limit	Monitoring frequency	Monitoring method
Phase 1: Two leachate monitoring points in addition to the collection sump for each hydraulically separate cell unless otherwise agreed in writing with the Agency.	3 m above cell base	Monthly	In accordance with Environment Agency document LFTGN02 (February 2003) 'Guidance on Monitoring of Landfill Leachate, Groundwater and Surface Water' or such other subsequent guidance as may be agreed in writing with the Environment Agency.
Phase 2: Two leachate monitoring points in addition to the collection sump for each hydraulically separate cell unless otherwise agreed in writing with the Agency.	6 m above cell base		

Emission point Ref. & Location	Parameter	Source	Limit (including unit)	Reference Period	Monitoring Frequency	Monitoring Standard or Method
Engines 1-5 Landfill gas engine on Plan ESID4	Oxides of Nitrogen	Gas utilisation plant	650 mg/m <sup>3</sup>	Hourly mean	Annually	As per M2 or such other subsequent guidance as may be agreed in writing with the Environment Agency.
	CO		1500 mg/m <sup>3</sup>			
	Total VOCs		1750 mg/m <sup>3</sup>			
A1: Flare on plan 116-1-3026/A dated 27/02/2006	Oxides of Nitrogen	Landfill Gas Flares	150 mg/m <sup>3</sup>	Hourly mean	Annually	As per M2 or such other subsequent guidance as may be agreed in writing with the Environment Agency. Monitoring is unnecessary where the flare is active for <10% of the year.
	CO		50 mg/m <sup>3</sup>			
	Total VOCs		10 mg/m <sup>3</sup>			
Biofilter Monitoring Point as shown on plan 3695-CAU-XX-XX-DR-V-1801	Ammonia	Biofilter at Soil Treatment Facility	20 mg/m <sup>3</sup>	Hourly mean	Every six months	As agreed in writing with the Environment Agency.
	TVOCs		40 mg/m <sup>3</sup>			
	Hydrogen Sulphide		No Limit			

Table S3.3 Point source emissions to water (other than sewer) – emission limits and monitoring requirements						
Emission point Ref. & Location	Parameter	Source	Limit (incl unit)	Reference Period	Monitoring Frequency	Monitoring Standard or Method
W1 On Plan ESID14 dated August 2007	Suspended Solids	Site drainage from the site surface water drainage system	75 mg/l	Spot Sample	Monthly	As specified in Environment Agency Guidance TGN02 'Monitoring of Landfill Leachate, Groundwater and Surface Water' (February 2003), <u>risk assessments for your environmental permit (www.gov.uk)</u> or such other subsequent guidance as may be agreed in writing with the Environment Agency
	Oil or grease		No visible discharge	Spot Sample	Monthly	
	pH		>6 and <9	Spot Sample	Monthly	
	Volume		750 m <sup>3</sup> /day	24 hours	Monthly	
	Flow rate		20 l/s	Instantaneous	Monthly	
	Conductivity		No limit set	Spot Sample	Monthly	
	Ammoniacal Nitrogen		No limit set	Spot Sample	Monthly	
	Chloride		No limit set	Spot Sample	Monthly	
	DO		No limit set	Spot Sample	Monthly	
	Sulphate		No limit set	Spot Sample	Quarterly	
	Alkalinity (as CaCO <sub>3</sub> )		No limit set	Spot Sample	Quarterly	
	COD		No limit set	Spot Sample	Quarterly	
	TON		No limit set	Spot Sample	Quarterly	
	Na		No limit set	Spot Sample	Quarterly	
K	No limit set	Spot Sample	Quarterly			
Ca	No limit set	Spot Sample	Quarterly			

**Table S3.3 Point source emissions to water (other than sewer) – emission limits and monitoring requirements**

Emission point Ref. & Location	Parameter	Source	Limit (incl unit)	Reference Period	Monitoring Frequency	Monitoring Standard or Method
	Mg		No limit set	Spot Sample	Quarterly	
	Cr		No limit set	Spot Sample	Quarterly	
	Cd		No limit set	Spot Sample	Quarterly	
	Mn		No limit set	Spot Sample	Quarterly	
	Fe		No limit set	Spot Sample	Quarterly	
	Cu		No limit set	Spot Sample	Quarterly	
	Ni		No limit set	Spot Sample	Quarterly	
	Zn		No limit set	Spot Sample	Quarterly	
	Pb		No limit set	Spot Sample	Quarterly	
	Hg		No limit set	Spot Sample	Quarterly	
	List 1 substances identified in leachate, unless otherwise agreed in writing with the Environment Agency		No limit set	Spot Sample	Annually	

<b>Table S3.4 Point source emissions to sewer, effluent treatment plant or by tankering or other transfer off-site – emission limits and monitoring requirements</b>						
<b>Emission point Ref. &amp; Location</b>	<b>Parameter</b>	<b>Source</b>	<b>Limit (including unit)</b>	<b>Reference Period</b>	<b>Monitoring Frequency</b>	<b>Monitoring Standard or Method</b>
Treated Process Water Monitoring Point as shown on Plan 3695-CAU-XX-XX-DR-V-1801	No parameters	Soil Treatment Facility	No limits	-	-	As agreed in writing with the Environment Agency

<b>Table S3.5 Groundwater – emission limits and monitoring requirements</b>					
<b>Monitoring point reference</b>	<b>Parameter</b>	<b>Limit (including unit)</b>	<b>Reference Period</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>
GW5.01 as detailed on drawing number 124E232 dated February 2013	Ammoniacal Nitrogen	1.41 mg/l <sup>1</sup>	Spot Sample	Monthly	As specified in Environment Agency Guidance TGN02 'Monitoring of Landfill Leachate, Groundwater and Surface Water' (February 2003), <u>risk assessments for your environmental permit (www.gov.uk)</u> or such other subsequent guidance as may be agreed in writing with the Environment Agency
	Chloride	225 mg/l <sup>1</sup>		Monthly	
	Mecoprop	0.04 µg/l <sup>1</sup>		Quarterly	
	Xylene	3.0 µg/l <sup>1</sup>		Quarterly	
	Trichlorobenzene	0.01 µg/l <sup>1</sup>		Quarterly	
GW08 as detailed on drawing number 124E232 dated February 2013	Ammoniacal Nitrogen	1.80 mg/l		Monthly	
	Chloride	410 mg/l		Monthly	
	Mecoprop	0.04 µg/l		Quarterly	
	Xylene	3.0 µg/l		Quarterly	
	Trichlorobenzene	0.01 µg/l		Quarterly	
1. Unless otherwise agreed in writing by the Environment Agency					

<b>Table S3.6 Landfill gas in external monitoring boreholes – limits and monitoring requirements</b>				
<b>Monitoring point Ref. /description</b>	<b>Parameter</b>	<b>Limit (including units)</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>
BH1, BH2, BH5-BH18, BH22-BH35 as detailed on drawing no. 124E232 dated February 2013	Methane	1% v/v	Monthly	As per LFTGN03 (Sept 2004) or such other subsequent guidance as may be agreed in writing with the Environment Agency.  Record whether the ground is: waterlogged frozen snow covered
	Carbon Dioxide	1.5% v/v		
	Oxygen	No limit		
	Atmospheric pressure	No limit		
	Differential Pressure	No limit		
BH3, BH3.01, BH3.02, BH4.00, BH4.01 as detailed on drawing no. 124E232 dated February 2013	Methane	1% v/v		
	Carbon Dioxide	2% v/v		
	Oxygen	No limit		
	Atmospheric pressure	No limit		
	Differential Pressure	No limit		
BH4.02 as detailed on drawing no. 124E232 dated February 2013	Methane	1% v/v		
	Carbon Dioxide	11.5% v/v		
	Oxygen	No limit		
	Atmospheric pressure	No limit		
	Differential Pressure	No limit		
BH36, BH37, BH38.1, BH39.1, BH40.1, BH41-BH44 as detailed on drawing no. 124E232 dated February 2013	Methane	1% v/v		
	Oxygen	No limit		
	Atmospheric pressure	No limit		
	Differential Pressure	No limit		
BH36 and BH37	Carbon Dioxide	1.5% v/v		
BH38.1	Carbon Dioxide	2.6% v/v		
BH39.1	Carbon Dioxide	5.5% v/v		



<b>Table S3.6 Landfill gas in external monitoring boreholes – limits and monitoring requirements</b>				
<b>Monitoring point Ref. /description</b>	<b>Parameter</b>	<b>Limit (including units)</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>
BH40.1	Carbon Dioxide	3.3% v/v	Monthly	As per LFTGN03 (Sept 2004) or such other subsequent guidance as may be agreed in writing with the Environment Agency.  Record whether the ground is: waterlogged frozen snow covered
BH41	Carbon Dioxide	3.0% v/v		
BH42	Carbon Dioxide	2.7% v/v		
BH43	Carbon Dioxide	2.2% v/v		
BH44	Carbon Dioxide	2.3% v/v		

<b>Table S3.7 Particulate matter in ambient air - monitoring requirements</b>					
<b>Monitoring Point Ref. /Description</b>	<b>Parameter</b>	<b>Limit</b>	<b>Reference Period</b>	<b>Monitoring Frequency</b>	<b>Monitoring Standard or Method</b>
Dust monitoring points as detailed on drawing no.ESID14, dated August 2007	Deposited dust	200 mg/m <sup>2</sup> /day	24 hours	Monthly	
	Suspended particulate PM10	None set	In accordance with correspondence ref: 402.0197.00423 dated 06/04/2006	In accordance with correspondence ref: 402.0197.00423 dated 06/04/2006	

<b>Table S3.8 Landfill gas emissions from capped surfaces for cells that have accepted non-hazardous biodegradable waste – monitoring requirements</b>			
<b>Monitoring point Ref. /description</b>	<b>Parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring Standard or method</b>
Permanently capped zone	Methane concentration	Every 12 months	As per LFTGN 07 (v2 2010) or such other subsequent guidance as may be agreed in writing with the Environment Agency.

<b>Table S3.8 Landfill gas emissions from capped surfaces for cells that have accepted non-hazardous biodegradable waste – monitoring requirements</b>			
<b>Monitoring point Ref. /description</b>	<b>Parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring Standard or method</b>
Temporarily capped zone	Methane concentration	Every 12 months	As per LFTGN 07 (v2 2010) or such other subsequent guidance as may be agreed in writing with the Environment Agency.
Whole site	Total methane emission	As agreed with the Environment Agency	As per LFTGN 07 (v2 2010) or such other subsequent guidance as may be agreed in writing with the Environment Agency.
Uncapped areas	Methane concentration	Every 12 months	As agreed with the Environment Agency based on the wording of revised LFTGN 07 or landfill sector guidance or such other subsequent guidance as may be agreed in writing with the Environment Agency.

<b>Table S3.9 Groundwater – other monitoring requirements</b>			
<b>Monitoring Point Ref./Description</b>	<b>Parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>
Up gradient MEPP	Water level, electrical conductivity, chloride, ammoniacal nitrogen, pH,	Quarterly	As specified in Environment Agency Guidance TGN02 'Monitoring of Landfill Leachate, Groundwater and Surface Water' (February 2003), <u><a href="#">risk assessments for your environmental permit (www.gov.uk)</a></u> or such other subsequent guidance as may be agreed in writing with the Environment Agency
	total alkalinity, magnesium, potassium, total sulphates, calcium, sodium, chromium, copper, iron, lead, nickel, zinc, manganese	Annually	
	Hazardous substances	Annually for first six years of operation	
Down or cross gradient MEPP	Water level, electrical conductivity, chloride, ammoniacal nitrogen, pH,	Quarterly	As specified in Environment Agency Guidance TGN02 'Monitoring of Landfill Leachate, Groundwater and Surface Water' (February 2003), <u><a href="#">risk assessments for your environmental permit (www.gov.uk)</a></u> or such other subsequent guidance as may be agreed in writing with the Environment Agency  After the initial 6 year monitoring period for hazardous substances, if the results of quarterly or annual monitoring suggest an increase in contamination, the operator shall also undertake a full leachate hazardous substances screen.
	total alkalinity, magnesium, potassium, total sulphates, calcium, sodium, chromium, copper, iron, lead, nickel, zinc, manganese	Annually	
	Hazardous substances detected in leachate	Annually for first six years of operation then every two years	
MEPP	Base of monitoring point (mAoD)	Annually	

<b>Table S3.10 Landfill gas – other monitoring requirements</b>				
<b>Monitoring Point Ref. /Description</b>	<b>Parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>	<b>Other specifications</b>
In waste gas monitoring boreholes or sealed leachate wells or sacrificial gas extraction system	Methane Carbon Dioxide Oxygen Carbon Monoxide Differential pressure Atmospheric pressure	Monthly until gas extraction commences	Calibrated handheld monitoring instrument	For cells or phases which have no active gas extraction. Gas extraction system shall be installed and extraction commenced once monitoring shows onset of methane production in waste at a rate that can be sustainably extracted. Once gas extraction has commenced in a particular cell or phase, there is no longer a requirement to carry out this monitoring.
	Hydrogen sulphide	Quarterly	Calibrated handheld monitoring instrument or Tedlar Bag sample in accordance with LFTGN04 (V3, March 2010) or other such subsequent guidance as may be agreed in writing with the Environment Agency or a method agreed with the Environment Agency.	For cells or phases which have no active gas extraction. Once gas extraction has commenced in a particular cell or phase, there is no longer a requirement to carry out this monitoring. Concentrations of hydrogen sulphide shall be assessed in accordance with the gas and odour management plans

<b>Table S3.10 Landfill gas – other monitoring requirements</b>				
<b>Monitoring Point Ref. /Description</b>	<b>Parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>	<b>Other specifications</b>
Gas collection system at well control valve, manifolds (if applicable) and strategic points on gas system	Methane Carbon Dioxide Oxygen Carbon Monoxide Atmospheric pressure Gas flow rate or suction % Balance Gas (calculated as the difference between the sum of measured gases and 100%)	Monthly or at such other frequency as may be agreed in writing with the Environment Agency.	Calibrated handheld monitoring instrument	Where the oxygen concentration exceeds 5% or the % balance gas is greater than 20% an assessment of air ingress into the system shall be undertaken. Where the concentration of carbon monoxide exceeds 100ppm then further investigation shall be undertaken Record the ambient air temperature and whether the ground is: waterlogged frozen snow covered
Gas collection system at well control valve	Hydrogen sulphide	Six monthly	Calibrated handheld monitoring instrument or Tedlar Bag sample in accordance with LFTGN04 (v3, March 2010) or other such subsequent guidance as may be agreed in writing with the Environment Agency or a method agreed with the Environment Agency.	Concentrations of hydrogen sulphide shall be assessed in accordance with the gas and odour management plans

<b>Table S3.10 Landfill gas – other monitoring requirements</b>				
<b>Monitoring Point Ref. /Description</b>	<b>Parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>	<b>Other specifications</b>
Output to flare or LFG Utilisation Compound	Trace gas	Annually	Trace gas analysis in accordance with LFTGN04 (v3, March 2010) or such other subsequent guidance as may be agreed in writing with the Environment Agency [or a trace gas characterisation method agreed with the Environment Agency].	The concentration of trace gas components shall be assessed against the assumptions made in the Landfill gas risk assessment and dispersion modelling.
Output to flare or LFG Utilisation Compound	Methane Carbon Dioxide Oxygen Gas flow rate Suction % Balance Gas (calculated as the difference between the sum of measured gases and 100%)	Weekly		Where the oxygen concentration exceeds 5% or the % balance gas is greater than 20% an assessment of air ingress into the system shall be undertaken.

<b>Table S3.10 Landfill gas – other monitoring requirements</b>				
<b>Monitoring Point Ref. /Description</b>	<b>Parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>	<b>Other specifications</b>
Flare 1 shown on Plan 3026/A dated 27/02/2006	Temperature	As per LFTGN05 (v2, March 2010) or such other subsequent guidance as may be agreed in writing with the Environment Agency.	As per M2 or such other subsequent guidance as may be agreed in writing with the Environment Agency.	
Gas engines 1-5, post turbo	NOx and CO	Quarterly	In accordance with Appendix C of LFTGN08, (v2, 2010) or such other subsequent guidance as may be agreed in writing with the Environment Agency.	Where monitoring using hand-held, electrochemical equipment indicates an exceedance of the emissions standards specified in Table S3.2, these shall be used as action levels and the operator shall investigate the cause and take appropriate measures to reduce emissions.

<b>Table S3.11 Leachate – other monitoring requirements</b>				
<b>Monitoring point reference or description</b>	<b>Parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>	<b>Other specifications</b>
<b>Operational Cells or Phases</b> (Any cell or phases that do not have a final engineered cap agreed in accordance with condition 2.6)			At leachate compliance point as listed in table S3.1.  As specified in Environment Agency Guidance TGN02 'Monitoring of Landfill Leachate, Groundwater and Surface Water' (February 2003), <u>risk assessments for your environmental permit (www.gov.uk)</u> or such other subsequent guidance as may be agreed in writing with the Environment Agency	
MEPP	pH, EC, total alkalinity, ammoniacal nitrogen, Chloride, COD, BOD, cadmium, chromium, copper, lead, nickel, iron, arsenic, magnesium, potassium, total sulphates, calcium, sodium, zinc, manganese	Quarterly		None
MEPP	Hazardous substances	Annually		None
MEPP	Depth to base (mAoD)	Annually		None
<b>Non Operational Cells or Phases</b> (Any cell or phases that have a final engineered cap agreed in accordance with condition 2.6)				
MEPP	pH, EC, total alkalinity, ammoniacal nitrogen, Chloride, COD, BOD, cadmium, chromium, copper, lead, nickel, iron, arsenic, magnesium, potassium, total sulphates, calcium, sodium, zinc, manganese	Annually		
MEPP	Hazardous substances	Once every four years	None	
MEPP	Depth to base (mAoD)	Annually		



<b>Table S3.12 Surface water – other monitoring requirements</b>				
<b>Monitoring Point Ref. /Description</b>	<b>Parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring standard or method</b>	<b>Other specifications</b>
MEPP	Ammoniacal nitrogen Chloride Suspended Solids Visual Oil and Grease pH electrical conductivity	Monthly	Spot sample	As specified in Environment Agency Guidance TGN02 'Monitoring of Landfill Leachate, Groundwater and Surface Water' (February 2003), <u>risk assessments for your environmental permit</u> ( <a href="http://www.gov.uk">www.gov.uk</a> ) or such other subsequent guidance as may be agreed in writing with the Environment Agency

<b>Table S3.13 Process monitoring requirements</b>				
<b>Monitoring Point</b>	<b>Substance or parameter</b>	<b>Monitoring frequency</b>	<b>Monitoring method</b>	<b>Other specifications</b>
Biofilter Monitoring Point as shown on Plan 3695-CAU-XX-XX-DR-V-1801	Moisture content, flow rate, nutrient levels, contaminant elimination	As required	As required	Biofilter should be checked and maintained to ensure appropriate temperature and moisture content on a daily basis. Monitoring equipment shall be available on-site and used as required.

## Schedule 4 – Reporting

Parameters, for which reports shall be made, in accordance with conditions of this permit, are listed below.

<b>Table S4.1 Reporting of monitoring data</b>		
<b>Parameter</b>	<b>Reporting period</b>	<b>Period ends</b>
Leachate and/ or groundwater level As specified by schedule 3, table S3.1	Every 3 months	31 March, 30 June, 30 September, 31 December
Point source emission to air As specified by schedule 3, table S3.2	Every 12 months	31 December
Point source emission to water (other than sewer) As specified by schedule 3, table S3.3	Every 3 months	31 March, 30 June, 30 September, 31 December
Point source emission to sewer As specified by schedule 3, table S3.4	Every 3 months	31 March, 30 June, 30 September, 31 December
Emission to groundwater As specified by schedule 3, table S3.5	Every 3 months	31 March, 30 June, 30 September, 31 December
Landfill gas in external monitoring boreholes As specified by schedule 3, table S3.6	Every 3 months	31 March, 30 June, 30 September, 31 December
Particulate matter in ambient air. As required by schedule 3, table S3.7	Every 6 months	30 June, 31 December
Emission of landfill gas from capped surfaces As specified by schedule 3, table S3.8	Every 12 months	31 December
Other groundwater monitoring As specified by schedule 3, table S3.9	Every 3 months	31 March, 30 June, 30 September, 31 December
Other Landfill gas monitoring As specified by schedule 3, table S3.10	Every 3 months	31 March, 30 June, 30 September, 31 December
Trace gas monitoring	Every 12 months	31 December
Other leachate monitoring As specified by schedule 3, table S3.11	Every 12 months	31 December
Other surface water monitoring As specified by schedule 3, table S3.12	Every 12 months	31 December

<b>Table S4.1 Reporting of monitoring data</b>		
<b>Parameter</b>	<b>Reporting period</b>	<b>Period ends</b>
Process monitoring requirements As specified by Schedule 3, table S3.13	As agreed with the Environment Agency	31 December
Meteorological data Landfill Directive, annex III, section 2	Every 12 months	31 December

\* - where the reporting period is 12 months, you may submit this information as part of the 'annual report' required by condition 4.2.2.

<b>Table S4.2 Annual production/treatment</b>	
Leachate: Disposed of off site; Disposed of to any onsite effluent treatment plant; Recirculated into the waste mass. Accepted from offsite for treatment at any onsite effluent treatment plant.	Cubic metres/year
Landfill gas: combustion in flares; combustion in gas engines; Other methods of gas utilisation. Average methane content entering the landfill gas utilisation or treatment compound (based on the annual average of Table S3.9 monitoring) Methane generation rate (50%ile from a representative model)	Normalised cubic metres/year  % methane v/v  m <sup>3</sup> /hr

<b>Table S4.3 Performance Parameters</b>			
<b>Parameter</b>	<b>Frequency of assessment</b>	<b>Annual total</b>	<b>Unit</b>
Energy used (including for leachate treatment)	Annually		MWh of electricity or natural gas

<b>Table S4.4 Reporting Forms</b>		
<b>Media/parameter</b>	<b>Reporting Format</b>	<b>Date of Form</b>
Leachate	Form leachate 1 or other reporting format to be agreed in writing with the Environment Agency	02/02/17
Air	Form Air 1 or other reporting format to be agreed in writing with the Environment Agency	02/02/17
Controlled water	Form Water 1 or other reporting format to be agreed in writing with the Environment Agency	02/02/17
Groundwater	Form Groundwater 1 or other reporting format to be agreed in writing with the Environment Agency	02/02/17
Landfill gas	Form LFG 1 or other reporting format to be agreed in writing with the Environment Agency	02/02/17
Particulate matter	Form Particulate 1 or other reporting format to be agreed in writing with the Environment Agency	02/02/17
Waste Return	Waste Return Form RATS2E	02/02/17
Landfill topographical surveys and interpretation	Reporting format to be agreed in writing with the Environment Agency	02/02/17

# Schedule 5 – Notification

This page outlines the information that the operator must provide.

Units of measurement used in information supplied under Part A and B requirements shall be appropriate to the circumstances of the emission. Where appropriate, a comparison should be made of actual emissions and authorised emission limits.

If any information is considered commercially confidential, it should be separated from non-confidential information, supplied on a separate sheet and accompanied by an application for commercial confidentiality under the provisions of the EP Regulations.

## Part A

Permit Number	
Name of operator	
Location of Facility	
Time and date of the detection	

<b>(a) Notification requirements for any incident or accident which significantly affects or may significantly affect the environment</b>	
<b>To be notified within 24 hours of detection</b>	
Date and Time of the event	
Reference or description of the location of the event	
Description of where any release into the environment took place	
Substances(s) potentially released	
Best estimate of the quantity or rate of release of substances	
Measures taken, or intended to be taken, to stop any emission	
Description of the failure or accident.	

<b>(b) Notification requirements for the breach of a limit</b>	
<b>To be notified within 24 hours of detection unless otherwise specified below</b>	
Emission point reference/ source	
Parameter(s)	
Limit	
Measured value and uncertainty	
Date and time of monitoring	

<b>(b) Notification requirements for the breach of a limit</b>	
<b>To be notified within 24 hours of detection unless otherwise specified below</b>	
Measures taken, or intended to be taken, to stop the emission	

<b>Time periods for notification following detection of a breach of a limit</b>	
<b>Parameter</b>	<b>Notification period</b>

<b>(c) Notification requirements in the event of a breach of permit condition which poses an immediate danger to human health or threatens to cause an immediate significant adverse effect on the environment</b>	
<b>To be notified within 24 hours of detection</b>	
Description of where the effect on the environment was detected	
Substances(s) detected	
Concentrations of substances detected	
Date of monitoring/sampling	

## Part B to be supplied as soon as practicable

Any more accurate information on the matters for notification under Part A.	
Measures taken, or intended to be taken, to prevent a recurrence of the incident	
Measures taken, or intended to be taken, to rectify, limit or prevent any pollution of the environment which has been or may be caused by the emission	
The dates of any unauthorised emissions from the facility in the preceding 24 months.	

<b>Name*</b>	
<b>Post</b>	
<b>Signature</b>	
<b>Date</b>	

\* authorised to sign on behalf of the operator

## Schedule 6 – Interpretation

“accident” means an accident that may result in pollution.

“annually” means once every year.

“application” means the application for this permit, together with any additional information supplied by the operator as part of the application and any response to a notice served under Schedule 5 to the EP Regulations.

“authorised officer” means any person authorised by the Environment Agency under section 108(1) of The Environment Act 1995 to exercise, in accordance with the terms of any such authorisation, any power specified in section 108(4) of that Act.

“Background concentration” means such concentration of that substance as is present in:

- For emissions to surface water, the surface water quality up-gradient of the site; or
- For emissions to sewer, the surface water quality up-gradient of the sewage treatment works discharge; or
- For emissions of landfill gas, the ground or air outside the site and not attributable to the site.

(3) “Cell layout drawing” means: A drawing or drawings of the proposed new cell that illustrate(s) in sufficient detail:

- (i) the location of the new cell on the site;
- (ii) the proposed level (Above Ordnance Datum) of the base of the excavation;
- (iii) the proposed finished levels of all containment and leachate drainage layers;
- (iv) the positions of leachate management infrastructure; and
- (v) the positions of landfill gas infrastructure (if appropriate).

(4) A detailed written explanation of any minor design changes from the most recently approved cell that result from the new cell layout. This would include, for example:

- (i) changes to slope length and gradient within the cell;
- (ii) new leachate or landfill gas infrastructure construction design;
- (iii) slope stability issues such as new basal excavation level; and/or
- (iv) depth of waste.

“Construction Proposals” means written information, at a level of detail appropriate to the complexity and pollution risk, on the design, specifications of materials selected, stability assessment (where relevant) and the construction quality assurance (CQA) programme in relation to the New Cell or Landfill Infrastructure.

“CQA Validation Report” means the final “as built” construction and engineering details of the New Cell or of the Landfill Infrastructure. It must provide a comprehensive record of the construction and must include, where relevant:

- The results of all testing required by the CQA programme - this must include the records of any failed tests with a written explanation, details of the remedial action taken, referenced to the appropriate secondary testing;
- Plans showing the location of all tests;
- “As-built” plans and sections of the works;
- Copies of the site engineer’s daily records;
- Records of any problems or non-compliances and the solution applied;

- Any other site specific information considered relevant to proving the integrity of the New Cell or Landfill Infrastructure;
- Validation by a qualified person that all of the construction has been carried out in accordance with the Construction Proposals.

“emissions to land” includes emissions to groundwater.

“EP Regulations” means The Environmental Permitting (England and Wales) Regulations 2016, SI 2016 No.1154 and words and expressions used in this permit which are also used in those Regulations have the same meanings as in those Regulations.

“emissions of substances not controlled by emission limits” means emissions of substances to air, water or land from the activities, either from the emission points specified in schedule 3 or from other localised or diffuse sources, which are not controlled by an emission or background concentration limit.

“exceeded” means that a value is above a permitted limit, or where a range of values or a minimum value is set as a permitted limit it means a value outside that range or below the minimum value, whichever is applicable.

‘Hazardous property’ has the meaning in Annex III of the Waste Framework Directive.

“Hazardous substances” as defined by the Environmental Permitting (England and Wales) Regulations 2010, SI 2010 No.675, schedule 22 and listed in our Hydrogeological risk assessment guidance, annex J to our H1 risk assessment guidance.

‘Hazardous waste’ has the meaning given in the Hazardous Waste (England and Wales) Regulations 2005 (as amended).

“Landfill Infrastructure” means any specified element of the:

- permanent capping;
- temporary capping (i.e. engineered temporary caps not cover materials);
- leachate abstraction systems;
- leachate transfer, treatment and storage systems;
- surface water drainage systems;
- leachate monitoring wells;
- groundwater monitoring boreholes;
- landfill gas monitoring boreholes;
- landfill gas management systems;
- lining within the installation.

within the site.

“Liquids” means any liquid other than leachate within the engineered landfill containment system.

“List of Wastes” means the list of wastes established by Commission Decision [2000/532/EC](#) replacing Decision [94/3/EC](#) establishing a list of wastes pursuant to Article 1(a) of Council Directive [75/442/EEC](#) on waste and Council Decision [94/904/EC](#) establishing a list of hazardous waste pursuant to Article 1(4) of Council Directive [91/689/EEC](#) on hazardous waste, as amended from time to time.

“LFTGN 05” means Environment Agency Guidance for monitoring enclosed landfill gas flares.

“LFTGN 07” means Environment Agency Guidance on monitoring landfill gas surface emissions.

“LFTGN 08” means Environment Agency Guidance for monitoring landfill gas engines.

“Groundwater” means all water, which is below the surface of the ground in the saturation zone and in direct contact with the ground or subsoil.



"Inert waste" means waste that does not undergo any significant physical, chemical or biological transformations. Inert waste will not dissolve, burn or otherwise physically or chemically react, biodegrade or adversely affect other matter with which it comes into contact in a way likely to give rise to environmental pollution or harm human health. The total leachability and pollutant content of the waste and the ecotoxicity of the leachate must be insignificant, and in particular not endanger the quality of surface water and/or groundwater.

"Medicinal product" means any medicine licensed by the Medicines and Healthcare products Regulatory Agency (MHRA) or their predecessors under the Medicines Act 1968, section 130.

"MEPP" Monitoring and extraction point plan, required by condition 4.2.2(h) to specify extraction points and routine monitoring locations.

"M2" means Environment Agency Guidance Monitoring of stack emissions to air.

"New Cell" means any new cell, part of a cell or other similar new area of the site where waste deposit is to commence after issue of this permit and can comprise:

- groundwater under-drainage system;
- permanent geophysical leak location system;
- leak detection layer;
- sub-grade;
- barriers;
- liners;
- leachate collection system;
- leachate abstraction system;
- separation bund/layer;
- cell or area surface water drainage system;
- side wall subgrade and containment systems;

for the New Cell.

"MCERTS" means the Environment Agency's Monitoring Certification Scheme.

"No impact" means that the change made to the construction process will not affect the agreed design criteria, specification or performance in a way that has a negative effect.

"Pests" means Birds, Vermin and Insects.

"Previous year" means the 12 month period preceding the month the annual report is submitted in.

"quarter" means a calendar year quarter commencing on 1 January, 1 April, 1 July or 1 October.

"Relevant waste acceptance procedures" means the procedure for the acceptance of waste at landfills and the associated sampling and test methods specified in the Council Decision Annex (2003/33/EC, European Council of 19 December 2002).

"Relevant waste acceptance criteria" means the waste acceptance criteria and the associated sampling and test methods specified in the Council Decision Annex (2003/33/EC, European Council of 19 December 2002).

"Review of the Hydrogeological Risk Assessment" means a written review of the hydrogeological risk assessment included in the Application, together with any other parts of the Application that addressed the requirements of the EP Regulations. The review shall assess whether the activities of disposal or tipping for the purpose of disposal of waste authorised by the permit continue to meet the requirements of the EP Regulations.

'Sustainably extracted' means where suction can be applied to the extraction wells such that a flow rate of landfill gas, with a methane content capable of either being combusted, or treated by bio-oxidation, can be extracted without increasing the risk of air ingress to the waste or inducing aerobic degradation within the waste.

'Waste code' - See 'List of Wastes'.

"WFD" means Directive 2008/98/EC of the European Parliament and of the Council of 19 November 2008 on waste [and repealing certain Directives] – the Waste Framework Directive.

Unless otherwise stated, any references in this permit to concentrations of substances in emissions into air means the standards included in Environment Agency Guidance for Monitoring Enclosed Landfill Gas Flares LFTGN 05 or Guidance for Monitoring Landfill Gas Engine Emissions LFTGN 08.

Where the following terms appear in the waste code list in Tables S2.1 or S2.2 they have the meaning given below:

'hazardous substance' means a substance classified as hazardous as a consequence of fulfilling the criteria laid down in parts 2 to 5 of Annex I to Regulation (EC) No 1272/2008;

'heavy metal' means any compound of antimony, arsenic, cadmium, chromium (VI), copper, lead, mercury, nickel, selenium, tellurium, thallium and tin, as well as these materials in metallic form, as far as these are classified as hazardous substances;

'polychlorinated biphenyls and polychlorinated terphenyls' ('PCBs') means PCBs as defined in Article 2(a) of Council Directive 96/59/EC'.

Article 2(a) says that 'PCBs' means:

- polychlorinated biphenyls
- polychlorinated terphenyls
- monomethyl-tetrachlorodiphenyl methane, Monomethyl-dichloro-diphenyl methane, Monomethyldibromo-diphenyl methane
- any mixture containing any of the above mentioned substances in a total of more than 0,005 % by weight;

'transition metals' means any of the following metals: any compound of scandium, vanadium, manganese, cobalt, copper, yttrium, niobium, hafnium, tungsten, titanium, chromium, iron, nickel, zinc, zirconium, molybdenum and tantalum, as well as these materials in metallic form, as far as these are classified as hazardous substances;


'stabilisation' means processes which change the hazardousness of the constituents in the waste and transform hazardous waste into non-hazardous waste;


'solidification' means processes which only change the physical state of the waste by using additives without changing the chemical properties of the waste;

'partly stabilised wastes' means wastes containing, after the stabilisation process, hazardous constituents which have not been changed completely into non-hazardous constituents and could be released into the environment in the short, middle or long term.



“© Crown Copyright. All rights reserved. Environment Agency, 100024198, 2020.”





END OF PERMIT