

Construction Noise and Vibration Monthly Report – August 2025

North Warwickshire Borough Council

Non-Technical Summary	1
Abbreviations and Descriptions	3
1 Introduction	4
1.2 Measurement Locations	6
2 Summary of Results	8
2.1 Summary of Measured Noise and Vibration Levels	8
2.2 Exceedances of the LOAEL and SOAEL	12
2.3 Exceedances of Trigger Level	14
2.4 Complaints	16
Appendix A Site Locations	17
Appendix B Monitoring Locations	23
Appendix C Data	29

List of tables

Table 1: Table of Abbreviations	3
Table 2: Monitoring Locations	6
Table 3: Summary of Measured dB L_{Aeq} Data over the Monitoring Period	9
Table 4: Summary of Measured PPV Data over the Monitoring Period	12
Table 5: Summary of Exceedances of LOAEL and SOAEL	13
Table 6: Summary of Exceedances of Trigger Levels	15
Table 7: Summary of Complaints	16

Non-Technical Summary

This Noise and Vibration Monitoring Report fulfils HS2 Limited's commitment detailed in the Environmental Minimum Requirements (EMRs), Annex 1, Code of Construction Practice, to present the results of noise and vibration monitoring carried out within North Warwickshire Borough Council (NWBC) area during the month of August 2025.

Within this period noise and vibration monitoring were undertaken at the following worksites:

- Church Lane Embankment worksite (ref.: CLE), where reinforced concrete works, baffle wall construction, ditch maintenance were underway.
- Kingsbury Main Compound worksite (ref.: KMC), where operation of precast yard, batching plant, offices and welfare facilities was underway.
- Marston Box worksite (ref.: MB), where no works were underway.
- Faraday Avenue Embankment and Underbridge worksite (ref.: FAEU), where segment installation works, platform and formwork operations and cabling works were underway.
- Chattle Hill Box Structure worksite (ref.: CHBS), where sheet pile installation and removal, cofferdam excavation, steel fixing, concrete pours, and general site maintenance were underway.
- Attleboro Lane Overbridge (ref.: ALO) and Marsh Lane Embankment (ref.: MLE) worksites, where dig and replace, embankment construction, compound and haul road operation and maintenance, culvert installation, demolition, stockpile management, operation of generators and traffic management were underway
- Gilson Embankment worksite (ref.: GE), where earthworks, material movements and site maintenance were underway.
- Gilson Drive worksite (ref.: GLD), where embankment works, excavation, soil stabilisation and vehicle movements were underway.
- Birmingham Road worksite (ref.: BRD), where decking installation, excavation and vehicle movements were underway.
- Water Orton South Compound (ref.: WOSC), where bridge decking works were underway.

The HS2 threshold levels for significant noise impacts, which are defined in Information Paper E23 (<https://www.gov.uk/government/publications/hs2-information-papers-environment>), were not exceeded due to HS2 works during August 2025.

There were no exceedances of trigger levels as defined in section 61 consents during the reporting period.

Five (5) complaints regarding noise and vibration were received by HS2 during the monitoring period.

Abbreviations and Descriptions

The abbreviations, descriptions and project terminology used within this report can be found in Table 1.

Table 1: Table of Abbreviations

Acronym/Term	Definition
$L_{Aeq,T}$	See equivalent continuous sound pressure level
Ambient sound	A description of the all-encompassing sound at a given location and time which will include sound from many sources near and far. Ambient sound can be quantified in terms of the equivalent continuous sound pressure level, $L_{pAeq,T}$
Decibel(s), or dB	Between the quietest audible sound and the loudest tolerable sound there is a million to one ratio in sound pressure (measured in Pascal (Pa)). Because of this wide range, a level scale called the decibel (dB) scale, based on a logarithmic ratio, is used in sound measurement. Audibility of sound covers a range of approximately 0-140dB.
Decibel(s) A-weighted, or dB(A)	The human ear system does not respond uniformly to sound across the detectable frequency range and consequently instrumentation used to measure sound is weighted to represent the performance of the ear. This is known as the 'A weighting' and is written as 'dB(A)'.
Equivalent continuous sound pressure level, or $L_{Aeq,T}$	An index used internationally for the assessment of environmental sound impacts. It is defined as the notional unchanging level that would, over a given period of time (T), deliver the same sound energy as the actual time-varying sound over the same period. Hence fluctuating sound levels can be described in terms of an equivalent single figure value, typically expressed as a decibel level.
Exclusion of data	Measurement of noise levels can be affected by weather conditions such as prolonged periods of rain, winds speeds higher than 5m/s and snow/ice ground cover. Noise levels measured during these periods are considered not representative of normal noise conditions at the site and, for the purposes of this report, are excluded from the assessment of exceedances and calculation of typical noise levels and are also greyed out in charts. Identifiable incongruous noise and vibration events not attributable to HS2 construction noise are also excluded.
Façade	A facade noise level is the noise level 1m in front of a large reflecting surface. The effect of reflection, is to produce a slightly higher (typically +3 dB) sound level than it would be if the reflecting surface was not there.
Free-field	A free-field noise level is the noise level measured at a location where no reflective surfaces, other than the ground, lies within 3.5 metres of the microphone position.
LOAEL	Lowest Observed Adverse Effect Level - the level above which adverse effects on health and quality of life can be detected.
Peak particle velocity, or PPV	Instantaneous maximum velocity reached by a vibrating element as it oscillates about its rest position. The PPV is a simple indicator of perceptibility and risk of damage to structures due to vibration. It is usually measured in mm/s.
SOAEL	Significant Observed Adverse Effect Level - the level above which significant adverse effects on health and quality of life occur.
Sound pressure level	The parameter by which sound levels are measured in air. It is measured in decibels. The threshold of hearing has been set at 0dB, while the threshold of pain is approximately 120dB. Normal speech is approximately 60dB at a distance of 1 metre and a change of 3dB in a time varying sound signal is commonly regarded as being just detectable. A change of 10dB is subjectively twice, or half, as loud.
Vibration dose value, or VDV	An index used to evaluate human exposure to vibration in buildings. While the PPV provides information regarding the magnitude of single vibration events, the VDV provides a measure of the total vibration experienced over a specified period of time (typically 16h daytime and 8h night-time). It takes into account the magnitude, the number and the duration of vibration events and can be used to quantify exposure to continuous, impulsive, occasional and intermittent vibration. The vibration dose value is measured in $m/s^{1.75}$.

1 Introduction

- 1.1.1 HS2 is required to undertake noise (and vibration) monitoring as necessary to comply with the requirements of the High Speed Rail (London-West Midlands) Environmental Minimum Requirements, including specifically Annex 1: Code of Construction Practice, in addition to any monitoring requirements arising from conditions imposed through consents under Section 61 of the Control of Pollution Act, 1974 or through Undertakings & Assurances given to third parties. Such monitoring may be undertaken for the following purposes:
- monitoring the impact of construction works;
 - to investigate complaints, incidents and exceedance of trigger levels; or
 - monitoring the effectiveness of noise and vibration control measures.
- 1.1.2 Monitoring data and interpretive reports are to be provided to each relevant local authority on a monthly basis and shall include a summary of the construction activities occurring, the data recorded over the monitoring period, any complaints received, any periods in exceedance of agreed trigger levels, the results of any investigations and any actions taken or mitigation measures implemented. This report provides noise data, and interpretation thereof, for monitoring carried out by HS2 within the North Warwickshire Borough Council (NWBC) area for the period 1st to 31st of August 2025.
- 1.1.3 Construction sites in the local authority area where monitoring was undertaken during this period include:
- Church Lane Embankment worksite, ref.: CLE (see Plan 1 in Appendix A), where work activities included:
 - Reinforced concrete works.
 - Baffle wall construction.
 - Ditch maintenance.
 - Kingsbury Main Compound worksite, ref.: KMC (see Plan 2 in Appendix A), where works activities included:
 - Operation of precast yard.
 - Operation of batching plant.
 - Operation of offices and welfare facilities.
 - Marston Box/Marston Lane worksite, ref.: MB (see Plan 2 in Appendix A), where no works were underway.

- Faraday Avenue Embankment and Underbridge worksite, ref.: FAEU (see Plan 3 in Appendix A), where works activities included:
 - Segment installation works, including delivery, lifting, gluing, installation and tensioning, and adjustments including hydraulic jacking.
 - Platform and formwork installation, including grouting.
 - Cable and mast activities including, stay cable tensioning, mast movements, and threading and tensioning operations.
- Chattle Hill Box Structure worksite, ref.: CHBS (see Plan 4 in Appendix A), where work activities included:
 - Sheet pile installation and removal.
 - Cofferdam excavation.
 - Steel fixing.
 - Concrete pours, including blinding and pile caps.
 - General site maintenance.
- Attleboro Lane Overbridge, ref.: ALO and Marsh Lane Embankment, ref: MLE worksites (See Plan 4 in Appendix A), where work activities included:
 - Dig and replace.
 - Embankment construction.
 - Compound and haul road operation and maintenance.
 - Culvert installation.
 - Demolition.
 - Stockpile management.
 - Operation of generators.
 - Operation of borrow pit.
 - Traffic management.
- Gilson Embankment worksite, ref.: GE (see Plan 4 in Appendix A), where works activities included:
 - Earthworks.
 - Material movements.
 - Site maintenance.

- Gilson Drive worksite, ref.: GLD (see Plan 4 in Appendix A), works activities included:
 - Embankment works.
 - Excavation.
 - Soil stabilisation.
 - Vehicle movements.
- Birmingham Road worksite, ref.: BRD (see Plan 4 in Appendix A), work activities included:
 - Decking installation.
 - Excavation.
 - Vehicle movements.
- Water Orton Sound Compound, ref.: WOSC (see Plan 4 in Appendix A), work activities included:
 - Bridge decking works.

1.1.4 The applicable standards, guidance, and monitoring methodology is outlined in the construction noise and vibration monitoring methodology report which can be found at the following location <https://www.gov.uk/government/collections/monitoring-the-environmental-effects-of-hs2>. Noise and vibration monitoring reports for previous months can also be found at this location.

1.2 Measurement Locations

- 1.2.1 Fourteen (14) noise monitoring installations and seven (7) vibration monitoring installations were active in August in the NWBC area. Table 2 summarises the location of noise and vibration monitoring installations within the NWBC area in August 2025.
- 1.2.2 An additional noise monitor, ref.: WOSC-N3, was installed south of 53 Watton Lane, worksite WOSC, on the 7th of August.
- 1.2.3 Maps showing the position of noise and vibration monitoring installations are presented in Appendix B.

Table 2: Monitoring Locations

Worksite Reference	Measurement Reference	Address
CLE	CLE-N1	Highfields Cottage, Middleton, North Warwickshire

Worksite Reference	Measurement Reference	Address
KMC	KMC-N1	Wheatley House, Kingsbury Road, Curdworth CP, Marston, Warwick
MB	MB-N1	Elford House, Kingsbury Road, Curdworth, Sutton Coldfield
	MB-V1	Elford House, Kingsbury Road, Curdworth, Sutton Coldfield
FAEU	FAEU-N1	South of Orchard Cottage, Newlands Lane, Curdworth, Warwickshire
	FAEU-V1	South of Orchard Cottage, Newlands Lane, Curdworth, Warwickshire
CHBS	CHBS-N1	6 Gorsey Way, Coleshill, Warwickshire, Birmingham
WOSC	WOSC-N3	(south of) 53 Watton Lane, Water Orton
MLE	MLE-N1	Rostrevor, Vicarage Lane, Water Orton CP, North Warwickshire
ALO	ALO-N1	West of 47 Attleboro Lane, Water Orton, Birmingham
	ALO-N2	(south of) 57 Attleboro Lane, Water Orton, Birmingham
	ALO-V1	West of 47 Attleboro Lane, Water Orton, Birmingham
	ALO-V5	(south of) 57 Attleboro Lane, Water Orton, Birmingham
	AFE-N1	Attleboro Farm, Attleboro Lane, Water Orton, Birmingham
	AFE-V1	Attleboro Farm, Attleboro Lane, Water Orton, Birmingham
GE	GE-N2	Lovegrove Cottage, Gilson Road, Warwickshire
GLD	GLD-N1	10 Gilson Dr, Coleshill, Birmingham
	GLD-V1	10 Gilson Dr, Coleshill, Birmingham
BRD	BRD-N2	1 New Cottages, Birmingham Road, Coleshill, Birmingham
	BRD-N3	1 New Cottages, Birmingham Road, Coleshill, Birmingham
	BRD-V1	1 New Cottages, Birmingham Road, Coleshill, Birmingham

2 Summary of Results

2.1 Summary of Measured Noise and Vibration Levels

- 2.1.1 Table 3 presents a summary of the measured noise levels at each monitoring location over the reporting period. The $L_{Aeq,T}$ is presented for each of the relevant time periods averaged over the calendar month, along with the highest single period $L_{Aeq,T}$ that was found to occur within the month.

Table 3: Summary of Measured dB L_{Aeq} Data over the Monitoring Period

Worksite Reference	Measurement Reference	Site Address	Free-Field or Façade Measurement	Weekday Average L _{Aeq,T} (Highest Day L _{Aeq,T})					Saturday Average L _{Aeq,T} (Highest Day L _{Aeq,T})					Sunday / Public Holiday Average L _{Aeq,T} (Highest Day L _{Aeq,T})	
				0700 - 0800	0800 - 1800	1800 - 1900	1900 - 2200	2200 - 0700	0700 - 0800	0800 - 1300	1300 - 1400	1400 - 2200	2200 - 0700	0700 - 2200	2200 - 0700
CLE	CLE-N1	Highfields Cottage, Middleton	Free-field	48.3 (64.5)	46.3 (49.4)	44.7 (48.2)	42.4 (48.8)	42.6 (56.1)	46.8 (53.2)	48.1 (53.1)	47.2 (50.7)	46.5 (55.9)	43.2 (53.5)	46.3 (54.4)	42.2 (50.0)
KMC	KMC-N1	Kingsbury Road, Curdworth	Free-field	54.6 (59.5)	58.8 (62.8)	54.4 (59.4)	53.3 (59.0)	50.9 (58.6)	52.4 (55.6)	56.7 (58.5)	58.1 (59.0)	53.8 (61.8)	48.5 (54.2)	55.3 (63.7)	49.5 (57.0)
MB	MB-N1	Elford House, Kingsbury Road, Curdworth	Free-field	55.8 (59.2)	56.1 (64.1)	55.7 (59.6)	55.2 (59.5)	52.7 (59.2)	54.2 (57.5)	54.6 (56.8)	54.3 (56.7)	54.3 (58.1)	50.9 (55.6)	53.3 (58.6)	51.0 (57.8)
FAEU	FAEU-N1	(South of) Orchard Cottage, Newlands Lane, Curdworth	Free-field	54.7 (58.4)	55.5 (60.6)	54.6 (59.0)	53.8 (57.4)	51.9 (58.2)	52.3 (55.9)	52.7 (56.3)	53.4 (58.0)	54.0 (60.9)	49.4 (55.3)	51.8 (61.1)	50.7 (56.0)
CHBS	CHBS-N1	6 Gorsey Way, Coleshill	Free-field	61.4 (62.7)	61.5 (62.6)	60.7 (64.4)	58.7 (63.8)	57.1 (62.7)	56.7 (57.9)	60.5 (61.9)	60.4 (61.1)	59.6 (66.5)	53.1 (57.3)	59.9 (64.9)	54.9 (64.9)

Worksite Reference	Measurement Reference	Site Address	Free-Field or Façade Measurement	Weekday Average $L_{Aeq,T}$ (Highest Day $L_{Aeq,T}$)					Saturday Average $L_{Aeq,T}$ (Highest Day $L_{Aeq,T}$)					Sunday / Public Holiday Average $L_{Aeq,T}$ (Highest Day $L_{Aeq,T}$)	
				0700 - 0800	0800 - 1800	1800 - 1900	1900 - 2200	2200 - 0700	0700 - 0800	0800 - 1300	1300 - 1400	1400 - 2200	2200 - 0700	0700 - 2200	2200 - 0700
WOSC	WOSC-N3	(south of) 53 Watton Lane, Water Orton	Free field	62.1 (65.5)	63.1 (65.7)	61.5 (66.1)	59.8 (62.5)	57.7 (64.9)	58.6 (60.4)	60.5 (62.4)	61.0 (63.9)	61.3 (66.3)	54.5 (58.1)	59.6 (62.9)	57.3 (63.6)
MLE	MLE-N1	Rostrevor, Vicarage Lane, Water Orton	Free field	54.0 (59.1)	55.4 (59.8)	54.3 (58.0)	51.9 (55.7)	50.0 (58.3)	52.3 (54.4)	52.5 (56.7)	53.0 (59.1)	52.1 (58.3)	49.2 (54.7)	51.7 (57.7)	50.4 (56.0)
ALO	ALO-N1	West of 47 Attleboro Lane, Water Orton	Free field	55.5 (59.9)	55.9 (61.6)	54.4 (59.5)	53.3 (60.1)	51.5 (60.1)	53.6 (57.4)	54.3 (59.3)	53.9 (59.7)	53.1 (60.5)	51.1 (59.1)	53.7 (61.4)	52.0 (59.6)
	ALO-N2	(South of) 57 Attleboro Lane, Water Orton	Free field	56.0 (60.4)	58.4 (62.7)	55.7 (60.2)	53.7 (60.2)	51.6 (60.5)	54.0 (57.4)	57.0 (61.9)	53.9 (59.8)	53.4 (60.4)	51.0 (59.6)	54.0 (61.5)	51.7 (59.4)
	AFE-N1	Attleboro Farm, Attleboro Lane	Free field	61.1 (64.9)	62.6 (65.6)	60.9 (64.4)	59.8 (64.4)	57.5 (65.0)	59.0 (61.2)	59.9 (63.7)	60.2 (64.9)	60.1 (65.2)	56.8 (63.6)	59.9 (65.9)	57.8 (64.4)
GE	GE-N2	Lovegrove Cottage, Gilson Road	Free-field	58.4 (61.9)	59.9 (68.5)	58.6 (61.6)	57.1 (61.0)	55.0 (61.5)	54.9 (57.2)	56.7 (60.0)	57.3 (60.3)	56.5 (60.7)	52.3 (58.6)	56.3 (61.0)	53.6 (60.2)

Worksite Reference	Measurement Reference	Site Address	Free-Field or Façade Measurement	Weekday Average $L_{Aeq,T}$ (Highest Day $L_{Aeq,T}$)					Saturday Average $L_{Aeq,T}$ (Highest Day $L_{Aeq,T}$)					Sunday / Public Holiday Average $L_{Aeq,T}$ (Highest Day $L_{Aeq,T}$)	
				0700 - 0800	0800 - 1800	1800 - 1900	1900 - 2200	2200 - 0700	0700 - 0800	0800 - 1300	1300 - 1400	1400 - 2200	2200 - 0700	0700 - 2200	2200 - 0700
GLD	GLD-N1	10 Gilson Dr, Coleshill	Free-field	58.1 (61.4)	58.2 (60.8)	57.3 (59.3)	51.8 (54.8)	51.0 (58.6)	58.3 (67.1)	55.0 (56.3)	56.3 (57.5)	54.2 (59.0)	49.1 (53.6)	53.0 (61.6)	51.7 (57.1)
BRD	BRD-N2	1 New Cottages, Birmingham Road, Coleshill	Free-field	60.5 (63.1)	62.5 (64.3)	58.6 (60.9)	57.1 (59.5)	55.7 (61.7)	56.1 (57.0)	58.3 (63.2)	58.0 (65.5)	56.6 (62.6)	53.3 (56.9)	57.0 (60.9)	56.0 (61.0)
	BRD-N3		Free-field	64.5 (68.0)	65.2 (67.1)	62.5 (66.8)	59.9 (65.0)	58.2 (66.6)	59.9 (62.0)	64.9 (67.2)	60.4 (64.8)	58.8 (66.7)	54.4 (62.2)	58.3 (65.1)	57.4 (64.7)

- 2.1.2 Table 4 presents a summary of the measured vibration levels at each monitoring location over the reporting period. The highest PPV measured during the monitoring along any axis is presented in the table.

Table 4: Summary of Measured PPV Data over the Monitoring Period

Worksite Reference	Measurement Reference	Monitor Address	Highest PPV measured in any axis, mm/s
MB	MB-V1	Kingsbury Road, Curdworth, Sutton Coldfield, West Midland	1.27 (Z-axis)
FAEU	FAEU-V1	(south of) Orchard Cottage, Newlands Lane, Curdworth, Warwickshire	0.36 (X-axis)
ALO	ALO-V1	West of 47 Attleboro Lane, Water Orton	0.77 (X-axis)
	ALO-V5	(south of) 57 Attleboro Lane, Water Orton	0.87 (Z-axis)
	AFE-V1	Attleboro Farm, Attleboro Lane, Water Orton	1.31 (X-axis)
GLD	GLD-V1	10 Gilson Dr, Coleshill	1.04 (Z-axis)
BRD	BRD-V1	1, New Cottages, Birmingham Road, Coleshill	3.61 (Z-axis)

- 2.1.3 Appendix C presents graphs of the noise and vibration monitoring data over the month for each of the measurement locations. Noise data presented consists of the hourly L_{Aeq} values and, where relevant, the $L_{Aeq,T}$ values (where the time period T has been taken to be the averaging period as specified in Table 1 of HS2 Information Paper E23). Vibration data presented consist of hourly PPV values. The full data set for the monitoring equipment can be found at the following location:

<https://data.gov.uk/dataset/24542ae7-dd44-444f-b259-871c4cc43b5e/environmental-monitoring-data>.

2.2 Exceedances of the LOAEL and SOAEL

- 2.2.1 The lowest observed adverse effect level (LOAEL) is defined in the Planning Practice Guidance – Noise (PPG) as the level above which "noise starts to cause small changes in behaviour and/or attitude, e.g. turning up volume of television; speaking more loudly; where there is no alternative ventilation, having to close windows for some of the time because of the noise. Potential for some reported sleep disturbance. Affects the acoustic character of the area such that there is a perceived change in the quality of life".
- 2.2.2 The significant observed adverse effect level (SOAEL) is defined in the 'Planning Practice Guidance – Noise' as the level above which "noise causes a material change in behaviour and/or attitude, e.g. avoiding certain activities during periods of intrusion; where there is no alternative ventilation, having to keep windows closed

most of the time because of the noise. Potential for sleep disturbance resulting in difficulty in getting to sleep, premature awakening and difficulty in getting back to sleep. Quality of life diminished due to change in acoustic character of the area."

- 2.2.3 HS2 Phase One Information Paper E23: Control of Construction Noise and Vibration sets out the LOAELs and SOAELs for construction noise.
- 2.2.4 Where reported construction noise levels exceed the LOAEL and SOAEL, relevant periods will be identified. Summary statistics to evaluate ongoing qualification for noise insulation and temporary rehousing are also presented where relevant.
- 2.2.5 Table 5 presents a summary of recorded exceedances of the LOAEL and SOAEL at each measurement location over the reporting period, including the number of exceedances during each time period.

Table 5: Summary of Exceedances of LOAEL and SOAEL

Worksite Reference	Measurement Reference	Site Address	Day (Weekday, Saturday, Sunday, Night)	Time period	Number of exceedances of LOAEL	Number of exceedances of SOAEL
CLE	CLE-N1*	Highfields Cottage, Middleton	All days	All periods	No exceedances	No exceedances
KMC	KMC-N1*	Kingsbury Road, Sutton Coldfield	All days	All periods	No exceedances	No exceedances
MB	MB-N1*	Elford House, Kingsbury Road, Curdworth	All days	All periods	No exceedances	No exceedances
FAEU	FAEU-N1*	South of Orchard Cottage, Newlands Lane, Curdworth	All days	All periods	No exceedances	No exceedances
CHBS	CHBS-N1*	6 Gorsey Way, Coleshill	All days	All periods	No exceedances	No exceedances
WOSC	WOSC-N3*	(south of) 53 Watton Lane, Water Orton, B46 1PB	All days	All periods	No exceedances	No exceedances
MLE	MLE-N1	Rostrevor, Vicarage Lane, Water Orton CP	All days	All periods	No exceedances	No exceedances
ALO	ALO-N1	West of 47 Attleboro Lane, Water Orton	All days	All periods	No exceedances	No exceedances

Worksite Reference	Measurement Reference	Site Address	Day (Weekday, Saturday, Sunday, Night)	Time period	Number of exceedances of LOAEL	Number of exceedances of SOAEL
	ALO-N2	(south of) 57 Attleboro Lane, Water Orton, Birmingham, B46 1SD	All days	All periods	No exceedances	No exceedances
	AFE-N1	Attleboro Farm, Attleboro Lane, Water Orton, Birmingham, B46 1SD	All days	All periods	No exceedances	No exceedances
GE	GE-N2	Lovegrove Cottage, Gilson Road	All days	All periods	No exceedances	No exceedances
GLD	GLD-N1	10 Gilson Dr, Coleshill	All days	All periods	No exceedances	No exceedances
BRD	BRD-N2	1 New Cottages, Birmingham Road, Coleshill	All days	All periods	No exceedances	No exceedances
	BRD-N3*	1 New Cottages, Birmingham Road, Coleshill	All days	All periods	No exceedances	No exceedances

*A distance correction has been applied when calculating exceedances of the LOAEL and SOAEL.

** The LOAEL has not been assessed due to high baseline levels.

2.2.6 No exceedances of the LOAEL were recorded due to HS2 construction works during August 2025.

2.2.7 No exceedances of the SOAEL were recorded due to HS2 construction works during August 2025.

2.3 Exceedances of Trigger Level

2.3.1 Table 6 provides a summary of exceedances of the Section 61 trigger noise levels determined to be due to HS2 related construction noise measured during the reporting period, along with the findings of any investigation.

Table 6: Summary of Exceedances of Trigger Levels

Complaint Reference Number (if applicable)	Worksite Reference	Date and Time Period	Identified Source	Results of Investigation (including noise monitoring results)	Actions Taken
-	-	-	-	-	-


2.4 Complaints


2.4.1 Table 7 provides a summary of complaint information related to noise and vibration received during the reporting period, along with the findings of any investigation.

Table 7: Summary of Complaints

Complaint Reference Number	Worksite Reference	Description of Complaint	Results of Investigation	Actions Taken
HS2-25-46609-C	ALO	Complaint due to vibration felt within resident property.	Investigation identified that vibration was related to the transportation of materials to the site via the haul road. No exceedances of threshold levels were recorded during this period.	Resident has been informed of the results of the investigation.
HS2-25-46621-C	ALO/WOSC	Complaint due to vibration felt within resident property.	Works took place during consented hours. Best practice and mitigation were in place during all works. No exceedances of threshold levels were recorded during this period.	Resident has been informed of the results of the investigation.
HS2-25-46632-C	ALO/WOSC	Complaint due to construction noise in the early morning.	Due to extended summer working hours works start from 7:00 and continue until 19:00; all works took place during consented hours. No exceedances of threshold levels were recorded during this period.	Resident has been informed of the results of the investigation.
HS2-25-46641-C	ALO	Complaint due to low frequency noise heard within resident property.	Investigation identified that noise was related to repair works taking place on plant equipment. No exceedances of threshold levels were recorded during this period and all residents have previously been informed of the works taking place..	Resident has been informed of the results of the investigation.
HS2-25-46666-C	ALO	Complaint due to pulsing vibration felt within resident property.	Complaint under investigation at time of publishing.	Complaint under investigation at time of publishing.


Appendix A Site Locations







HS2 Worksite Identification Plan - 2

HS2 Worksite Identification Plan - 2




OFFICIAL








Appendix B Monitoring Locations
















Appendix C Data

Noise

The following graphs show the hourly measured ambient noise level $L_{Aeq,1h}$ and, where relevant, the averaged noise level $L_{Aeq,T}$ values, where the time period T is as specified in Table 1 of HS2 Information Paper E23. Periods with adversely weather affected noise levels are greyed out and have been excluded from the calculation of the $L_{Aeq,T}$ values in Table 3 of the main report.:




Worksite: CLE – Monitoring Ref: CLE-N1







OFFICIAL


Worksite: KMC – Monitoring Ref: KMC-N1







OFFICIAL





Worksite: MB – Monitoring Ref: MB-N1













Worksite: FAEU – Monitoring Ref: FAEU-N1








Worksite: CHBS – Monitoring Ref: CHBS-N1



OFFICIAL






Worksite: WOSC – Monitoring Ref: WOSC-N3








Note: Monitor was installed at 09:00 on Thursday 7th August.

OFFICIAL







Worksite: MLE – Monitoring Ref: MLE-N1








Worksite: ALO – Monitoring Ref: ALO-N1













Worksite: ALO – Monitoring Ref: ALO-N2





OFFICIAL







Worksite: ALO – Monitoring Ref: AFE-N1








Worksite: GE – Monitoring Ref: GE-N2













Worksite: GLD - Monitoring Ref: GLD-N1








Worksite: BRD - Monitoring Ref: BRD-N2




OFFICIAL





Worksite: BRD - Monitoring Ref: BRD-N3




Note: Missing data between 01:00 and 10:00 on Sunday 3rd August was due to a clock synchronisation issue at the monitoring station.



Note: Missing data between 01:00 and 11:00 on Sunday 10th August was due to a clock synchronisation issue at the monitoring station.










Vibration




The following graphs show the hourly measured peak particle velocity PPV recorded during the monitoring period. The graphs show the highest PPV of the three orthogonal axes x, y and z. Where high values of PPV were caused by local interference with the vibration monitor, which are not representative of HS2 construction works, these values have been greyed out in the following charts and have been excluded to calculate values in Table 4 of the main report.

Worksite: MB – Monitoring Ref: MB-V1








Worksite: FAEU – Monitoring Ref: FAEU-V1







OFFICIAL





Worksite: ALO – Monitoring Ref: ALO-V1













Worksite: ALO – Monitoring Ref: ALO-V5







Worksite: ALO – Monitoring Ref: AFE-V1







Note: Missing data throughout the week was due to a loss of power to the monitoring station caused by vegetation preventing sufficient light reach the solar panel.

OFFICIAL




Worksite: GLD – Monitoring Ref: GLD-V1








OFFICIAL




Worksite: BRD – Monitoring Ref: BRD-V1






Note: Missing data between 06:00 on Saturday 16th and 15:00 on Thursday 21st August was due to suspected cable issues at the monitoring station.



Note: Missing data between 06:00 on Saturday 16th and 15:00 on Thursday 21st August was due to suspected cable issues at the monitoring station.



OFFICIAL