INDICATIVE SHRUB PLANTING PALETTE

Species	Height/ spread cm	Pot size (Litres)	Habit	Min no. of breaks
Aucuba japonica Variegata	30-40	3L	Bushy	7
Bergenia cordifolia Purpurea	15-20	3L	-	-
Cotoneaster conspicuus Decorus	30-40	3L	Bushy	3
Cornus sericea 'Kelseyi'	40-60	3L	Branched	4
Cotoneaster 'Coral Beauty'	30-40	2L	Spreading	3
Carex oshimensis Evergold	20-30	2L	-	-
Cotoneaster 'Skogholm'	30-40	3L	Spreading	3
Cistus Silver Pink	30-40	3L	Bushy	4
Cornus sanguinea 'Midwinter Fire'	40-60	3L	Branched	3
Choisya ternata	30-40	3L	Bushy	7
Elaeagnus x ebbingei	60-80	3L	Bushy	3
Euonymus Emerald 'n' Gold	20-30	3L	Bushy	7
Euonymus Emerald Gaiety	20-30	3L	Bushy	7
Geranium 'Johnsons Blue'	20-30	2L	-	-
Hebe albicans Red Edge	20-30	3L	Bushy	5
Hebe rakaiensis	20-30	3L	Bushy	5
Hypericum Hidcote	30-40	3L	Bushy	5
Hebe 'Mrs Winder'	20-30	3L	Bushy	7
Heuchera 'Sugar Frosting'	20-30	2L	-	-
Lavandula Hidcote	20-30	3L	Bushy	5
Lonicera Bagessens Gold	30-40	3L	Bushy	3
Lonicera 'Maygreen'	30-40	2L	Bushy	3
Mahonia Appollo	30-40	3L	Bushy	3
Olearia haastii	30-40	3L	Bushy	2
Osmanthus burkwoodii	30-40	3L	Bushy	5
Potentilla Abbotswood	30-40	3L	Bushy	4
Potentilla Elizabeth	30-40	4L	Bushy	6
Potentilla Red Ace	30-40	3L	Bushy	4
Prunus Otto Luyken	30-40	3L	Bushy	3
Photoinia x Fraseri 'Red Robin'	40-60	3L	Branched	6
Rosa 'Kent'	30-40	3L	Bushy	4
Rosa 'Hertfordshire'	30-40	3L	Bushy	3
Rosa 'Suffolk'	30-40	3L	Bushy	4
Spiraea Anthony Waterer	30-40	3L	Branched	5
Symphoricarpos Hancock	40-60	3L	Branched	2
Sarcoccoa hookeriana	30-40	3L	Bushy	3
Sarcoccoa hummilis	30-40	3L	Bushy	3
Stachys lanata 'Silver Carpet'	30-40	3L	Bushy	3
Skimmia 'Kew White'	30-40	3L	Bushy	3
Senecio Sunshine	30-40	3L	Bushy	4
Vinca Minor	15-20	2L	-	-
Viburnum davidii	30-40	3L	Bushy	3
Viburnum tinus 'Eve Price'	30-40	3L	Bushy	7

TREE PLANTING

Species	Form	Girth cm	Height cm	Root condition
Acer campestre	EHS	14-16	425-600	65/85 L
Alnus glutinosa	EHS	14-16	425-600	65/85 L
Amelanchier lamarckii	EHS	14-16	425-600	65/85 L
Betula pendula	EHS	14-16	425-600	65/85 L
Carpinus betulus 'Frans Fontaine'	EHS	14-16	425-600	65/85 L
Malus domestica	EHS	14-16	425-600	65/85 L
Prunus avium	EHS	14-16	425-600	65/85 L
Prunus Padus	EHS	14-16	425-600	65/85 L
Prunus 'Rancho'	EHS	14-16	425-600	65/85 L
Prunus 'Sunset Boulevard'	EHS	14-16	425-600	65/85 L
Sorbus 'Golden Wonder'	EHS	14-16	425-600	65/85 L
Quercus robur	EHS	14-16	425-600	65/85 L
Tilia cordata Greenspire	EHS	14-16	425-600	65/85 L
Sorbus aucuparia	EHS	14-16	425-600	65/85 L
Sorbus commixta 'Embley'	EHS	14-16	425-600	65/85 L

NATIVE WOODLAND TRANSPLANTS @ 2.0m cts in drifts of up to 7

Species	Root Condition	Age + Times Transpl	Height cm
Acer campestre (10%)	Bagged	2x	150-175
Alnus glutinosa (10%)	Bagged	2x	150-175
Betula pendula (10%)	Bagged	1+1	100-125
Crataegus monogyna (10%)	Bagged	1+1	40-60
Corylus avellana (10%)	Bagged	1+1	40-60
Ilex aquifolium (10%)	3L	-	40-60
Prunus avium (10%)	Bagged	2x	150-175
Malus sylvestris (10%)	Bagged	1+2	100-125
Quercus robur (10%)	Bagged	1u1	100-125
Salix caprea (10%)	Bagged	1+1	40-60

SINGLE SPECIES HEDGE PLANTING

Species	Height/ spread cm	Pot size (Litres)	Habit	Min no. of breaks	No. / m2
Carpinus betulus (hedge)	60-80	2L	Feathered	4	5/lin m
Fagus sylvatica (hedge)	60-80	2L	Feathered	4	5/lin m

NATIVE STRUCTURE MIX @ 1M CTRS

Species	Root Condition	Age + Times Transpl	Height cm
Acer campestre (10%)	Bagged	1+1	40-60
Crataegus monogyna (20%)	Bagged	1+1	40-60
Corylus avellana (10%)	Bagged	1+1	40-60
Cornus sanguineum (10%)	Bagged	1+1	40-60
Euonymus europaeus (10%)	Bagged	1+1	40-60
Ligustrum vulgare (10%)	Bagged	1+1	40-60
Prunus spinosa (10%)	Bagged	1+1	40-60
Viburnum lantana (10%)	Bagged	1+1	40-60
Viburnum opulus (10%)	Bagged	1+1	40-60

POND EDGE AND AQUATIC MARGINALS
(Planted randomly – up to 0.5m above and 0.3m below settled water level)

Species	Root condition	No. / m2
Potentilla palustris	P9/0.5lt	3
Alisma plantago-aquatica	P9/0.5lt	3
Mentha aquatica	P9/0.5lt	3
Veronica beccabunga	P9/0.5lt	3
Lythrum salicaria	P9/0.5lt	3
Potamogeton pectinatus	P9/0.5lt	3
Potamogeton crispus	P9/0.5lt	3
Ceratophyllum demersum	P9/0.5lt	3
Myriophyllum spicatum	P9/0.5lt	3
Persicaria amphibium	P9/0.5lt	3
Sagittaria sagittifolia	P9/0.5lt	3

Emorsgate EG8 Meadow Mixture for Wet Soils sown at 5gms/m2

Grasses

%	Latin name	Common name
12.5	Agrostis capillaris	Common Bent
3.75	Alopecurus pratensis	Meadow Foxtail (w)
3.75	Anthoxanthum odoratum	Sweet Vernal-grass (w)
3.75	Briza media	Quaking Grass (w)
32.5	Cynosurus cristatus	Crested Dogstail
2.5	Deschampsia cespitosa	Tufted Hair-grass (w)
35	Festuca rubra	Red Fescue
6.25	Schedonorus pratensis (Festuca pratensis)	Meadow Fescue
100		



KEY

Soft Landscaping

- Existing Trees Retained - Existing ground flora also retained in line with RPAs and BS: 5837
- Proposed Tree Planting
- Proposed Single Species Native Hedge Planting
- Proposed Mixed Native Scrub Planting
- Proposed Mixed Native Woodland Planting
- Proposed Shrub Planting
- Proposed Lawn Grass
- Existing Grassland
- Proposed Grassland - EG8 Meadow Mix for Wet Soils

Hard Landscaping

- Access - Tarmac
- Proposed Parking/Drives/Shared Surface - Block Paving, 240mm x 160m x 50mm
- Proposed Paving - 450mm x 450mm paving slabs
- Proposed 1.8m High Close Board Fencing
- Proposed 1.8m High Brick Wall

N

0 100m

Note: The original of this drawing was produced in colour - a monochrome copy should not be relied upon.

Revision	Description	Date
-	First issue	6/6/26

LANDARB SOLUTIONS

Project:
The land north of Old Quarry House, Fenway, Steeple Aston

Description:
Landscape Strategy

Status:
For Planning

Scale:	Drawn I Checked	Date:
1:500 @A0	**DP MP**	**06/06/2026**

Job Number:	Drawing Number:	Revision:
LAS 995	**01**	**-**